LOT 287 SOUTH WESTERN HIGHWAY, GWINDINUP SAND AND GRAVEL PIT **DEVELOPMENT APPROVAL AND EXTRACTIVE INDUSTRY LICENCE APPLICATION**

PREPARED FOR:


MARIO MICHELE GIACCI

MARCH 2024

PREPARED BY:

Martinick Bosch Sell Pty Ltd 4 Cook Street West Perth WA 6005 Ph: (08) 9226 3166 Email: info@mbsenvironmental.com.au Web: www.mbsenvironmental.com.au





environmental and geoscience consultants

LOT 287 SOUTH WESTERN HIGHWAY, GWINDINUP DA AND EIL APPLICATION

Distribution List:

Company	Company Contact name		Date
MGM Bulk	Craig Carbone Sales/Business Development	Electronic	11 March 2024

Document Control for Job Number: MGM287EXT

Document Status Prepared By		Authorised By	Date
Draft Report	Sharon Rose, Alyse Lupardo	Kirsi Kauhanen	7 March 2024
Final Report	Sharon Rose	Kirsi Kauhanen	11 March 2024

Disclaimer, Confidentiality and Copyright Statement

This report is copyright. Ownership of the copyright remains with Martinick Bosch Sell Pty Ltd (MBS Environmental) and Mario Michele Giacci.

This report has been prepared for **Mario Michele Giacci** on the basis of instructions and information provided by **Mario Michele Giacci** and, therefore, may be subject to qualifications which are not expressed.

No other person other than those authorised in the distribution list may use or rely on this report without confirmation in writing from MBS Environmental and **Mario Michele Giacci**. MBS Environmental has no liability to any other person who acts or relies upon any information contained in this report without confirmation.

This report has been checked and released for transmittal to Mario Michele Giacci.

These Technical Reports:

- Enjoy copyright protection and the copyright vests in Martinick Bosch Sell Pty Ltd (MBS Environmental) and Mario Michele Giacci unless otherwise agreed in writing.
- May not be reproduced or transmitted in any form or by any means whatsoever to any person without the written permission of the Copyright holder.



EXECUTIVE SUMMARY

Mario Michele Giacci is applying for a Development Approval (DA) and Extractive Industry License (EIL) for the extraction of sand and gravel on Lot 287 (Plan 100056) on South Western Highway in Gwindinup. The applicant, who is also the landowner, currently holds a DA and EIL for an active extraction site on the property, but these approvals are due to expire in September 2024. The new DA and EIL applications propose a 15.31 ha extension to the current EIL area, a change in maximum final batter slopes from 1:10 (vertical:horizontal) to 1:6, an addition of half-day operations on Saturdays, and to introduce a maximum number of trucks per day.

The application covers a total area of 32.58 ha, which will include the currently approved pit (17.27 ha) that is undergoing rehabilitation and a proposed expansion area to the east (15.31 ha). DA/EIL was first granted for the property in 2013, with subsequent five year DA/EILs granted in 2018 and 2019. The proposed expansion area is expected to extend the life of the pit by approximately 10 years.

Access to the pit will remain off Lowrie Road, which connects to South Western Highway. The number of truck movements per day will vary depending on market demand for the resource; however, it is estimated that during large hauling campaigns the number of trucks could potentially reach a maximum of 75 return trips per day. In between contracts, quiet periods with no truck movements are expected. A traffic assessment was conducted in August 2023 for the extraction operations on neighbouring Lot 393 (also owned by Mario Michele Giacci), which also applies to traffic from Lot 287 due to the combined nature of the operations. The assessment determined that the existing roads and associated intersections are suitable for accommodating the proposed vehicle movements.

The proposed 15.31 ha expansion area will involve the clearing of 9.70 ha of native vegetation, which will require a Clearing Permit from the Department of Water and Environmental Regulation (DWER). The remainder of the proposed expansion area is already cleared or contains blue gum plantation that will be harvested prior to extraction. Following the staged extraction, it is proposed that rehabilitation will return a mixture of native vegetation (3.14 ha) and pasture (29.45 ha) to the extraction area. Further to this, 15.57 ha of harvested blue gums will be rehabilitated to native vegetation, which means that in total 18.71 ha of native vegetation is proposed to be established on the property as part of the proposed works. Further 9.31 ha of existing remnant native vegetation on Lot 287 is proposed to be retained and improved (e.g. via weed control and infill plantings). It is noted that the proposed vegetation clearing and rehabilitation areas may be modified as part of the Clearing Permit application process through DWER.

The post-excavation landform is designed with maximum batter slopes of 1:6, though the majority of the pit floor will be closer to 1:10. Maximum excavation depth will be 5 m from the natural ground surface. The pit floor level will remain at least 2 m above maximum groundwater levels.

The closest residence is located approximately 155 m to the north of the proposed expansion area. A noise assessment has been undertaken for the proposed operations and the proponent will implement the recommended management measures to reduce noise emissions and achieve compliance with the relevant regulations. A Dust Management Plan has also been prepared to minimise impacts on surrounding residences. Additional management plans are in place for weeds and dieback, stormwater, and rehabilitation.

The proponent has operated numerous extractive industries (formerly as Giacci Brothers Pty Ltd and currently as MGM Bulk) and is very experienced in the basic raw material industry. The pit on Lot 287 is securely fenced and signed, and will continue to operate in a safe and efficient manner.

Overall, it is expected that the proposed extraction operations can be managed in a way that avoids and minimises adverse environmental and social impacts and delivers a net positive outcome for the environment through facilitating the conversion of blue gum plantation to native vegetation.



TABLE OF CONTENTS

1.	Introduction	
2.	BACKGROUND INFORMATION	2
2.1 2.3 2.4 2.5 2.6 2.7 2.8 2.9 2.10 2.11	LOCATION, AREA, AND OWNERSHIP OF PROPERTY LAND USE AND ZONING SOILS AND TOPOGRAPHY. GROUNDWATER SURFACE WATER VEGETATION AND FAUNA DIEBACK CROWN LAND AND RESERVES HERITAGE EXISTING PUBLIC UTILITIES AND SERVICES	
3.	PLANNING AND POLICY SETTING	
3.1 3.2 3.3 3.4 3.5 3.6 3.7 3.8 3.9 3.10	STATE PLANNING STRATEGY (2050) GREATER BUNBURY REGION SCHEME GREATER BUNBURY STRATEGY (2013) SHIRE OF CAPEL LOCAL PLANNING STRATEGY SHIRE OF CAPEL LOCAL PLANNING SCHEME NO. 8. SHIRE OF CAPEL EXTRACTIVE INDUSTRIES LOCAL LAW 2016 SHIRE OF CAPEL LOCAL PLANNING POLICY 6.2. STATE PLANNING POLICY 2.4 - PLANNING FOR BASIC RAW MATERIALS STATE PLANNING POLICY 3.7 - PLANNING IN BUSHFIRE PRONE AREAS. SEPARATION DISTANCES BETWEEN INDUSTRIAL AND SENSITIVE LAND USES	
4.	DEVELOPMENT PROPOSAL	16
4.1 4.2 4.3 4.4 4.5 4.6 4.7 4.8 4.9 4.10 4.11 4.12 4.13 4.14	SUMMARY OF WORKS EXTRACTION AREA AND SETBACKS NATURE AND DURATION OF PROPOSED EXCAVATION STAGES AND TIMING CLEARING METHODOLOGY TOPSOIL AND OVERBURDEN EXCAVATION METHODS DEPTH AND EXTENT OF EXCAVATION ACCESS TO SITE NUMBER AND SIZE OF TRUCKS OPERATING HOURS PROPOSED INFRASTRUCTURE PUBLIC DANGER SURVEY INFORMATION	
5.	ENVIRONMENTAL MANAGEMENT	
5.1 5.2 5.3 5.4 5.5 5.6 5.7 5.8 5.9	BIODIVERSITY DRAINAGE NOISE DUST HYDROCARBONS AND CHEMICALS WEEDS DIEBACK ABORIGINAL HERITAGE SCREENING OF VISUAL IMPACTS	



24252627

5.10	REHABILITATION AND DECOMMISSIONING	
6.	OTHER APPROVALS	
7.	CONCLUSION	
8.	References	
	TABLES	
Table 1:	Zoning and Land Use of Properties Adjacent to Lot 287	3
Table 2:	Groundwater Levels on Lot 287	7
Table 3:	Groundwater Levels on Lot 393	8
Table 4:	LPS No.8 Special Control Areas on Lot 287	12
	Figures	
Figure 1:	Location Plan	4
Figure 2:	Land Use	5
Figure 3:	Existing Contours and Features	6
Figure 4:	Sensitive Receptors	15
Figure 5:	Works and Excavation Plan	20
Figure 6:	Finished Development Plan	21
	APPENDICES	
	AFFLINDICLS	

Appendix 1	 Certificate 	of Title

Appendix 2: Flora and Vegetation Survey

Appendix 3: Fauna Survey

Appendix 4: Heritage Search

Appendix 5: Noise Assessment

Appendix 6: Traffic Impact Statement

Appendix 7: Survey Verification

Appendix 8: Stormwater Management Plan

Appendix 9: Dust Management Plan

Appendix 10: Weed and Dieback Management Plan

Appendix 11: Rehabilitation and Decommissioning Programme

Appendix 12: Existing Contour and Feature Plan (A1)

Appendix 13: Finished Development Plan (A1)



1. Introduction

Mario Michele Giacci (the applicant), owner of Lot 287 (Plan 100056) (the property) on South Western Highway in Gwindinup, is applying for a Development Approval (DA) and Extractive Industry Licence (EIL) for the expansion of sand and gravel extraction operations on the property. An initial DA and EIL were granted for the property in 2013, with subsequent DAs and EILs granted in 2018 and 2019. The approvals for the current extraction area are due to expire in September 2024.

This 2024 DA and EIL application incorporates the following changes compared to the previously approved DA/EIL:

- Extension of the EIL area in an easterly direction for an additional 15.31 ha.
- Increase in the maximum final batter slopes from 1:10 (vertical:horizontal) to 1:6 to align with the batters approved for adjacent Lot 393.
- Setting the maximum number of truck movements to 75 trips per day (150 one-way trips).
- Addition of half days operations on Saturdays from 7 am to 1 pm.

This report provides supporting information for the DA and EIL applications submitted to the Shire of Capel (the Shire). This report describes the project site and surrounds, the planning context, works completed to date, and works proposed to be undertaken. Further, potential environmental and social impacts of the project and their management are addressed.



2. Background Information

2.1 Location, Area, and Ownership of Property

Lot 287 is located on South Western Highway approximately 3.5 km south of Boyanup, as shown in Figure 1. The property covers total area of 60.01 ha (Figure 2) and is owned by the applicant (Certificate of Title is provided as Appendix 1). Access to the site is gained off Lowrie Road via an easement on adjacent Lot 393, which is also owned by the applicant.

2.2 DETAILS OF APPLICANT

The applicant – Mario Michele Giacci (PO Box 1263, Bunbury WA 6231) – is the landowner of Lot 287. The applicant has extensive experience in the extractive industry through previous directorship of Giacci Brothers Pty Ltd and current directorship of MGM Bulk. This has included several EILs within the Shire, including the current EILs for Lot 287 and adjacent Lot 393 (Plan 159607). MGM Bulk operates out of Picton and maintains a sizable fleet of machinery and trucks.

2.3 LAND USE AND ZONING

Lot 287 is zoned 'Rural' under the Shire's Local Planning Scheme (LPS) No.8 and intercepts three Special Control Areas (SCA) (Figure 2):

- SCA4 Transport Corridors.
- SCA6 Strategic Minerals and Basic Raw Materials.
- SCA8 Regional Ecological Linkages.

SCA6 is associated with mineral sand deposit further to the west and Lot 287 intersects the buffer zone to the deposit. SCA8 is associated with axis lines of ecological linkages running along the Preston River and the Whicher Scarp. Lot 287 is not on the axis line but in close vicinity to it.

SCA4 is associated with the South Western Highway and covers approximately 40 m wide strip along the eastern property boundary. SCA4 is well outside the extraction area. The eastern edge of Lot 287 is also reserved for 'Transport Corridors' (Shire of Capel 2023c) (Figure 2). A 'Highway Protection Line' straddles the property along its eastern highway road frontage and delineates an area (100 m distance from either side of the centre line of the road), which is defined as the 'Highway Protection Area'. The purpose of the 'Highway Protection Area' is to protect the function, amenity, and visual character of the Highway. The proposed extraction area is well outside the 'Highway Protection Area'.

Lot 287 contains no buildings. In addition to the current extraction area, Lot 287 contains blue gum (*Eucalyptus globulus*) plantation with pockets of remnant native vegetation (Figure 3). Blue gums within the currently approved extraction area have been harvested with the remainder of the application area to be harvested prior to extraction commencing.

The land surrounding Lot 287 is zoned either 'Rural', 'State Forest', 'Regional Open Space', or 'Primary Regional Road' (Figure 2). Lot 287 has a Mineral Sands Caveat (in favour of Cristal Mining Limited) to protect mineral sand mining rights on the property. Extensive mineral sands mining has been undertaken to the west of Lot 287. The mining operations are now complete with some rehabilitation activities remaining.


Zoning and land use of adjacent properties are further described in Table 1 and shown in Figure 2.





Table 1: Zoning and Land Use of Properties Adjacent to Lot 287

Property	Zoning	Landuse
Lot 393 (Plan 159607)	Rural	Active sand and gravel extraction, one shed.
Lot 107 (Plan 232802)	Rural	Covered in remnant native vegetation. No residences.
Lot 478 (Plan 34760)	State Forest	Reserve 18237 - for the purpose of Landscape Protection. Contains remnant native vegetation. No residences.
Lot 477 (Plan 34756)	State Forest	Reserve 2307 - for the purpose of Landscape Protection. Contains remnant native vegetation. No residences.
Lot 31 (Plan 214856)	Regional Open Space	Reserve 25500 - for the purpose of Landscape Remnant native vegetation. No residences.
Lot 26 (Plan 143766)	Rural	Remnant native vegetation. Dwelling, outbuildings, and a dam. Dwelling located 157 m from proposed extraction area boundary.
Lot 100 (Plan 44666)	Rural	Some remnant native vegetation. Dwelling and outbuildings. Dwelling located 272m from the proposed extraction area boundary.
Lot 6 (Plan 130054)	Rural	Some remnant native vegetation.
Lot 7 (Plan 130054)	Rural	Some remnant native vegetation. Dwelling and outbuildings. Dwelling located 362 m from the proposed extraction area boundary.
Lot 8 (Plan 130054)	Rural	Some remnant native vegetation. Outbuildings attached to dwelling on Lot 9 (Plan 130054).
Lot 9 (Plan 130054)	Rural	Some remnant native vegetation. Dwelling and outbuildings. Dwelling located 310 m from the proposed extraction area boundary.









2.4 SOILS AND TOPOGRAPHY

The highest point on Lot 287 is situated approximately halfway along the southern boundary and has an elevation of 111 m Australian Height Datum (AHD) (Figure 3). From this point, the land to the west and north slopes and undulates downward at gradients between approximately 1:10 and 1:20. Near the northern boundary there are steep areas of approximately a 1:6 slope. To the east of the proposed extraction area lies the steepest gradients on the property, which slope towards the South Western Highway at gradients up to 1:6 within the proposed extraction area and 1:4 further east, beyond the proposed extraction area. Natural landform within the proposed extraction area on Lot 287 ranges from 109 m AHD in the south to 67 mAHD in the northwest.

A grid of test holes was dug on the site in May 2011 to estimate material depths. A layer of sand (0.3 to 1.5 m thick) was found to overlay gravel. Subsequent extraction has confirmed this and found that the gravel layer is typically 1 to 1.5 m thick (thicker in some areas) and overlies clay.

Three soil and landform mapping systems are present within and surrounding the proposed extraction area (DPIRD 2022, DPIRD-064):

- Whicher Scarp System: Low scarp and raised platform, on the northern edge of the Donnybrook Sunkland. Sandy gravel and pale deep sands, loamy gravel and non-saline wet soils. Jarrah-marri forest and woodland.
- Goodwood Valleys System: Valleys of the Donnybrook Sunkland. Sandy gravel, loamy gravel, and deep sands. Jarrah-marri forest and woodland.
- Blackwood Plateau System: Lateritic plateau in the Donnybrook Sunkland. Sandy gravel, loamy gravel, and deep sand. Jarrah-marri forest.

Lot 287 is located away from wetlands and waterways on well-draining soils, making the risk of acid sulfate soil (ASS) low.

2.5 GROUNDWATER

Two piezometers were installed on Lot 287 in September 2012, and their locations are shown in Figure 3. Readings taken on 20 September 2012 are shown in Table 2. The results show that groundwater is approximately 7.8 m from the surface. Groundwater level data is also available from two piezometers on adjacent Lot 393 from October-December 2016 (Table 3). This data supports the results from Lot 287 and further also indicates that depth to groundwater increases as moving up the hill. The extractive operations on the site since 2013 have not intersected the groundwater table.

The lowest point of excavation on Lot 287 is the stormwater retention pond (at 65 mAHD) in the northwestern part of the property (Figure 6). This pond will remain approximately 2 m above maximum groundwater levels. Landform in the rest of the extraction area will be higher than the pond and depth to maximum groundwater will be more than 2 m.

Table 2: Groundwater Levels on Lot 287

Piezometer	Ground Level (AHD)	Groundwater Depth from Natural Ground Level	Groundwater Level (AHD)	Sampling Date
А	68.20 m	7.85 m	60.35 m	20 Sep 2012
В	70.90 m	7.84 m	63.06 m	20 Sep 2012



Piezometer	Ground Level (AHD)	Groundwater Depth from Natural Ground Level	Groundwater Level (AHD)	Sampling Date
	94.30 m	More than 8.8 m as bore dry	Bore dry at 85.50 m	18 Oct 2016
1 (southeast)		More than 8.8 m as bore dry	Bore dry at 85.50 m	2 Nov 2016
		More than 8.8 m as bore dry	Bore dry at 85.50 m	14 Dec 2016
2 (northwest)	45.80 m	5.25 m	40.55 m	18 Oct 2016
		5.35 m	40.45 m	2 Nov 2016
		5.74 m	40.06 m	14 Dec 2016

Table 3: Groundwater Levels on Lot 393

2.6 SURFACE WATER

The extraction area is mostly situated at the eastern edge of the catchment of Gynudup Brook, a tributary of the Capel River, which discharges into the Indian Ocean at Geographe Bay. A small area (approximately 2.3 ha) at the eastern limit of the extraction area is within the Preston River catchment and drains east toward the Preston River, approximately 800 m away.

There are no watercourses on Lot 287 due to the well-draining soil and lack of upstream catchment area. Surface flow is only likely to occur during intense or prolonged rainfall events. Any surface flow leaving the extraction areas of Lot 287 does so across the western boundary into Lot 393 Lowrie Road, with the exception of the 2.3 ha in the Preston River catchment. Lot 393 is also owned by the applicant and is being used for extraction of gravel and sand in conjunction with operations on Lot 287 under a separate EIL. Management of stormwater runoff for these two sites has been combined and is described further in Section 5.2.

The location of the proposed extraction area is compliant with the advice of *Water Quality Protection Note no. 15* (DWER 2019). It is not within a proclaimed Public Drinking Water Supply Area, land subject to seasonal flooding or defined floodplain and is well separated from all waterways, the nearest being Gynudup Brook approximately 1 km west of the extraction area, and Preston River 0.8 km to the east.

2.7 VEGETATION AND FAUNA

Lot 287 has approximately 19 ha of native vegetation, split into several patches. A reconnaissance flora and vegetation survey conducted by Daniel Marsh Botanical Consulting in 2019 (Appendix 2) identified three native vegetation types and an introduced vegetation type in the proposed extraction area:

- VT1: Tall woodland of *Eucalyptus marginata* and *Corymbia calophylla* over low woodland of *Banksia grandis* over tall sparse shrubland of *Kunzea glabrescens* over low sparse shrubland of *Xanthorrhoea preissii*.
- VT2: Tall woodland of *Eucalyptus marginata* and *Corymbia calophylla* over tall sparse shrubland of *Kunzea glabrescens* over low sparse shrubland of *Xanthorrhoea preissii* and *Xanthorrhoea gracilis*.
- VT3: Tall woodland of *Eucalyptus marginata* and *Corymbia calophylla* over low sparse shrubland of *Xanthorrhoea preissii* and *Hibbertia hypericoides*.
- D: Disturbed: Blue gum plantations, tracks, and clearings.

The native vegetation communities vary in condition from Degraded to Very Good - Good (using condition scale by Keighery 1994) and show signs of multiple historical disturbances including selective logging, fire, weeds, and



Phytophthora cinnamomi (dieback). Currently there is disturbance in the form of cleared tracks and bare areas. The blue gum plantation areas have been completely cleared of native vegetation in the past.

No Threatened or Priority Ecological Communities or Threatened or Priority flora species have been recorded at Lot 287. Several weed species have been recorded but no Declared Pest species or weeds of national significance (Marsh 2019).

In 2019, Greg Harewood was engaged to conduct a Fauna Assessment for Lot 287 (Appendix 3). The Forest Redtailed Black Cockatoo (*Calyptorhynchus banksii naso*), Baudin's Cockatoo (*Calyptorhynchus baudinii*), and Western Ringtail Possum (*Pseudocheirus occidentalis*) were recorded within the proposed clearing area. A Black Cockatoo habitat tree assessment identified 405 trees with diameter at breast height (DBH) > 50 cm, of which 26 contained hollows potentially large enough for black cockatoo nesting. This assessment was based on approximate size of hollow entrance only, no conclusive evidence of use by black cockatoos was recorded. Within the proposed extraction area there are 215 trees with DBH > 50 cm proposed to be cleared, including 12 with hollows potentially large enough for black cockatoo nesting. None of these hollows showed signs of occupancy or chew marks. The impact of this clearing and associated mitigation and offset measures will be addressed as part of the Clearing Permit application process through the Department of Water and Environmental Regulation (DWER).

2.8 DIEBACK

Dieback assessment of Lot 287 was undertaken by Bark Environmental in 2020 (the report is provided as an appendix to Appendix 10). Approximately 15 ha of the native vegetation on Lot 287 was found to be infested with *Phytophthora cinnamomi* (dieback) with just under 1 ha surveyed as uninfested. The remainder of the native vegetation, the blue gum plantation areas and cleared areas were mapped as 'excluded' due to the lack of indicator species to determine the occurrence of dieback; however, the presence of dieback in these areas cannot be ruled out. The areas of bushland surrounding Lot 287 are considered dieback infested with moderate confidence based on publicly available dieback mapping (Project Dieback 2024). Dieback management as part of the proposed extraction works is further addressed in Section 5.7.

2.9 Crown Land and Reserves

There are three reserves in close vicinity to the application area as shown in Figure 2:

- Reserve 2307 (Lot 477) "Landscape Protection" (to the northeast).
- Reserve 25500 (Lot 31) "Landscape Protection" (to the northeast).
- Reserve 18237 (Lot 478) "Landscape Protection" (to the east).

2.10 HERITAGE

There are no registered Aboriginal Heritage Sites or Other Heritage Places within the application area or immediate surrounds (DPLH 2024) (Appendix 4). Lot 287 is close to the Preston River, which is a registered site of 'Mythological' type, but the river is approximately 800 m east of the extraction area and is buffered by the South Western Highway and rural property, therefore, the proposed operations will have no impact on this site. The property falls within the South West Native Title Settlement Area; however, this does not preclude development from taking place on this privately owned property.

2.11 EXISTING PUBLIC UTILITIES AND SERVICES

No utilities (water, power, or telecommunications) traverse Lot 287 (Figure 3). Existing extractive operations access the site from Lowrie Road in the north via an easement across Lot 393 and this access will be maintained for the duration of the proposed operations on Lot 287.



3. PLANNING AND POLICY SETTING

3.1 STATE PLANNING STRATEGY (2050)

The strategy identifies the Greater Bunbury Area as 'Regional Urban Area'. This includes the subject land and identifies the need for further strategic and structure planning in the area. Since the time of this strategy, a number of more detailed studies have been undertaken, including the majority of the policies and plans described throughout Section 3.

The State Planning Strategy identifies the Greater Bunbury Area progressing towards becoming a continuous urban area with the Perth and Peel regions. It highlights the importance of mining growth in the region, noting that: "*Mining and downstream processing continues to be a key economic driver for the South West sector*" (WA Gov 2021). The strategy identifies six key principles to guide land use planning and development, of which the following relate to the proposal:

- Economy: Facilitate trade, investment, innovation, employment, and community betterment.
- Environment: Conserve the State's natural assets through sustainable development.
- Regional Development: Build the competitive and collaborative advantages of the region.

3.2 Greater Bunbury Region Scheme

The majority of Lot 287, including the proposed extraction area is zoned 'Rural' under the Greater Bunbury Region Scheme (GBRS) 2014. The purpose of the 'Rural' zone is:

"for the sustainable use of land for agricultural purposes, to assist in the conservation and the wise use of natural resources including water, flora, fauna and minerals. These areas can also provide a distinctive rural landscape unique to the region and accommodate carefully planned rural living developments."

The proposal is consistent with this purpose of the rural zoning as the use of the natural resources on the property is proposed to be balanced with rehabilitation to a mixture of pasture and native vegetation that will maintain the rural landscape and environmental values in the long term.

Under the GBRS *Strategic Minerals and Basic Raw Materials Resource Policy* (DPLH 2018), the extraction area in the western portion of Lot 287 is located within a buffer area for Titanium-Zircon mineralisation. Minerals are protected on site via an existing Caveat in favour of Cristal Mining Limited. Extractive operations on Lot 287 have to date not encountered mineral strata. In the unlikely event that minerals are encountered, work will be stopped to ensure protection of this resource and contact will be made with the relevant authority. On this basis, the proposal is consistent with the strategic resource area as it will enable the extraction of basic raw materials while ensuring appropriate measures are in place to protect mineral deposits should they be encountered.

The eastern portion of Lot 287 is partly reserved 'Primary Regional Roads'. The proposed extractive operations do not intersect this zoning.

3.3 Greater Bunbury Strategy (2013)

The Greater Bunbury Strategy (DPLH 2013) is the primary strategic document and Structure Plan prepared by the Department of Planning – now Department of Planning, Lands and Heritage (DPLH) – to guide urban, industrial, and regional land use within the City of Bunbury and Shires of Capel, Dardanup, and Harvey. The subject site is located within the area classified as "Residual of study area: rural (no change to land use)". Under the strategy:

"Rural land is to be retained for primary production, natural resource management and its landscape characteristics that define the rural character of the Greater Bunbury sub-region."



The strategy outlines challenges for sustainable Greater Bunbury, which specifically include the lack of suitable fill for new greenfield developments with drainage issues. The Department of Planning response to this challenge was to identify and safeguard the resources required for extractive industries, future fill requirements and construction. The proposal is consistent with the intent of the strategy as it makes use of the basic raw material available in the region while retaining the rural landscape values of the property in the long term through rehabilitation to pasture and native vegetation.

3.4 Shire of Capel Local Planning Strategy

The Shire's Local Planning Strategy (LPS) (Shire of Capel 2023b) is a vision for the development and long-term planning within the Council boundary over the next 15 years and was endorsed in June 2023. It is a two-part strategy, with part 1 focused on overall vision including strategies and actions and part 2 addressing background, relevant policies and the justification for the LPS. The LPS has replaced the Shire's Land Use Strategy 1999.

The LPS Part 1 sets strategies under six key Future Directions: community, environment, economy, leadership, infrastructure, and communication. Whilst all of the six have some relevance to the proposal, the most relevant is the environment as it covers natural resources (Shire of Capel 2023b):

Environment: natural resources – such as soil, water, rivers, wetlands, coastline, minerals, basic raw materials, and biodiversity are managed in a sustainable way that does not degrade the environment or reduce the quality of life within the Shire.

The proposal is consistent with the intent of the environmental and other strategies and actions as it will enable the use of increasingly rare basic raw materials in accordance with the GBRS and Basic Raw Materials Policy while ensuring that the end landform and landscape outcomes are benefiting the 'Rural' values and improved environmental outcomes. In particular:

- The property has been mostly cleared in the past and the required clearing of 9.30 ha of native vegetation can be mitigated and offset by revegetation and improvement works on the property.
- As part of the proposal, 18.71 ha of native revegetation will be undertaken (3.14 ha within extraction area and 15.57 ha outside extraction area), resulting in net gain in native vegetation on the property and improvement in ecological connectivity in the local area. Further 9.31 ha of existing native vegetation will be retained and improved through weed control and infill plantings.
- After extraction, 29.45 ha will be returned to pasture. This will support local rural and agricultural pursuits.
- To minimise the impact of extraction activities on sensitive receptors (Figure 4), plans to manage dust, noise, stormwater, weeds, and dieback have been developed (see Section 5).
- This site provides local employment opportunities within the Shire.
- Resources from this site are being used in local and regional developments, which provides further local employment opportunities, and reduces transport costs.

3.5 Shire of Capel Local Planning Scheme No. 8

The LPS No.8 came into effect in July 2023 (Shire of Capel 2023c). Under LPS No.8, Lot 287 is zoned as 'Rural', the objectives of which are:

- To provide for the maintenance or enhancement of specific local rural character.
- To protect extensive agricultural activities such as cropping and grazing and intensive uses such as horticulture as primary uses, with other rural pursuits and rural industries as secondary uses in circumstances where they demonstrate compatibility with the primary use.
- To maintain and enhance the environmental qualities of the landscape, vegetation, soils and water bodies, in order to protect sensitive areas especially the natural valley and watercourse systems from drainage.



- To provide for the operation and development of existing, future and potential rural land uses by limiting the introduction of sensitive land uses in the Rural zone.
- To provide for a range of non-rural land uses where they have demonstrated benefit and are compatible with surrounding rural uses.

Extractive industry on rural zoned land is subject to a development approval from the Shire. Once extraction of sand and gravel is completed, the final landform will consist of 29.45 ha of pasture, which aligns with preserving the local rural character of the area and will provide for a range of potential future rural uses (Figure 6). Additionally, 18.71 ha of native vegetation is proposed to be established and 9.31 ha of existing native vegetation to be retained and improved across the property (Figure 6). A range of plans to manage dust, noise, stormwater, weeds, dieback and rehabilitation have been developed (see Section 5) to avoid, minimise, mitigate and offset potential impacts.

Lot 287 also falls within three SCAs, as detailed in Table 4.

Table 4: LPS No.8 Special Control Areas on Lot 287

SCA	Purpose	Within Extraction Area
SCA 4	Transport Corridors: To protect the function and safety of the key travel routes within the Scheme area, along with the amenity and visual character of adjacent land and to ensure that the requirements of State Planning Policy 5.4 – Road and Rail Noise (SPP 5.4) are satisfied by all proposed development and land use.	No
SCA 6	Strategic Minerals and Basic Raw Materials: To identify areas where basic raw materials and strategic mineral resources need to be protected from incompatible land uses in line with the Greater Bunbury Region Scheme Strategic Minerals and Basic Raw Materials Resource Policy 2018.	Yes
SCA 8	Regional Ecological Linkages: To identify significant ecosystems on the Scheme Map as a Special Control Area and to provide measures to ensure that land use and development within its boundaries are regulated and managed to protect significant ecological linkages, foreshore environments, biodiversity, and environmental quality.	Yes

The proposed EIL is aligned with the purpose of SCA6 as it is a compatible land use in line with the Greater Bunbury Region Scheme, see in Section 3.2 for more detail. The proposal also aligns with SCA 8 as there are no priority or threatened ecological communities, or priority or threatened flora species present and whilst significant fauna habitat is present (Section 2.7), the impacts can be mitigated and offset so that the proposal will result in net gain in native vegetation on the property (from current 19.02 ha to 28.03 ha after extraction), improving connectivity through the local area.

3.6 Shire of Capel Extractive Industries Local Law 2016

This DA/EIL application has been prepared in accordance with the Shire's *Extractive Industry Local Law* (Shire of Capel 2016).

3.7 Shire of Capel Local Planning Policy 6.2

Local Planning Policy 6.2 Extractive Industries (LPP6.2) was implemented by the Shire in 2023 with the objective to sustainably manage extractive industries and regional supply needs without causing disruption to the amenity, environment, or function of transport networks within the Shire, as follows:

• Ensure extractive industries do not adversely affect the environment or the amenity of the locality during or after extraction.



- Ensure extractive industries are in the most appropriate locations.
- Ensure volumes of extraction occurs where the available haulage routes and road hierarchy are satisfactory
 or can be upgraded to support an extractive industry without affecting the safety of road users and the
 sustainability of the transport network.
- Achieve a high level of staged rehabilitation to native vegetation where required or where clearing of remnant native vegetation is proposed and approved.
- Achieve a high level of groundwater resource protection.
- Clearly outline matters required to be addressed by proponents.
- To provide clarity of the development assessment process for proponents and the broader community.
- Inform the community and stakeholders of the importance of a rigorous assessment process and the reasoning for the Shire's policy stance.

The LPP6.2 applies to all extractive industry proposals for properties zoned 'Rural' under the LPS No.8, which includes Lot 287. The proposal and associated supporting documentation is consistent with the purpose of LPP6.2 as it is within an appropriate location with available haulage routes, addresses potential amenity issues to nearby residences, addresses stormwater management for the operations, proposes a high level of staged rehabilitation to native vegetation and pasture, will increase local ecological connectivity after extraction, will support future rural use, and will not impact on groundwater resources. Further detail on the proposed operations and their management is provided in Section 4 and Section 5.

3.8 STATE PLANNING POLICY 2.4 - PLANNING FOR BASIC RAW MATERIALS

State Planning Policy 2.4 - Planning for Basic Raw Materials (2021a) (SPP2.4) was prepared under the *Planning and Development Act 2005*. The intent of SPP2.4 is to ensure basic raw materials (BRM) and extractive industries matters are considered during planning and development decision-making, to facilitate the responsible extraction and use of the State's BRM resources. The objectives of this policy are to:

- Ensure BRM and its regional importance is considered at the earliest stages of the planning process.
- Protect BRM in SGS areas and ES by avoiding encroachment from incompatible land uses.
- Ensure BRM resources are used efficiently in land use planning and development.
- Identify BRM extraction opportunities through sequential land use without compromising the final intended land use.
- Ensure the extraction of BRM avoids, minimises, or mitigates any adverse impacts on the community, water resources, and biodiversity values.

The proposed extractive operations are in line with the objectives of SPP2.4 as follows:

- The proposed operations facilitate sequential land uses without compromising planned post-extraction landuse (rural) or other potential future landuses.
- The proposed extension to the previously approved operations ensures that the sand/gravel resource available on the property is used efficiently.
- Potential adverse impacts on community (nearby residences) have been considered and addressed through appropriate management measures (see Section 5).
- The potential biodiversity impacts of the expansion area will be mitigated and offset by retaining and improving 9.31 ha of native vegetation and by establishing 18.71 ha of native vegetation as part of the



operations, achieving a net gain in the amount of native vegetation on the property from pre to post development.

SSP2.4 is associated with a guideline document *State Planning Policy 2.4 - Planning for Basic Raw Materials Guidelines* (DPLH 2021b). Section 4 of this guideline lists a number of factors that should be considered in the assessment of proposals to establish, extend, or expand an extractive industry operation, as well as managing the potential impacts of the operation. Information to address these factors has been included in this supporting document to the DA and EIL application.

3.9 STATE PLANNING POLICY 3.7 - PLANNING IN BUSHFIRE PRONE AREAS


State Planning Policy 3.7 - Planning in Bushfire Prone Areas (2015) (SPP3.7) directs how land use should address bushfire risk management in Western Australia. It applies to all land that has been designated as bushfire prone by the Department of Fire and Emergency Services. While parts of Lot 287 are designated as bushfire prone, the proposed extraction operation does not involve intensification of land-use and does not increase the threat of bushfire. Therefore, exemptions from the requirements of SPP3.7 are expected to apply (similarly to previous applications).

3.10 SEPARATION DISTANCES BETWEEN INDUSTRIAL AND SENSITIVE LAND USES

Guidance for the Assessment of Environmental Factors No.3: Separation Distances between Industrial and Sensitive Land Uses, was prepared by Environmental Protection Authority in 2005. It sets generic separation distances for various types of industrial operations and sensitive land uses. For 'Extractive Industry - Sand and Limestone', the main potential impacts are identified as noise and dust and the generic separation distance to sensitive land uses is set at 300-500 m depending on the size of the operations.

The proposed sand extraction operations are at least 300 m from sensitive landuses apart from two residences that are 155 m and 250 m from the proposed EIL boundary (Figure 4). A site specific noise assessment has been undertaken (Appendix 5) that found that the proposed operations can achieve compliance with the noise regulations as long as specific management measures are put in place (further detail in Section 5.3). A range of dust management measures are also proposed to be implemented (as per Section 5.4). Therefore, based on site specific technical analysis and proposed management measures, the separation distances between the proposed operations and sensitive land uses are considered sufficient.





4. DEVELOPMENT PROPOSAL

4.1 SUMMARY OF WORKS

In summary, the extraction operations will proceed in stages and comprise the following:

- Harvest blue gums and clear native vegetation.
- Remove and stockpile topsoil, litter, and any overburden.
- Extract sand and gravel material in stages (in accordance with the Works and Excavation Plan, shown in Figure 5).
- Crush and screen gravel with a mobile crusher.
- Load trucks and transport sand and gravel off site.
- Form final landform in accordance with the Finished Development Plan (Figure 6).
- Rip pit floor, respread topsoil and other overburden, and rehabilitate.

Further information on the proposed operations is provided below.

4.2 EXTRACTION AREA AND SETBACKS

The current application area (32.58 ha) is larger than the previously approved extraction area (17.27 ha) with a 15.31 ha extension of the pit to the east. The proposed extension area is a mix of remnant native vegetation and blue gum plantation. Native vegetation clearing is proposed to be limited to 9.70 ha.

Setbacks from property boundaries are as follows (Figure 3):

- Western boundary: no setback from Lot 393 as previously approved (to connect the two adjacent pits).
- Northern boundary: 40 m to 100 m setback.
- Southern boundary: 40 m setback that was previously approved for the existing pit, has been applied to the extension as well.
- Eastern boundary: Minimum 250 m setback.

4.3 Nature and Duration of Proposed Excavation

Insitu resource volumes within the proposed extraction area are estimated at approximately 445,000 m³ of sand and gravel. Assuming an extraction rate of 50,000 m³ per year, the pit has potential resource for approximately 10 years; however, the rate of extraction is subject to market forces. In recent years, the amount of sand and gravel removed from site has varied from more than 100,000 m³ per annum to less than 20,000 m³ annum.

4.4 STAGES AND TIMING

Extraction has concluded and rehabilitation activities are underway in the previously approved Stages 1 through 11. For the proposed extension, the operations will proceed gradually from Stage 12 to Stage 21 (up to 2 ha each), commencing in the southwest corner of the proposed extension area (Figure 5). Depending on market demand for product, the life of the pit may extend past the licence period of five years and, if so, a renewal application will be made in the future. Once a stage is completed it will be rehabilitated in accordance with the Rehabilitation and Decommissioning Programme (see Section 5.10).



4.5 CLEARING METHODOLOGY

The stages will be pegged and flagged to demarcate the extent of clearing and excavation. The blue gums within the extraction area will be harvested ahead of other works. Proposed native vegetation clearing is limited to 9.70 ha and will be subject to any conditions DWER will set on a Clearing Permit (yet to be determined). Vegetation will be cleared with a bulldozer or similar. Some of the cleared vegetation will be mulched and used in the native rehabilitation areas. Some logs and larger branches may also be salvaged and relocated to buffer zones along boundaries or into native vegetation rehabilitation areas to add to habitat formation.

4.6 TOPSOIL AND OVERBURDEN

Thickness of topsoil is expected to be approximately 100-150 mm with minimal other overburden. Topsoil will be removed with a bulldozer and stockpiled in windrows to a maximum height of 4 m for later use in rehabilitation. Any overburden will be similarly stockpiled. Whenever possible, stripped topsoil will be directly transferred into native revegetation areas and spread across finalised land surfaces to avoid stockpiling, thus maximising seed and microbial benefits. All movement and stockpiling of topsoil and overburden will be conducted in accordance with dieback requirements (Section 5.7). Topsoil from native vegetation areas will be stockpiled separately from topsoil from blue gum plantation areas.

4.7 EXCAVATION METHODS

Sand and gravel extraction will mostly proceed from southwest to northeast (Figure 5). The crushing and screening of gravel rock (by way of a mobile rotary impact crusher and/or jaw crusher) will be undertaken on the floor of the previously approved extraction area, more than 500 m from the closest residence to maximise noise amelioration. Where necessary, a noise bund will be constructed (Section 5.3). Face batters will be maintained at no steeper than 1:2 and no higher than 4 m. Material will be stockpiled as required prior to loading onto trucks (by loader). Final batters (maximum 1:6 slopes) and pit floor (approximately 1:10 slope) will be formed with a bulldozer and/or loader in accordance with the Finished Development Plan (Figure 6) prior to revegetation (see Section 5.10).

4.8 DEPTH AND EXTENT OF EXCAVATION

The extent of excavation is detailed on the Works and Excavation Plan (Figure 5) and the Finished Development Plan (Figure 6). Natural landform within the proposed extraction area ranges from 109 m AHD in the south to 67 mAHD in the northwest, whereas the proposed final landform ranges from 109 mAHD in the south to 65 mAHD in the northwest. Maximum depth of excavation will be up to 5 m below the natural ground surface level to cater for areas of deeper gravel.

The lowest point of excavation is the stormwater retention pond (at 65 mAHD) in the northwestern part of the property (Figure 6). This pond will remain approximately 2 m above maximum groundwater levels. Landform in the rest of the extraction area will be higher than the pond and depth to maximum groundwater will be more than 2 m.

The proposed maximum final batter slope has been changed from previously approved 1:10 to 1:6 to maximise the utilisation of the available resource. The proposed 1:6 slope is within the range of natural slopes present on the property and has also been approved for the pit on adjacent Lot 393.

It is noted that while maximum final batter slopes are proposed to change from 1:10 to 1:6 this does not mean that all slopes will be 1:6. As shown in the Finished Development Plan (Figure 6), the steepest final slopes (1:6) will occur along the edges of the extraction area, with the majority of the final slopes in the pit being much gentler. It is also noted that while the proposed maximum depth of excavation is 5 m, the excavation in most areas will be shallower as indicated by the Finished Development Plan (Figure 6).



4.9 Access to Site

Access to site is off sealed Lowrie Road via the easement on the adjoining Lot 393 (Figure 3). The crossover from Lowrie Road to the site track has been sealed and caters for road train truck configuration take-off and radii. The site has easy access to South Western Highway as Lowrie Road connects to it approximately 500 m east of the crossover. A traffic impact assessment has been undertaken (Stantec 2023) (Appendix 6) and the findings are described further in Section 4.10.

Within the property, adequate unsealed access to the individual stages will be established as needed. This will include loading and turnaround facilities for all required plant and vehicles, which will be temporary in nature.

4.10 Number and Size of Trucks

It is expected that several truck configurations will be used to haul material from the proposed extraction site, primarily in gauge semi-trucks and RAV Pocket Road Trains. The traffic assessment (Appendix 6) considered truck configurations of up to 27.5 m long.

It was previously estimated that the number of truck movements would be on average 10 to 20 per day over the lifetime of the pit. However, the number of truck movements per day will be variable depending on market demand. During large hauling campaigns the number of trucks could potentially reach maximum of 75 per day (150 one-way trips). In the quiet periods between contracts, no truck movements are expected (as has occurred in the past) and these can last for several months. The overall number of trucks over the lifetime of the pit is limited by the finite sand and gravel resource available in the pit. Therefore, the higher the number of trucks per day, the faster the pit will be exhausted and the operations will cease permanently.

Lowrie Road currently has permit status for road train configuration vehicles and forms part of the Shire's regional road network. Cristal Mining hauled mineral sands from their operations via Lowrie Road and South Western Highway to Bunbury Port. Primary industry in the local area also makes use of this route. Further, the existing sand and gravel extraction operations on Lot 287 and Lot 393 use this route. Therefore, the route is expected to be well suited for the proposed scale of operations.

A traffic impact assessment was undertaken in 2023 by Stantec Australia Pty Ltd (Stantec 2023) that assessed the impact of the development on the adjacent road network and also focused on access arrangements to and from the access track leading into Lot 393 and Lot 287 (Appendix 6). The analysis was conducted on a maximum scenario of 14 truck movements per hour (seven trucks in and seven out), equating to a maximum of 150 movements over an 11 hour operational day (75 trucks in and out). It was concluded that the existing access to and from site on Lowrie Road is sufficient and the existing basic right turn and the auxiliary left turn lanes already in place where Lowrie Road exits onto South Western Highway provide good Safe Intersection Sight Distance, which will significantly reduce the risk of major crashes. Therefore, the additional truck movements in and out of the intersection are less likely to contribute to additional crashes (Appendix 6). It is noted that the assessment was undertaken on a maximum scenario and on average the truck volumes are likely to be much lower than assessed and are unlikely to have a substantial long-term impact on traffic operations and the overall safety of the road network around it.

4.11 OPERATING HOURS

The operating hours of the site are proposed to be limited to between 7 am and 6 pm Monday to Friday and between 7 am to 1 pm on Saturdays, with no operations on Sundays or Public Holidays. The current DA permits operations Monday to Friday and the addition of half day on Saturday is necessary to cater for clients who also operate on Saturdays. There are other extractive sites within the Shire that are approved to operate half days on Saturdays and it is also common practice in other local government areas.



4.12 Proposed Infrastructure

No permanent buildings or other infrastructure are proposed to be constructed on Lot 287. A portable toilet may be located on site.


4.13 PUBLIC DANGER


The site access gate is located at the start of the access track off Lowrie Road on Lot 393 and is locked when there is no personnel on site. Entry signage is in place and will be maintained warning the public of potential dangers. Warning signs (no more than 200 m apart) will also be placed along the property boundary. The property is securely fenced.

4.14 SURVEY INFORMATION

Verification of the original survey information (feature and contour survey) by BCE Surveying is provided in Appendix 7. Further, a copy of the Existing Contour and Feature Plan (Figure 3), including the location of the datum peg as requested by the Shire, is provided in size A1 in Appendix 12. A copy of the Finished Development Plan (Figure 6) is also provided in size A1 in Appendix 13.







5. ENVIRONMENTAL MANAGEMENT

5.1 BIODIVERSITY

The proposed extraction involves clearing of 9.70 ha of native vegetation that provides habitat for significant fauna species and also contributes to ecological connectivity of the local area. The impacts of this clearing and appropriate mitigation and offset measures will be addressed in detail as part of the Clearing Permit application process through DWER. At this stage, it is proposed that the impacts of the clearing will be mitigated and offset on the property by following key measures:

- Revegetation to native vegetation within the extraction area 3.14 ha.
- Converting blue gum plantation to native vegetation outside the extraction area 15.57 ha.
- Retaining and improving 9.31 ha of native vegetation.

This will result in net gain in the amount of native vegetation on the property from current 19.02 ha to 28.03 ha post-extraction. It is noted that the proposed extraction would provide the funding for converting some of the blue gum plantation to native vegetation and without that funding the blue gum areas will return to cleared land after harvesting.

5.2 Drainage

Lot 287 shares a Stormwater Management Plan with neighbouring Lot 393, which allows for appropriate management of stormwater across the combined sites. A revised Stormwater Management Plan (Rev 7) is included in this DA/EIL application package (Appendix 8).

5.3 Noise

A noise assessment for the proposed operations on Lot 287 was undertaken by Lloyd George Acoustics in April 2022 (Appendix 5) and involved modelling of anticipated noise levels on surrounding properties (Figure 4), firstly without and then with noise control measures. This assessment took into consideration that the proposed operations are located 155 m from the closest residence (Lot 26). The assessment showed that extraction operations can be undertaken in compliance with all applicable regulatory requirements subject to appropriate management measures being in place.

In accordance with the assumptions and recommendations of the noise assessment, the following measures will be put in place to ensure compliance with regulatory requirements and to minimise noise for the surrounding area:

- Operating hours of the site will be limited to between 7 am and 6 pm Monday to Friday, with Saturday operations limited to between 7 am and 1 pm.
- The crushing and screening plant will remain more than 500 m from the closest resident.
- For excavation operations within 200-450 m of receiver on Lot 26:
 - Provide a 4 m high noise bund within 6 m of the top edge of the pit at all times.
- For excavation operations within 150-200 m of receiver on Lot 26:
 - Provide a 4 m high noise bund within 6 m of the top edge of the pit at all times.
 - Provide a 3.5 m high bund to the north east of the crushing and screening plant.
 - The dozer will not to be operated at the same time as the loader.
- For excavation operations at the eastern extents:
 - Provide a 5 m high noise bund within 6 m of the top edge of the pit at all times.



- Provide a 3.5 m high bund to the north east of the crushing and screening plant.
- CAT 972 loader will be used as this item is 2 dB quieter than e.g. CAT 980.
- The dozer will not to be operated at the same time as the loader and will not be operated for more than 24 minutes in any 4 hour period.

5.4 Dust

The Dust Management Plan (Appendix 9) describes potential sources of dust generation and associated management measures. Dust management on the property will include prevention actions, monitoring and mitigation measures, and reporting and complaints procedures.

5.5 HYDROCARBONS AND CHEMICALS

No fuel or lubricant storage will take place on site. A refuelling vehicle, fitted with appropriate spill prevention and mitigation equipment, will visit site as required to refuel on site plant. No major repairs or maintenance will take place on site.

5.6 WEEDS

Weed control will be conducted during the extraction works on an as-needed basis to minimise weed occurrence in the operational and stockpiling areas. In addition to broad spectrum herbicides, weed specific herbicides will be used where appropriate to target broadleaf, grass, geophyte, and woody weeds. Targeted control will be undertaken for any identified pest weed species. Management of weeds is addressed in more detail in the accompanying Weed and Dieback Management Plan (Appendix 10). Weed control will also be undertaken during rehabilitation works as described in the Rehabilitation and Decommissioning Programme (Appendix 11).

5.7 DIEBACK

The majority of the native vegetation on Lot 287 is dieback infested (15 ha) with just under 1 ha uninfested (Bark Environmental 2020). The remainder of the native vegetation, the blue gum plantation areas, and cleared areas are mapped as 'excluded' due to the lack of indicator species to determine the occurrence of dieback. However, the presence of dieback in these areas cannot be ruled out and, because of this, the areas will be treated as if they are dieback infested. Information on dieback prevention and management is detailed in the Weed and Dieback Management Plan (Appendix 10). The Weed and Dieback Management Plan includes the site assessment and management recommendations from Bark Environmental. Dieback management will also adhere to any relevant conditions of a future Clearing Permit from DWER.

5.8 ABORIGINAL HERITAGE

As noted in Section 2.10, there are no registered Aboriginal heritage sites on the property. The applicant shall have due respect to the Aboriginal heritage of the area and all workers will be briefed accordingly prior to commencement of works on site. Should any potential artifacts or remains be discovered during operations, any works in the vicinity will stop immediately and the matter will be referred to the Department of Planning, Lands and Heritage. If bones are discovered, then the police will also be advised. The applicant notes that it is an offence to knowingly cause damage to an Aboriginal cultural heritage site under the WA *Aboriginal Cultural Heritage Act 1972*.

5.9 SCREENING OF VISUAL IMPACTS

The majority of the extraction works are screened from public roads or residences in the vicinity due to the presence of screening vegetation. The proposal consists of staged extraction and some of the stages are higher in the



landscape meaning they may be partly visible, mostly to the west and north. The eastern side the proposed operations is screened by a mixture of native vegetation and blue gums, and the clearing of the blue gums can be controlled to minimise potential visual impacts.

The gradual nature of the clearing and rehabilitation measures will ensure that any visual impacts will be as short in duration as possible. Rehabilitation of the extraction area will create a mixture of pasture and native vegetation that will blend the site into the surrounding landscape.

5.10 Rehabilitation and Decommissioning

A Rehabilitation and Decommissioning Programme (R&D Programme) is provided in Appendix 11. The objectives of the R&D Programme are as follows:

- Establish stable and safe landform post-extraction.
- Remove temporary infrastructure, rubbish, and debris.
- Establish a mixture of pasture and native vegetation (Figure 6) that will maintain the rural character of the property but also mitigate for the impacts of native vegetation clearing.

At this stage it is proposed that within the extraction area, 29.46 ha will be rehabilitated to pasture and 3.14 ha to native vegetation. Outside the extraction area, it is proposed that 15.57 ha of blue gum plantation will be converted to native vegetation and that 9.31 ha of existing native vegetation will be retained and improved. Please see the R&D Programme (Appendix 11) for further information. The proposed rehabilitation areas and rehabilitation measures may change as part of the Clearing Permit application process with DWER.



6. OTHER APPROVALS

The applicant holds an Environmental Licence (L9267/2020/1) for the crushing of gravel on both Lot 287 and Lot 393. A renewal application for this licence is currently being prepared which will be consistent with this DA/EIL application and incorporate the expansion area. The applicant is also in the process of preparing a Clearing Permit application to DWER. DWER is not expected to finalise processing of the application until the DA and EIL have been granted.

Abstraction of groundwater, if necessary, will be subject to a licence from DWER. The operations so far, have not required groundwater abstraction.



7. Conclusion

Lot 287 provides a valuable sand and gravel resource for the local construction industry. It has an established, active pit with good access to a major regional road and nearby communities. The proposed expansion will extend the life of the operations and provide a secure supply of sand and gravel at a time of high demand. Two thirds of the extraction area contain no native vegetation and the proposed clearing of 9.70 ha of native vegetation will be mitigated and offset as rehabilitation efforts will result in a greater area of native vegetation on the property after the extraction project than what is currently present. Historical clearing and disturbance and the presence of blue gum plantation make the site more suitable for extraction than other more densely vegetated sites. The removal of blue gums and progressive rehabilitation to pasture and native vegetation will ensure that in the long-term the rural character and environmental values of the area are maintained.

Potential noise and dust impacts on the closest residences have been addressed by incorporating recommendations of a noise assessment and by developing a management plan for dust. Parts of the pit may be visible from surrounding areas but the progressive rehabilitation to pasture and native vegetation will ensure that any visual impacts are temporary and that in the long-term the rural character of the area is maintained. The proposed changes to truck numbers and operational hours are not expected to result in significant additional impacts compared to the currently approved operations. Additional management plans are in place for weeds and dieback, stormwater, and rehabilitation.

Overall, it is expected that the proposed extraction operations can be managed in a way that avoids and minimises adverse environmental and social impacts and delivers a net positive outcome for the environment through facilitating the conversion of blue gum plantation to native vegetation.



8. REFERENCES

Australian Government (Aus Gov). 1999. *Environment Protection and Biodiversity Conservation Act 1999*. Administered by the Department of Climate Change, Energy, the Environment and Water. Accessed February 2024. https://www.legislation.gov.au/C2004A00485/2014-03-27/text

Bark Environmental. 2020. *Phytophthora Dieback Assessment Report Lot 287 Gwindinup*. Unpublished report for MGM.

Daniel Marsh Botanical Consulting. 2019. *Desktop Study and Reconnaissance Flora and Vegetation Survey. Lot 287 South Western Highway Gwindinup.* Unpublished report for MGM.

Department of Planning, Lands and Heritage (DPLH). 2013. *Greater Bunbury Strategy 2013*. Accessed February 2024.

https://www.dardanup.wa.gov.au/Profiles/dardanup/Assets/ClientData/Documents/Regional_Strategies___Structure_Plans/Greater_Bunbury_Strategy_2013-final-report.pdf

Department of Planning, Lands and Heritage (DPLH). 2018. *Strategic Minerals and Basic Raw Materials Resource Policy 2018*. Accessed February 2024. https://www.wa.gov.au/system/files/2021-06/POL-GBRS-Strategic-minerals-and-basic-raw-materials-policy.pdf

Department of Planning, Lands and Heritage (DPLH). 2015. *State Planning Policy 3.7 Planning in Bushfire Prone Areas*. Accessed February 2024.

https://www.wa.gov.au/system/files/2021-12/SPP-3.7-Planning-in-Bushfire-Prone-Areas.pdf

Department of Planning, Lands and Heritage (DPLH). 2021a. *State Planning Policy 2.4 - Planning for Basic Raw Materials*. Accessed February 2024.

https://www.wa.gov.au/system/files/2022-02/SPP-2.4-Planning-for-Basic-Raw-Materials.pdf

Department of Planning, Lands and Heritage (DPLH). 2021b. State Planning Policy 2.4 Planning for Basic Raw Materials Guidelines. Accessed February 2024.

https://www.wa.gov.au/system/files/2021-09/SPP_2.4_Guidelines_0.pdf

Department of Planning, Lands and Heritage (DPLH). 2023. *Aboriginal Cultural Heritage Act 1972*. Accessed February 2024.

https://www.wa.gov.au/organisation/department-of-planning-lands-and-heritage/aboriginal-cultural-heritage-act-2021

Department of Planning, Lands and Heritage (DPLH). 2024. *Search Aboriginal sites or heritage places*. Accessed February 2024.

https://www.wa.gov.au/government/document-collections/search-aboriginal-sites-or-heritage-places-ahis

Department of Primary Industries and Regional Development (DPIRD). 2022. *Soil Landscape Mapping - Systems (DPIRD-064)*. https://catalogue.data.wa.gov.au/dataset/soil-landscape-mapping-systems (accessed January 2024).

Department of Water and Environmental Regulation (DWER). 2019. *Water Quality Protection Note no. 15.* Accessed February 2024.

https://www.wa.gov.au/system/files/2022-06/WQPN-15-Basic-raw-materials-extraction.pdf

Environmental Protection Authority. 2005. *Guidance for the Assessment of Environmental Factors - Separation Distances between Industrial and Sensitive Land Uses No. 3.* Accessed February 2024. https://www.epa.wa.gov.au/sites/default/files/Policies_and_Guidance/GS3-Separation-distances-270605.pdf



Government of Western Australia. 2014. *Greater Bunbury Region Scheme*. Accessed February 2024. https://www.legislation.wa.gov.au/legislation/statutes.nsf/main_mrtitle_12899_homepage.html

Government of Western Australia (WA Gov). 2016. *Biodiversity Conservation Act 2016*. Administered by the Department of Biodiversity, Conservation and Attractions. Accessed February 2024. https://www.legislation.wa.gov.au/legislation/statutes.nsf/main_mrtitle_13811_homepage.html

Government of Western Australia (WA Gov). 2023. *State Planning Strategy 2050*. Accessed February 2024. https://www.wa.gov.au/system/files/2021-05/FUT-SPS-State_Planning_Strategy_2050.pdf

Harewood. 2019. Fauna Assessment - Lot 287 South Western Highway Gwindinup. Unpublished report for MGM.

Keighery, B.J. 1994. Bushland Plant Survey: A Guide to Plant Community Survey for the Community. Wildflower Society of WA (Inc). Nedlands, Western Australia.

Lloyd George Acoustics. 2022. Environmental Noise Assessment - Gravel Pit Expansion Lot 287 South Western Highway. Revision C. Unpublished report for MGM.

Shire of Capel. 2016. Extractive Industries Local Law 2016. Accessed February 2024. www.legislation.wa.gov.au/legislation/prod/gazettestore.nsf/FileURL/gg2016_197.pdf/\$FILE/Gg2016_197.pdf?OpenElement

Shire of Capel. 2021. 2021-2031 Strategic Community Plan. Accessed February 2024. https://www.capel.wa.gov.au/about/governance/publications/

Shire of Capel. 2023a. *Local Planning Policy LPP6.2 Extractive Industries*. Accessed February 2024. https://shireofcapel.sharepoint.com/:b:/s/website/EVmE3FeEIBFAmqrtL9pa7boBsUO6YRJSn-1EK97cQ03UbQ?e=Bj0jqr

Shire of Capel. 2023b. *Local Planning Strategy. Part 1 The Strategy and Part 2 Local Profile*. Accessed February 2024. https://www.capel.wa.gov.au/plan-build/planning-services/local-planning-strategy.aspx

Shire of Capel. 2023c. *Shire of Capel Local Planning Scheme No. 8.* Department of Planning, Lands and Heritage. Accessed February 2024.

 $\underline{https://shireof capel.sharepoint.com/:b:/s/website/EfcZCXvwFZBOiADsrtunoNIBALrKXx81-CfYCbzXoaNXLw?e=40Zruj}$



APPENDICES



DA AND EIL APPLICATION

APPENDIX 1: CERTIFICATE OF TITLE







AUSTRALIA

287/DP100056

DUPLICATE EDITION 31/7/2002

RECORD OF CERTIFICATE OF TITLE

1245

936

UNDER THE TRANSFER OF LAND ACT 1893

The person described in the first schedule is the registered proprietor of an estate in fee simple in the land described below subject to the reservations, conditions and depth limit contained in the original grant (if a grant issued) and to the limitations, interests, encumbrances and notifications shown in the second schedule.

REGISTRAR OF TITLES

LAND DESCRIPTION:

LOT 287 ON DEPOSITED PLAN 100056

REGISTERED PROPRIETOR:

(FIRST SCHEDULE)

MARIO MICHELE GIACCI OF POST OFFICE BOX 1263, BUNBURY

(TL764187) REGISTERED 20 OCTOBER 2011

LIMITATIONS, INTERESTS, ENCUMBRANCES AND NOTIFICATIONS:

(SECOND SCHEDULE)

1. TITLE EXCLUDES THE LAND SHOWN ON LTO PLAN 18912.

2. *L764188 MORTGAGE TO AUSTRALIA & NEW ZEALAND BANKING GROUP LTD REGISTERED

20.10.2011.

*L764189 CAVEAT BY CABLE SANDS (WA) PTY LTD LODGED 20.10.2011.

Warning: A current search of the sketch of the land should be obtained where detail of position, dimensions or area of the lot is required.

* Any entries preceded by an asterisk may not appear on the current edition of the duplicate certificate of title.

Lot as described in the land description may be a lot or location.

-- END OF CERTIFICATE OF TITLE--

STATEMENTS:

The statements set out below are not intended to be nor should they be relied on as substitutes for inspection of the land and the relevant documents or for local government, legal, surveying or other professional advice.

SKETCH OF LAND: 1245-936 (287/DP100056).

PREVIOUS TITLE: This Title.

NOTE 3:

PROPERTY STREET ADDRESS: LOT 287 SOUTH WESTERN HWY, GWINDINUP.

LOCAL GOVERNMENT AREA: SHIRE OF CAPEL.

NOTE 1: A000001A LAND PARCEL IDENTIFIER OF BOYANUP AGRICULTURAL AREA LOT 287 (OR THE

PART THEREOF) ON SUPERSEDED PAPER CERTIFICATE OF TITLE CHANGED TO LOT 287 ON DEPOSITED PLAN 100056 ON 02-MAY-02 TO ENABLE ISSUE OF A DIGITAL

CERTIFICATE OF TITLE.


NOTE 2: THE ABOVE NOTE MAY NOT BE SHOWN ON THE SUPERSEDED PAPER CERTIFICATE

OF TITLE OR ON THE CURRENT EDITION OF DUPLICATE CERTIFICATE OF TITLE.

DUPLICATE CERTIFICATE OF TITLE NOT ISSUED AS REQUESTED BY DEALING

L764188

				TOTAL		and have	
24	INDEXED.	e sense Pitli	ial			Land On XX	Vol. 1 Fol C36
	LANDS.	3/625 18 24 18 25	WESTERN		AUSTRALIA	Permitt AW XX	P. 1891>.
	zahoth the	Serning	armit .	Colourninstad		Name 5	
	the satisfaction of Our G	Enow re that We, of Our especial Grace, cer	e United Ringdom, Australia tain knowledge, and mere in Dive and Grant unto	and Her other Realms and Terr sotion, have given and granted,	tiories, Queen, Head of the Co., and We do these Presents,	mmonwealth, Defender of the Faith, for Us, Our helrs and successors, in co	To all to whom these Presents neideration of the payment of the ent of the prescribed conditions to
	vacreinafter called the O	rantes), the natural surface and so much a	f the land as is below the ne	ntural murface to a depth of	200	feet of ALL THA	T Tract or Parcel of Land situate
	and being in the District	a and Books of the Department of Lands	nnd Surveys of Our said Bia	ontaining 148 acres	3 roods 12 perch cultural Area Lo	t 287	- more or less, and marked and
	and as the same is deline AND TO HOLD the said To	ated and coloured green in the plan drawn act or Parcel of Land to the depth aformald,	hereon; TOGETHER with all and singular the Fremi	Profits, Commodities, Heredits nes hereby granted, with their ap-	oments, and Appurtenances wi purtenances, unto the said Gran	intsoever thereunto belonging, or in	anywise appertaining: TO HAVE
- 4							
	nerally for any other	T Works or numbers of public use utility or	ig in remar any roads, tramw	nys, ratiways, railway stations, bri	dges, canals, towing paths, horh	our works, brenkwaters, river improvem	ents, drainage or trigation works
	tip a including all Bands	who distributed the said land, with full liberty alwood and Maliet trees on the said lands to the said	at all times to search and di s reserved to the Grown save	ig for and carry away the same, that the grantce may ringbard	and for that purpose to enter	upon the said land or any part thereo	d; and all marketable indigenous or than Sandalwood and Mallet
	of extracting any markets	Us or by any person or corporation in whom able indigenous timber from any other in- rom any spaning arream, well or water hole a	m the control of forests is for ad in the locality, full liber; and to lay down and constru-	r the time being vested, to enter r for Us and any of the persons of pipe lines for conveying the	r, obtain and remove any of the aforesaid to pass and re-pass o water and to make roads and	* marketable indigenous timber and for your the said lands with or without ways and construct and maintain tim	to Us, Our helrs and successors or that purpose or far the purpose workmen, machinery, horses and ther transvars on the said lines.
U	will moke good the actual	ands, reserves or State forcets without ma	king to the grantee or transf	ferces or assigns of the grantee :	any compensation in respect of	any of the matters aforesaid: Provided	that We. Our heirs and successors
	797.19	Company of the Compan					
		Empire, Companion of	the Most Honourable Ord	ier of the Bath, Governor in			
4	Seal				and nine hundred and	sixty two.	0
· 8/10	Grant under the	Land Act, 1933	ENTI	ERED ON RECORD this			
Se	Sans	Do acto	10	the day or August	Muddlela 1982	111 (111) 1 (11)	245 0936 F
	Min			for minis	ter for Lands.	1893	
AUSTRALIA Land May 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	nd described in this grant.						
7						ASSISTANT PEGI	
			1 Tra	AN HEREIN REFERRED T	to Rhonor	a Mary Kilche	at of Boyamp.
		477	11 (ar	reed froman	· Kegist	ned 9 fame	way 1964 at
	Le 10		All a				1
• •	393		I Ic	ansfer cayao	259 to W.a. C	rip & Pulp Co. Ply	y-htd., of
4	1)	62/9	A R	igistered 28th	October 198	at 10:080'C	(3+ 111 (c)
*	107	286	R0A0 (wdg) Grz 10-1-95 Plan 18912 2702m nes d			1.17	The state of the s
			-	ROAD (Wdg) BAZ 23/1/96 LTO PLAN 18912			
,	Scale la	chains to an inch.					
	4 18 7/40, S. a	Assorting How In Exit	a.				
	5						
= =							
-		10					
	_						
	2	34					
43140,	/4/61—1m—11/0	For e	ncumbrances and	other matters affecti	ng the land see bac	k.	



DA AND EIL APPLICATION

APPENDIX 2: FLORA AND VEGETATION SURVEY



DESKTOP STUDY AND RECONNAISANCE FLORA AND VEGETATION SURVEY LOT 287 SOUTH WEST HWY, GWINDINUP, WA

FOR MARIO MICHELE GIACCI

JANUARY 2019

Daniel Marsh & Botanical Consulting



Table of Contents

1. SUMMARY	6
2. INTRODUCTION	7
2.1 Background	7
2.2 Scope and objectives	7
2.3 Desktop Study Findings	7
3. METHODS	18
3.1 Desktop Study	18
3.2 Field Assessment	18
3.3 Vegetation Mapping	19
3.4 Limitations	19
4. RESULTS	20
4.1 Native Flora	20
4.2 Threatened and Priority Flora	20
4.3 Introduced Species	20
4.4 Vegetation Types	20
4.5 Vegetation Condition	24
5. DISCUSSION AND CONCLUSIONS	26
6. REFERENCES	27

Appendices

Appendix A:	Summary of	Vascular I	Plants I	Recorded	within	Survey A	4rea
-------------	------------	------------	----------	----------	--------	----------	------

Appendix B: Relevé and Opportunistic Data

Appendix C: NatureMap Search Results for Threatened and Priority Species that have Potential to Occur within Survey Area

Appendix D: EPBC Protected Matters Search Report for Threatened and Priority Species that have Potential to Occur within Survey Area

Figures

- Figure 1: Survey Area Location
- Figure 2: Aerial Photograph of Survey Area
- Figure 3: Conservation Coded Flora within 10km of Survey Area
- Figure 4: Vegetation Complexes of Survey Area
- Figure 5: Threatened and Priority Ecological Communities within 10km of Survey Area
- Figure 6: Vegetation Types Recorded within Survey Area
- Figure 7: Vegetation Condition within Survey Area
- Figure 8: Location of Relevé Sites
- Figure 9: Photograph of Site 06 (VT1, very good/good condition)
- Figure 10: Photograph of Site 09 (VT2, very good/good condition)
- Figure 11: Photograph of Site 21 (VT3, very good/good condition)

Tables

- Table 1: Summary of the Conservation coded flora that were identified in the desktop study as having potential to occur within the survey area
- Table 2: Description and extent of vegetation complexes in the survey area
- Table 3: Potential limitations of the desktop study and reconnaissance survey
- Table 4: Native vegetation types defined within the survey area
- Table 5: Vegetation condition within the survey area

1. SUMMARY

Daniel Marsh Botanical Consulting undertook a desktop study and reconnaissance survey of Lot 287 South Western Hwy, Gwindinup, Western Australia in November 2018. The survey area was approximately 46ha of which 19ha was covered with native vegetation. The survey area was traversed by car and on foot and a total of 8 relevé survey sites plus opportunistic recordings and collections were conducted. The sample intensity and time of survey was considered adequate for a reconnaissance survey.

A total of 55 native vascular plant taxa representative of 47 plant genera and 29 plant families were recorded within the survey area. Seven introduced species were recorded, none of which are listed as a Declared Pest under the *Biosecurity and Agriculture Management Act* 2007 (DPIRD 2018).

No Threatened flora species as listed under section 178 of the Commonwealth *Environmental Protection and Biodiversity Conservation Act 1999* (EPBC Act) were recorded within the survey area (SPRAT 2018).

No Threatened flora species pursuant to the Western Australian *Biodiversity Conservation Act 2016* and listed by the Department of Biodiversity, Conservation and Attractions (DBCA 2018a) were recorded within the survey area. No Priority flora species listed by the Department of Biodiversity, Conservation and Attractions (WAH 2018) were recorded within the survey area.

Three vegetation types were defined within the survey area, all consisting of variations of *Eucalyptus marginata* and *Corymbia calophylla* woodlands over *Xanthorrhoea preissii*. No Threatened Ecological Communities (TEC) or Priority Ecological Communities (PEC) were inferred to occur within the survey area (DBCA 2018b, DBCA 2018c) and the vegetation complexes mapped by Mattiske and Havel (1998) for the survey area are all regarded as well-conserved.

The DBCA database search indicated that the survey area mapped within the buffer of Priority 1 Whicher Scarp Paluslope Wetlands / Swan Coastal Plain Paluslope Wetlands. "These wetlands are very wet all year round and are associated with areas of groundwater seepage from the sandy low hills at the base of the Whicher Scarp" (DBCA 2018c). Wetland habitats were not encountered within the survey area and the vegetation types recorded in this survey were not structurally or floristically similar to the mapped PEC. Statistical analysis was not performed.

Most of the remnant areas of native vegetation ranged in condition from very good to good (40.2%). Vegetation condition was variable due to the fragmented nature of the remnant areas and the impacts of disturbances such as old tracks, logging, cleared areas and weeds. The remainder of the survey area consisted of bluegum plantations, tracks and cleared areas and was considered completely degraded (58.7%).

2. INTRODUCTION

2.1 Background

The survey area was located on Lot 287 (Plan 100056) approximately 10km north-west of the town of Donnybrook along the South Western Highway (Figure 1). The survey area was 46ha of which approximately 19ha was covered with native vegetation. The remainder of the survey area consisted of bluegum plantations, cleared areas and tracks (Figure 2).

Donnybrook experiences a Mediterranean-type of climate, with warm dry summers and cool wet winters. The average annual rainfall for Donnybrook is 973.1 mm and the mean minimum / maximum temperatures for Donnybrook range from 14.1 °C to 30.6 °C in January, and from 5.7 °C to 16.5 °C in July (Bureau of Meteorology 2018).

Lot 287 is situated on the Darling Fault which delineates the eastern periphery of the southern Perth basin and separates the Archaean granitic rocks of the Yilgarn Block to the east from sediments in the Bunbury Trough, a structural sub-division of the Perth Basin (Wilde and Walker 1982).

2.2 Scope and objectives


The scope and objectives of the flora survey were to carry out a desktop study and reconnaissance survey of the survey area on Lot 287 South Western Hwy, Gwindinup. The survey scope included the following requirements:


- Review contextual information on the survey area from previous surveys, literature, aerial imagery, database searches and spatial information to summarise the values of flora and vegetation significance in the project area;
- Conduct a field assessment to:
 - o Identify the vascular flora species present;
 - o Determine the presence or absence of Threatened flora, Priority or significant species and to record the abundance and distribution if present;
 - o Assess the conservation significance of vegetation and flora;
 - o Define and map vegetation communities using the relevés method;
 - o Define and map vegetation condition;
 - o Determine the presence or absence of Threatened and Priority ecological communities and map their extent if present.

2.3 Desktop Study Findings

2.3.1 Flora

Database searches identified eight plant taxa declared as rare flora under the state *Biodiversity Conservation Act 2016* that have been recorded within 10km of the survey area. In addition, seven P1 taxa, six P2, eleven P3 and six P4 taxa have been recorded within 10km of the survey area. The EPBC protected matters search tool identified two Critically Endangered taxa, eleven Endangered and six Vulnerable taxa that have the potential to occur within 10km of the survey area. These taxa are listed in Table 1 that also includes details on preferred habitat characteristics and the flowering period as well as the likelihood of occurrence in the survey area, assessed on the basis of distribution and habitat availability.








Table 1: Summary of the Conservation coded flora that were identified in the desktop study as having potential to occur within the survey area

NM = Naturemap with 10km buffer

EPBC = EPBC Act Protected Matters Search Tool with 10km buffer (CE=Critically Endangered,

E=Endangered, V=Vulnerable)

PW = DBCA database search with 10km buffer

Species	NM	EPBC	PW	Flowering	Habitat	Likelihood
Apiaceae						
Brachyscias verecundus (SPRAT 2018)		V		Dec (Annual)	Winter-wet clay over ironstone. In a moss sward on a granite outcrop.	Unli kely (Habitat)
Aponogetonaceae						
Aponogeton hexatepalus (WAH 2018)	P4		P4	July - Oct	Aquatic plant found in freshwater	Unlikely (Habitat)
Asparagaceae	D2		D.2	N. D.		D '11
Lomandra whicherensis (WAH 2018)	P3		P3	Nov – Dec (Perennial)	Shallow sand over laterite on ridgelines	Possible
Cyperaceae	D.0		D.2	2.7		D '11
Caustis sp. Boyanup (WAH 2018)	Р3		P3	No information found	White or grey sand	Possible
Cyathochaeta teretifolia (WAH 2018)	Р3		Р3	No information found	Grey sand and sandy clay in swamps, creek edges	Unlikely (Habitat)
Eleocharis keigheryi (WAH 2018)	Т	V	T	Aug - Nov	Emergent in freshwater: creeks, claypans	Unlikely (Habitat)
Elaeocarpaceae						
Platytheca anasima (Butcher 2008)	P2		P2	Oct-Dec	Gentle slopes of white- grey sand or brown sandy loam	Possible
Ericaceae						
Andersonia ferricola (WAH 2018)	P1		P1	Oct	White sand or red-brown loam over ironstone. Seasonally wetlands	Unlikely (Habitat)
Andersonia gracilis (WAH 2018)		Е		Sep – Nov	White/grey sand, sandy clay, gravelly loam. Winter-wet areas, near swamps	Unlikely (Distribution)
Leucopogon sp. Busselton (Ecoedge 2016)	P2		P2	Aug - Sep	Pericalymma ellipticum wet shrubland, Marri- Jarrah woodland	Possible
Fabaceae	D2			T 1 4	T	77 111 1
Acacia drummondii subsp. affinis (WAH 2018)	P3			Jul – Aug	Lateritic gravelly soils	Unlikely (Distribution)
Acacia flagelliformis (WAH 2018)	P4		P4	May – Sep	Sandy soils. Winter-wet areas	Possible
Acacia semitrullata (WAH 2018)	P4		P4	May – Oct	White/grey sand, sometimes over laterite, clay. Sandplains, swampy areas.	Possible
Daviesia elongata (WAH 2018)	T	V	T	Sep or Dec or Jan to Feb	Sand, laterite	Possible
Dillwynia sp. Capel (WAH 2018)	P1		P1	Sep-Oct	Littered grey loamy sand, rocky soils. Valleys, rangelands.	Possible
Gastrolobium sp. Yoongarillup (DBCA 2017)	P1		P1	Oct Perennial	No information found	Possible

Species	NM	EPBC	PW	Flowering	Habitat	Likelihood
Gastrolobium papilio		Е		Oct – Dec	Sandy clay over ironstone	Unlikely
(WAH 2018)				Perennial	and laterite. Flat plains	(Distribution)
(SPRAT 2018)						
Gastrolobium	P2		P2	Oct	Red-grey sandy clay over	Unlikely
whicherense				Perennial	quartzite. Steep westerly	(Habitat)
(WAH 2018)					slopes	
Pultenaea skinneri	P4		P4	Jul – Sep	Sandy or clayey soils.	Unlikely
(WAH 2018)				(Perennial)	Winter-wet depressions	(Habitat)
Loganiaceae						
Orianthera wendyae	P1		P1	Oct	No information found	Possible
(DBCA 2017)						
Malvaceae						
Lasiopetalum laxiflorum	P3		P3	Oct-Jan	Eucalyptus marginata,	Possible
(Shepherd and Wilkins				(Perennial)	Corymbia, Allocasuarina	
2015)					or Banksia grandis	
					woodland or forest, in	
					gravelly, brown clay over	
					laterite, rarely in white	
					sand	
Menyanthaceae	P4		P1	San Oat	Surface of the shallow	I Indidentes
Ornduffia submersa (TBW 2013)	P4		PI	Sep-Oct	water	Unli kely (Habitat)
Myrtaceae					water	(Habitat)
Chamelaucium sp. S		V		Nov – Dec	Swamp margins in open	Unlikely
coastal plain		V		(Perennial)	Dryandra shrubland in	(Habitat)
(SPRAT 2018)				(1 ereilliai)	winter-wet sandy clay sites	(Haonai)
(SIRAI 2016)					on a coastal plain	
Darwinia whicherensis	T		T	Oct – Nov	winter-wet area of	Unlikely
(SPRAT 2018)	1		1	(Perennial)	shrubland over shallow red	(Habitat)
(511011 2010)				(1 cremmar)	clay over ironstone	(Haonat)
Verticordia densiflora	Т	Е	Т	Dec – Jan	Grey/yellow sand, sandy	Unlikely
var. pedunculata	1	L	1	(Perennial)	loam. Winter-wet low-	(Habitat)
(WAH 2018)				(= =======)	lying areas.	(======================================
Orchidaceae						
Caladenia hoffmanii		Е		Aug – Oct	Clay, loam, laterite,	Unlikely
(WAH 2018)				(Perennial)	granite. Rocky outcrops	(Distribution)
				,	and hillsides, ridges,	,
					swamps and gullies.	
Diuris micrantha		V		Sep – Oct	Winter-wet swamps, in	Unlikely
(WAH 2018)				(Perennial)	shallow water	(Habitat and
,						distribution)
Diuris purdiei		Е		Sep – Oct	Grey-black sand, moist.	Unlikely
(WAH 2018)				(Perennial)	Winter-wet swamps.	(Habitat and
					_	distribution)
Drakaea elastica	T	Е	T -	Oct - Nov	White or grey sand. Low-	Unlikely
(WAH 2018)			CR	(Perennial)	lying situations adjoining	(Habitat and
(SPRAT 2018)		<u></u>			winter-wet swamps	distribution)
Drakaea micrantha		V		Sep – Oct	Cleared firebreaks or open	Unlikely
(WAH 2018)				(Perennial)	sandy patches that have	(Distribution)
(SPRAT 2018)					been disturbed. White-grey	
					sand. In Jarrah or Sheok	
					woodland	
Thelymitra variegata	P2		P2	June – Sep	Sandy clay, sand, laterite	Possible
(WAH 2018)				(Perennial)		

Species	NM	EPBC	PW	Flowering	Habitat	Likelihood
Proteaceae						
Banksia squarrosa subsp. Argillacea (WAH 2018) (SPRAT 2018)	Т		T	June – Nov (Perennial)	White/grey sand, gravelly clay or loam. Winter-wet flats, clay flats	Unlikely (Distribution)
Banksia nivea subsp. uliginosa (WAH 2018) (SPRAT 2018)		Е		Aug – Sep (Perennial)	Sandy, clay, gravel	Unlikely (Distribution)
Franklandia triaristata (WAH 2018)	P4		P4	Aug – Oct (Perennial)	White or grey sand	Possible
Grevillea bronwenae (WAH 2018)	Р3		P3	June – Dec (Perennial)	Grey sand over laterite, lateritic loam. Hillslopes.	Possible
Isopogon formosus subsp. dasylepis (WAH 2018)	Р3		Р3	Jun – Dec (Perennial)	Sand, sandy clay, gravelly sandy soils over laterite. Often swampy areas.	Possible
Lambertia echinata subsp. occidentalis (WAH 2018) (SPRAT 2018)		Е		Feb, Apr, Dec (Perennial)	White sandy soils over laterite, orange/brown-red clay over ironstone. Flats to foothills, winter-wet sites.	Unlikely (Distribution)
Petrophile latericola (WAH 2018) (SPRAT 2018)		E		Nov (Perennial)	Red lateritic clay. Winterwet flats.	Unlikely (Habitat and distribution)
Sphenotoma drummondii (WAH 2018) (SPRAT 2018)		E		Sep – Dec (Perennial)	Stony or shallow soils over granite or quartzite. Steep rocky slopes, crevices of rocks.	Unlikely (Habitat and distribution)
Synaphea hians (WAH 2018)	Р3		Р3	July, Sep, Nov (Perennial)	Sandy soils. Rises.	Possible
Synaphea odocoileops (WAH 2018)	P1		P1	Aug – Oct (Perennial)	Brown-orange loam & sandy clay, granite. Swamps, winter-wet areas.	Unli kely (Habitat)
Synaphea petiolaris subsp. simplex (WAH 2018)	P3		P3	Sep – Oct (Perennial)	Sandy soils. Flats, winterwet areas.	Possible
Synaphea polypodioides (WAH 2018) (DBCA 2017)	Р3		P3	Sep – Oct (Perennial)	Light brown loam, red- brown sandy loam, gravelly, brown sandy clay over laterite. In undulating areas.	Unli kely (Habitat)
Synaphea sp. Fairbridge Farm (WAH 2018) (SPRAT 2018)		CE		Oct (Perennial)	Sandy with lateritic pebbles. Near winter-wet flats, in low woodland with weedy grasses.	Possible
Synaphea sp. Pinjarra Plain (WAH 2018) (SPRAT 2018)	Т		T	Sep – Nov (Perennial)	Grey sandy loam or clay, grey-brown clayey sand, brown clayey loam, laterite. Flats, seasonally wet areas, railroad reserves often with wet depressions or drains.	Unli kely (Distribution)
Synaphea sp. Serpentine (SPRAT 2018)		CE		Aug – Nov (Perennial)	No information found	Unlikely (Distribution)

Species	NM	EPBC	PW	Flowering	Habitat	Likelihood
Synaphea stenoloba (WAH 2018)	T	Е	T - CR	Aug - Oct	Sandy or sandy clay soils. Winter-wet flats, granite.	Unli kely (Habitat)
Rhamnaceae						
Stenanthemum sublineare (WAH 2018)	P2			Oct – Dec (Perennial)	Littered white sand. Coastal plain.	Unlikely (Habitat and distribution)
Rutaceae						
Boronia humifusa	P1		P1	Jun – Sep (Perennial)	Gravelly clay loam over laterite. Jarrah-marri open forest	Possible
Stylidiaceae						
Stylidium acuminatum subsp. acuminatum (Wege 2010)	P2		P2	Oct – Nov	Lateritic soils on hillslopes and in valleys, in Eucalyptus marginata and/or Corymbia calophylla forest.	Possible
Stylidium nitidum (Lowrie and Kenneally 2017)			P1	Oct - Nov	Occurs in the southern Jarrah Forest growing in grey sand mostly under Casuarina and Baeckea species	Possible
Xanthorrhoeaceae						
Chamaescilla gibsonii (WAH 2018)	Р3		Р3	Sep	Clay to sandy clay. Winterwet flats, shallow waterfilled claypans.	Unli kely (Habitat)

Many of the conservation coded taxa in Table 1 are restricted to habitats or soils and landforms that are not found within the survey area. They are therefore unlikely to occur within the survey area. On the basis of habitat characteristics and known distribution, 21 taxa are considered to have potential to occur within the survey area (Table 1).

Within the survey area boundary there are no past records of Threatened or Priority flora taxa (Figure 3). The closest records of Priority flora consist of two identical records of *Lomandra whicherensis*, however their location does not match the description of the location for the record. The described location is approximately 3km to the south of the survey area growing on a ridgeline in sandy clay over laterite. Several hundred of plants were recorded growing in *Eucalyptus haematoxylon / E. marginata* low woodland over *Xanthorrhoea acanthostachya* shrubland.

Other Priority flora taxa recorded near the survey area such as *Aponogeton hexatepalus*, an aquatic plant, and *Cyathochaeta teretifolia*, a sedge, are not expected in the survey area due to lack of suitable habitat.

2.3.2 Vegetation

The survey area occurs within the Jarrah Forest Bioregion as defined in the Interim Biogeographical Regionalisation for Australia (IBRA). DBCA has compiled a dataset that is a comprehensive coverage of pre-1750 distribution of vegetation complexes of the south west forest region of Western Australia based on 1:50,000 mapping of Mattiske and Havel (1998). It has been reviewed and changes have been made to ensure the complexes of the Whicher Scarp reviewed by Webb et al. (2016) were a continuation of those defined by Mattiske and Havel (1998).

The majority of the survey area is located in an area mapped as low valley slopes of the Rosa vegetation complex (Figure 4). The western edge of the survey area has been mapped as gentle slopes of the Whicher Scarp. A small section of the survey area is mapped as uplands of the Kingia complex. The soil is characterised by sandy gravels on broad lateritic crests over sedimentary rocks. The descriptions, percentage of survey area and reservation are listed in Table 2.


Table 2: Description and extent of vegetation complexes in the survey area (Government of Western Australia 2018).


Description	Portion of Total Survey Area (ha)	Current Extent Protected (IUCN I-IV) for Conservation (ha)	Current Extent in DBCA Managed Land (ha)	Pre- European Area Remaining (ha)
Rosa valleys (243)— Woodland to open forest of <i>Corymbia calophylla-Eucalyptus marginata</i> subsp. <i>marginata-Xylomelum occidentale</i> on slopes and tall shrubland of <i>Agonis linearifolia</i> in valley floors in the humid zone.	41.26	2,093.61	11,447.51	12,979.04
	(89.6%)	(12.05%)	(66.4%)	(75.28%)
Whicher Scarp Uplands (290) - Open forest of Eucalyptus marginata subsp. marginata-Corymbia calophylla on escarpment with some Corymbia haematoxylon, Banksia attenuata and Xylomelum occidentale in the humid zone.	4.08 (8.8%)	423.43 (9.39%)	2,417.31 (53.60%)	3,129.06 (69.39%)
Kingia Uplands (155) - Open forest of Eucalyptus marginata subsp. marginata-Corymbia calophylla-Allocasuarina fraseriana-Banksia grandis-Xylomelum occidentale on lateritic uplands in prehumid and humid zones.	0.73	26,212.55	94,478.07	96,173.78
	(1.6%)	(25.69%)	(92.60%)	(94.26%)

The DBCA database search for TECs and PECs showed the survey area mapped within the buffer of Whicher Scarp Paluslope Wetlands - Swan Coastal Plain Paluslope Wetlands Priority 1 (Figure 5). This community is described as:

"These wetlands are very wet all year round and are associated with areas of groundwater seepage from the sandy low hills at the base of the Whicher Scarp. At times these wetlands are contiguous with areas of Pinjarra Plain wetlands, and the wetlands of the two landforms merge. Combinations of the following species are typically found in the type: *Melaleuca preissiana*, *Taxandria linearifolia*, *Taxandria fragrans*, *Melaleuca incana*, and *Cyathochaeta teretifolia*. Other species include: *Eucalyptus patens*, *Homalospermum firmum*, *Gahnia decomposita*, *Callistachys lanceolata*, *Hakea linearis*, *Melanostachya ustulata*, *Evandra aristata*, *Beaufortia sparsa*, *Calistemon glaucus* and *Pultenaea pinifolia*" (DPAW 2018c).

After a review of the spatial data and aerial imagery, no wetland habitat or vegetation communities are expected in the survey area.





3. METHODS

3.1 Desktop Study

The desktop study gathered contextual information on the survey area from previous surveys, literature, aerial imagery, database searches and spatial information. Resources used included:

- DBCA Threatened Flora Database;
- DBCA Threatened Ecological Communities Database;
- NatureMap (DBCAd);
- Florabase (Western Australian Herbarium);
- EPBC Act List of Threatened Flora;
- EPBC Act List of Threatened Ecological Communities;
- Australian Government's EPBC Act Protected Matters Search Tool (Department of the Environment and Energy);
- Spatial data available from the Government of Western Australia;
- Previous surveys and articles describing significant flora.

3.2 Field Assessment

The field assessment was conducted by one ecologist in November 2018. The vegetation was assessed using the relevé method according to standards set out in Technical Guidance – Flora and Vegetation Surveys for Environmental Impact Assessment (EPA 2016). Relevé sites were selected using aerial imagery and field selection. Opportunistic collections were made when appropriate. The following parameters were recorded at unmarked survey sites.

- GPS location;
- Description of vegetation structure;
- Vegetation condition score (Keighery 1994);
- The height and percentage cover of dominant or important plant species of the differing strata layers;
- Presence and absence of all species other than the dominants within approximately 10m of the recorder;
- Soil type;
- Disturbance;
- Site photographs.

Plant taxa that could not be identified in the field were collected systematically, dried and fumigated before identification. Plant specimens collected were identified using keys or through comparisons with pressed specimens at the WA Herbarium. When necessary, plant taxonomists with specialist skills were consulted to confirm identification.

3.3 Vegetation Mapping

Vegetation types were defined based on structure and dominant species at each survey site and described in accordance to the standards set out in the National Vegetation Information System (NVIS) Australian Vegetation Attribute Manual Version 7.0 (ESCAVI 2017). Mapping polygons were developed using aerial photography interpretation in conjunction with field notes and co-ordinates recorded during the survey.

3.4 Limitations

Table 3 displays the evaluation of the flora and vegetation assessment against a range of potential limitations. Based on this evaluation, the assessment has not been subject to constraints that would affect the thoroughness of the assessment and the conclusions reached.

Table 3: Potential limitations and constraints

Potential Limitation	Impact of Constraint	Comment
Availability of contextual	Not a constraint	The area of survey has been reasonably
information at a regional and local		well surveyed and adequate data were
scale		available.
Competency/experience of the	Not a constraint	Personnel have the appropriate training
team carrying out the survey,		and extensive survey experience within
including experience in the		the Jarrah Forest and Swan Coastal Plain.
bioregion surveyed. Access restrictions within the	Not a constraint	
	Not a constraint	The survey area has numerous tracks
survey area		and the survey area is small enough to be traversed by foot.
Intensity of survey	Not a constraint	For a desktop study and reconnaissance
intensity of survey	rvot a constraint	survey, the depth of investigation and
		data collection was considered
		sufficient.
Timing of the survey	Not a constraint	The field assessment was conducted in
		November. Flora and vegetation
		surveys are normally conducted
		following winter rainfall in the South-
		West Province, ideally during spring
		(EPA 2016).
Disturbance	Not constraints	Although the survey area has been
		subject to multiple disturbances, the
		flora and vegetation was adequately
		described.
Completeness	Not a constraint	The information collected during the
		survey was sufficient to assess the
		vegetation that was present during the
		time of the survey.

4. RESULTS

4.1 Native Flora

A total of 55 native vascular plant taxa representative of 47 plant genera and 29 plant families were recorded within the survey area (Appendix 1). The majority of the taxa recorded were representative of the Myrtaceae (7 taxa), Proteaceae (5 taxa) and Hemerocallidaceae (4 taxa) families.

4.2 Threatened and Priority Flora

No Threatened flora pursuant to the *Environment Protection and Biodiversity Conservation Act 1999* (EPBC Act) and as listed by the Department of the Environment and Energy (DEE 2018) were recorded within the survey area. No Threatened flora pursuant to the Western Australian *Biodiversity Conservation Act 2016* and as listed by the Department of Biodiversity, Conservation and Attractions (DBCA 2018a) were recorded within the survey area. No Priority flora species as listed by the Western Australian Herbarium (WAH 2018) were recorded within the survey area.

4.3 Introduced Species


Of the 62 plant taxa recorded within the survey area, 7 species were introduced (11%). None of these introduced taxa are listed as a Declared Pest under the *Biosecurity and Agriculture Management Act* 2007 (DPIRD 2018).


4.4 Vegetation Types


Three native vegetation types were defined within the survey area and are described in Table 4 and presented in Figure 6. The remainder of the survey consisted of disturbed areas (D).

Table 4: Native vegetation types defined within the survey area

Code	Vegetation Type Description	Area (ha)	% of survey area
VT1	Tall woodland of <i>Eucalyptus marginata</i> and <i>Corymbia calophylla</i> over low woodland <i>of Banksia grandis</i> over tall sparse shrubland of <i>Kunzea glabrescens</i> over low sparse shrubland of <i>Xanthorrhoea preissii</i> .	0.79	1.7%
VT2	Tall woodland of <i>Eucalyptus marginata</i> and <i>Corymbia calophylla</i> over tall sparse shrubland of <i>Kunzea glabrescens</i> over low sparse shrubland of <i>Xanthorrhoea preissii</i> and <i>Xanthorrhoea gracilis</i> .	0.84	1.8%
VT3	Tall woodland of <i>Eucalyptus marginata</i> and <i>Corymbia calophylla</i> over low sparse shrubland of <i>Xanthorrhoea preissii</i> and <i>Hibbertia hypericoides</i> .	17.39	37.8%
D	Disturbed: Bluegum plantations, tracks and clearings.	27.04	58.7%







4.5 Vegetation Condition

Most of the remnant areas of native vegetation had a condition ranging from very good to good (Table 5; Figure 7). Vegetation condition was variable due to the fragmented nature of the remnant areas and the impacts of disturbances such as old tracks, logging, cleared areas and weeds. The remainder of the survey area consisted of bluegum plantations, tracks and cleared areas and was considered completely degraded.

Table 5: Vegetation condition within the survey area

Vegetation Condition	Area (ha)	% of survey area
Very Good/Good	18.51	40.2%
Good	0.27	0.6%
Degraded	0.24	0.5%
Completely Degraded	27.04	58.7%



Figure 9: Site 06 - VT1 - very good/good vegetation condition



Figure 10: Site 09 – VT2 – Very good/good vegetation condition



Figure 11: Site 19 – VT3 – Very good/good vegetation condition

5. DISCUSSION AND CONCLUSIONS

No significant flora species were recorded within the survey area. It was not possible to identify one taxon collected, *Lomandra* sp., to species level due to the lack of flowering parts. The sample was compared with specimens at the Western Australian Herbarium and it was confirmed that it was not *Lomandra whicherensis* (P3) which has flatter, thinner leaves with many more striations.

An Orchidaceae sp. was collected during the survey but its identification was not possible due to the deterioration of the sample. The only conservation significant Orchidaceae sp. that was considered possible to occur in the survey area after further investigation was *Thelymitra variegata* (P2). It flowers between June and September and has been recorded in sandy clay, sand and laterite (WAH 2018). There is only one record of this taxon within 10km and it is located approximately 4km to the north-west of the survey area. While it is possible that this taxon may occur within the survey area, it is unlikely due to the lack of nearby records.

Other conservation coded flora taxa identified in the desktop survey that were considered possible to occur within the survey area are either recorded as flowering during November or are perennial species that would have been observable during the survey, despite not flowering. Therefore, the sample intensity and time of survey was considered adequate, considering the size of the survey area and significant flora species identified in the desktop study.

The three native vegetation types defined in the survey area consist of variations of Jarrah/Marri woodlands over *Xanthorrhoea* and do not resemble any TECs or PECs. The vegetation types recorded in this survey were not structurally or floristically similar to the mapped PEC, Priority 1 Whicher Scarp Paluslope Wetlands / Swan Coastal Plain Paluslope Wetlands, and wetland habitats were not encountered within the survey area. The vegetation types recorded in this survey were also compared to TECs and PECs listed by DBCA but statistical analysis was not performed. The vegetation complexes mapped by Mattiske and Havel (1998) for the survey area have relatively high pre-European extent and reservation (Government of Australia 2018).

The fragmented nature of the remnant vegetation has affected its condition. Vegetation was patchy due to the impacts of various forms of disturbance and was therefore mapped as a mosaic of very good and good condition. Edge effects from fragmentation are known to influence vegetation condition, in particular weed infestation (Stenhouse 2004).

6. REFERENCES

Beard, J.S. (1990) Plant Life of Western Australia. Kangaroo Press.

Bureau of Meteorology (2013) Climate Statistics for Donnybrook http://www.bom.gov.au/climate/averages/tables/cw 009534.shtml

Butcher, R. (2008) *Platytheca anasima* (Elaeocarpaceae) a new, geographically restricted species from the Whicher Range, south-west Western Australia, *Nuytsia* 18: 31–37 (2008) https://florabase.dpaw.wa.gov.au/science/nuytsia/545.pdf

Department of Biodiversity, Conservation and Attractions (DBCA) (2017) Department of Parks and Wildlife Threatened and Priority Flora List 8 March 2017 https://library.dbca.wa.gov.au/static/Journals/081078e/081078-2017.03.08.pdf

Department of Biodiversity, Conservation and Attractions (DBCA) (2018a) Wildlife Conservation (Threatened Flora) Notice 2018, [Online], Government of Western Australia https://www.dpaw.wa.gov.au/images/documents/plants-animals/threatened-species/Listings/flora notice.pdf

Department of Biodiversity, Conservation and Attractions (DBCA) (2018b) Threatened ecological communities endorsed by the Minister for the Environment (June 2018) https://www.dpaw.wa.gov.au/images/plants-animals/threatened-species/threatened_ecological_communities_endorsed_by_the_minister_for_the_environment_june_2018.pdf

Department of Biodiversity, Conservation and Attractions (DBCA) (2018c) Priority Ecological Communities for Western Australia Version 27 https://www.dpaw.wa.gov.au/images/documents/plants-animals/threatened-species/Listings/priority_ecological_communities_list.pdf

Department of Biodiversity, Conservation and (DBCA) (2018d) NatureMap. http://naturemap.dec.wa.gov.au/default.aspx

Department of the Environment and Energy (DEE) (2018) EPBC Act Protected Matters Search http://www.environment.gov.au/epbc/pmst/index.html

Department of the Environment and Energy (SPRAT) (2018) Species Profile and Threats Database.

http://www.environment.gov.au/cgi-bin/sprat/public/publicthreatenedlist.pl?wanted=flora

Department of Primary Industries and Regional Development (DPIRD) (2018) Western Australia Organism List.

https://www.agric.wa.gov.au/organisms

Ecoedge (2016) Level 1 Flora and Vegetation Survey – Yalyalup Proposed Mine Site < http://epbcnotices.environment.gov.au/_entity/annotation/6ffeff8b-54c0-e711-b175-005056ba00a8/a71d58ad-4cba-48b6-8dab-f3091fc31cd5?t=1511222400335>

Environmental Protection Authority (EPA) (2016) Technical Guidance: Flora and Vegetation Surveys for Environmental Impact Assessment. Government of Western Australia, Perth. http://www.epa.wa.gov.au/sites/default/files/Policies and Guidance/EPA%20Technical%20 Guidance%20-%20Flora%20and%20Vegetation%20survey Dec13.pdf

Executive Steering Committee for Australian Vegetation Information (ESCAVI) (2017) Australian Vegetation Attribute Manual: National Vegetation Information System, Version 7.0, Department of the Environment and Heritage, Australian Capital Territory. https://www.environment.gov.au/system/files/resources/292f10e2-8670-49b6-a72d-25e892a92360/files/australian-vegetation-attribute-manual-v70.pdf

Government of Western Australia. (2018) 2017 South West Vegetation Complex Statistics. Current as of October 2017. WA Department of Biodiversity, Conservation and Attractions, Perth, https://catalogue.data.wa.gov.au/dataset/dbca

Keighery, B.J. (1994) Bushland Plant Survey: A Guide to Plant Community Survey for the Community. Wildflower Society of WA (inc). Nedlands, Western Australia

Lowrie, A. and Keneally, K.F. (2017) A taxonomic revision of the basin-like rosetted triggerplants of the Stylidium piliferum complex (Stylidiaceae) from south-western Australia, Nuytsia 28: 339–382

https://florabase.dpaw.wa.gov.au/science/nuytsia/799.pdf

Mattiske, E.M. 1 and Havel, J.J. 2 (1998) Regional Forest Agreement Vegetation Complexes Map – Collie Western Australia 1:250 000. Royal Forest Agreement. CALM

Shepherd, K.A. and Wilkins, C.F. (2015) A revision of species from the tribe *Lasiopetaleae* (Byttnerioideae: Malvaceae) with rostrate anthers, *Nuytsia* 25: 171–189 https://florabase.dpaw.wa.gov.au/science/nuytsia/753.pdf

Stenhouse, R.N. (2004) Fragmentation and internal disturbance of native vegetation reserves in the Perth metropolitan area, Western Australia, Landscape and Urban Planning, Volume 68, Issue 4, Pages 389-401

The Bush Whistler (TBW) (2013) Friends of Forrestdale Newsletter, 1st Edition, December 2013

www.sercul.org.au/wp-content/uploads/2016/12/The Bushland Whistler Ed1.pdf

Wege, J.A. (2010) *Stylidium* miscellany 1: typifications and new taxa from south-west Western Australia Nuytsia 20: 79–108 (2010) https://florabase.dpaw.wa.gov.au/science/nuytsia/594.pdf

Western Australian Herbarium (WAH) (2018) Florabase – the Western Australian Flora, [Online], Government of Western Australia, Available from: http://florabase.dpaw.wa.gov.au/

Wilde, S.A. and Walker, I.W. (1982) Collie, Western Australia, 1:250 000 geological series explanatory notes. Sheet SI/50-06. Geological Survey of Western Australia 1v.

APPENDIX A: SUMMARY OF VASCULAR PLANTS RECORDED WITHIN SURVEY AREA

+ = Recorded on site

* = Introduced species

			Site								
Family Name	Status	Species	06	09	11	14	17	19	20	21	Opp
Apiaceae		Daucus glochidiatus		+				+		+	
Asparagaceae		Lomandra sericea	+								
		Lomandra sp.	+	+	+	+	+	+			
		Thysanotus arenarius				+		+			
Asteraceae	*	Hypochaeris glabra	+	+		+	+		+		
		Lagenophora huegelii	+		+			+			
		Rhodanthe citrina	+								+
	*	Ursinia anthemoides	+		+	+	+	+			
Campanulaceae		Lobelia tenuior							+		
	*	Wahlenbergia capensis						+			
Caryophyllaceae	*	Petrorhagia dubia						+			
Celastraceae		Stackhousia monogyna									+
Colchicaceae		Burchardia congesta								+	
Cyperaceae		Tetraria sp. Jarrah Forest	+	+	+	+	+	+		+	
Dilleniaceae		Hibbertia amplexicaulis	+		+						
		Hibbertia hypericoides subsp. hypericoides	+	+	+	+	+	+	+	+	
		Hibbertia mylnei	+	+	+		+				
Droseraceae		Drosera stolonifera	+								
Elaeocarpaceae		Tetratheca hirsuta subsp. viminea			+	+					
Ericaceae		? Conostephium pendulum							+		
Fabaceae	*	Acacia iteaphylla								+	
		Bossiaea eriocarpa	+								
		Gompholobium preissii			+						
		Hovea elliptica	+	+			+				

Family Name	Status	Species	Site 06	Site 09	Site 11	Site 14	Site 17	Site 19	Site 20	Site 21	Орр
Goodeniaceae		Goodenia eatoniana					+		+	+	
		Leschenaultia biloba		+	+				+	+	
		Scaevola calliptera	+		+			+			
Hemerocallidaceae		Agrostocrinum scabrum subsp. scabrum					+				
		Caesia micrantha						+			
		Johnsonia lupulina								+	
		Tricoryne elatior					+		+		
Iridaceae		Patersonia occidentalis	+	+					+		
Myrtaceae		Agonis flexuosa				+					
		Calothamnus sanguineus							+		
		Corymbia calophylla	+	+	+	+	+	+	+	+	
		Eucalyptus marginata	+	+	+	+	+	+	+	+	
		Hypocalymma robustum	+				+				
		Kunzea glabrescens	+	+	+						
		Melaleuca thymoides							+		
Orchidaceae		Orchidaceae sp.					+				
Poaceae	*	Aira cupaniana	+							+	
		Amphipogon amphipogonoides					+			+	
	*	Briza maxima	+	+	+	+	+			+	
		Poaceae sp.				+					
		Rytidosperma setaceum			+						
Polygalaceae		Comesperma calymega			+	+			+		
Primulaceae		Lysimachia arvensis						+			
Proteaceae		Banksia dallanneyi subsp. dallanneyi	+	+			+		+	+	
		Banksia grandis	+								
		Hakea amplexicaulis	+	+	+	+			+		
		Hakea lissocarpha									+

Family Name	Status	Species	Site 06	Site 09	Site 11	Site 14	Site 17	Site 19	Site 20	Site 21	Орр
Tamily Ivame	Status	Xylomelum occidentale	00	0)	- 11	1.7	1,	17	+	21	Орр
Restionaceae		Desmocladus fasciculatus		+	+		+	+		+	
Rubiaceae		Opercularia hispidula		+			+				
Rutaceae		Boronia dichotoma	+	+	+	+		+	+	+	
Stylidiaceae		Levenhookia pusilla	+	+	+			+			
		Stylidium ciliatum									+
Thymelaeceae		Pimelea sp.			+						
Violaceae		Hybanthus calycinus		+	+						
Xanthorrhoeaceae		Xanthorrhoea gracilis		+	+	+					
		Xanthorrhoea preissii	+	+	+	+	+	+	+	+	
Zamiaceae		Macrozamia riedlei								+	

APPENDIX B: RELEVÉ AND OPPORTUNISTIC DATA

Lomandra sp.

Rhodanthe citrina

Tetraria sp. Jarrah Forest

Hypocalymma robustum Scaevola calliptera Boronia dichotoma

Banksia dallanneyi subsp. dallanneyi

Name: STY Site: 06 Datum: GDA 94 Easting: 0382777

Date: 14/11/2018 Soil: Sandy loam Northing: 6290769

<u>Vegetation description</u> Time since fire: >3

Eucalyptus marginata and Corymbia calophylla, Banksia grandis and Kunzea glabra over Xanthorrhoea preissii



Vegetation Condition: Very good Disturbance type: Weeds

	10 10 15 15 15	%	
<u>Dominants</u>	Height (m)	cover	Comments
Eucalyptus marginata	7.1	5	
Corymbia calophylla	7.1	20	
Kunzea glabrescens	3.5	2	
Xanthorrhoea preissii	1.2	8	
Banksia grandis	6	10	
Additional Species			
Hibbertia hypericoides			
Hakea amplexicaulis			
Briza maxima			Weed
Lagenophora huegelii			
Hovea elliptica			
Patersonia occidentalis			
Hibbertia amplexicaulis			
Lomandra sericea			
Ursinia anthemoides			Weed
Bossiaea eriocarpa			
Drosera stolonifera			
Hypochaeris glabra			Weed
Levenhookia pusilla			
Aira cupaniana			Weed
Hibbertia mylnei			

Name: STY Site: 09 Datum: GDA 94 Easting: 0383010

Date: 14/11/2018 Soil: Grey sandy loam Northing: 6290749

<u>Vegetation description</u> Time since fire: >3

Eucalyptus marginata and Corymbia calophylla over Kunzea glabra over Xanthorrhoea preissii and Hibbertia hypericoides



Vegetation Condition: Very good **Disturbance type:** Weeds, tracks nearby, plantation nearby

Weed

Sterile

		%	
<u>Dominants</u>	Height (m)	cover	Comments
Eucalyptus marginata	>10	20	
Corymbia calophylla	>10	5	
Kunzea glabrescens	4	10	
Xanthorrhoea preissii	1.2	4	
Hibbertia hypericoides	0.3	2	
Additional Species			
Hakea amplexicaulis			
Banksia dallanneyi subsp. dallanneyi			
Hibbertia mylnei			
Desmocladus fasciculatus			
Hypochaeris glabra			Weed

Boronia dichotoma
Hakea amplexicaulis
Daucus glochidiatus
Levenhookia pusilla
Xanthorrhoea gracilis
Hovea elliptica
Tetraria sp. Jarrah Forest
Leschenaultia biloba
Patersonia occidentalis
Hybanthus calycinus
Opercularia hispidula

Briza maxima

Lomandra sp.

Hybanthus calycinus

Rytidosperma setaceum

Comesperma calymega

Tetratheca hirsuta subsp. viminea

Name: STY Site: 12 Datum: GDA 94 Easting: 0383030
Date: 14/11/2018 Soil: Brown/grey sandy loam Northing: 6290745

<u>Vegetation description</u> Time since fire: >3

Eucalyptus marginata and Corymbia calophylla over Kunzea glabra over Xanthorrhoea gracilis and Hibbertia hypericoides



Vegetation Condition: Very good
Disturbance type: Weeds, tracks nearby, plantation nearby

<u>Dominants</u>	Height (m)	% cover	Comments
Eucalyptus marginata	15	25	
Corymbia calophylla	12	10	
Kunzea glabrescens	3.5	3	
Xanthorrhoea gracilis	0.8	2	
Hibbertia hypericoides	0.4	1	
Additional Species			
Boronia dichotoma			
Leschenaultia biloba			
Hibbertia mylnei			
Hakea amplexicaulis			
Scaevola calliptera			
Hibbertia amplexicaulis			
Desmocladus fasciculatus			
Lagenophora huegelii			
Levenhookia pusilla			
Ursinia anthemoides			Weed
Lomandra sp.			Sterile
Hibbertia mylnei			
Tetraria sp. Jarrah Forest			
Briza maxima			Weed

Pimelea sp. Needs flowers

Gompholobium preissii

Xanthorrhoea preissii

Name: STY Site: 14 Datum: GDA 94 Easting: 0383097
Date: 14/11/2018 Soil: Brown loamy sand Northing: 6290728
Vegetation description Time since fire: >3

Eucalyptus marginata and Corymbia calophylla over Xanthorrhoea preissii



Vegetation Condition: Good **Disturbance type:** Plantation nearby, tracks, weeds

<u>Dominants</u>	Height (m)	% cover	Comments
Eucalyptus marginata	15	25	
Corymbia calophylla	14	10	
Xanthorrhoea preissii	0.9	6	
Additional Species			
Hakea amplexicaulis			
Hibbertia hypericoides			
Tetraria sp. Jarrah Forest			
Lomandra sp.			
Boronia dichotoma			
Briza maxima			Weed
Hypochaeris glabra			Weed
Comesperma calymega			
Thysanotus arenarius			
Xanthorrhoea gracilis			
Poaceae sp.			Sterile
Agonis flexuosa			1 only
Ursinia anthemoides			Weed
Tetratheca hirsuta subsp. viminea			

Name: STY Site: 17 Datum: GDA 94 Easting: 0383406

Date: 14/11/2018 Soil: Brown loamy Northing: 6290682

<u>Vegetation description</u> Time since fire: >3

Height

(m)

14

%

cover

35

Eucalyptus marginata and Corymbia calophylla over Hibbertia hypericoides



Vegetation Condition: Good **Disturbance type:** Tracks and plantation nearby

<u>Dominants</u>
Eucalyptus marginata
Corymbia calophylla
Hibbertia hypericoides
Additional Species
Banksia grandis
Hypocalymma robustum
Lomandra sp.
Desmocladus fasciculatus
Xanthorrhoea preissii
Banksia dallanneyi subsp. dallanneyi
Tetraria sp. Jarrah Forest
Briza maxima
Hovea elliptica
Hypochaeris glabra
Opercularia hispidula
Goodenia eatoniana
Agrostocrinum scabrum
_

Tricoryne elatior

Ursinia anthemoides Orchidaceae sp. Hibbertia mylnei

Amphipogon amphipogonoides

12	5			
0.4	8			
		c		
		Sterile		
		Weed		
		Too dead	d to work out genu	S

Comment

S

Name: STY Site: 19 Datum: GDA 94 Easting: 0382981
Date: 14/11/2018 Soil: Brown loamy Northing: 6290568
Vegetation description Time since fire: >3

Eucalyptus marginata and Corymbia calophylla over Xanthorrhoea preissii



Vegetation Condition: Good **Disturbance type:** Tracks and

plantation

Particular	Height	%	Comment
<u>Dominants</u>	(m)	cover	S
Eucalyptus marginata	15	20	
Corymbia calophylla	10	8	
Xanthorrhoea preissii	0.8	8	
Additional Species			
Hibbertia hypericoides			
Scaevola calliptera			
Desmocladus fasciculatus			
Tetraria sp. Jarrah Forest			
Lomandra sp.			
Daucus glochidiatus			
Lagenophora huegelii			
Boronia dichotoma			
Levenhookia pusilla			
Thysanotus arenarius			
Lysimachia arvensis			Weed
Caesia micrantha			
Ursinia anthemoides			
Wahlenbergia capensis			Weed
Petrorhagia dubia			Weed

Name: STY Site: 20 Datum: GDA 94 Easting: 0382962
Date: 14/11/2018 Soil: Brown loamy Northing: 6290365
Vegetation description Time since fire: >3

Eucalyptus marginata and Corymbia calophylla over Xanthorrhoea preissii



Vegetation Condition: Very good **Disturbance type:** Tracks, operations and plantations nearby

<u>Dominants</u>
Eucalyptus marginata
Corymbia calophylla
Xanthorrhoea preissii
Additional Species
Hibbertia hypericoides
Patersonia occidentalis
Hakea amplexicaulis
Boronia dichotoma
Banksia dallanneyi subsp. dallanneyi
Leschenaultia biloba
Amphipogon amphipogonoides
Goodenia eatoniana
Tricoryne elatior
Hypochaeris glabra
Comesperma calymega
? Conostephium pendulum
Lobelia tenuior
Melaleuca thymoides
Xylomelum occidentale

Calothamnus sanguineus

 Height (m)
 % Comment cover s

 15
 20

 11
 5

 0.8
 4

Sterile

Name: STY Site: 21 Datum: GDA 94 Easting: 0383220
Date: 14/11/2018 Soil: Brown loamy Northing: 6290473
Vegetation description Time since fire: >3

Eucalyptus marginata and Corymbia calophylla over Xanthorrhoea preissii



Vegetation Condition: Very

good

Disturbance type: Plantations,

tracks nearby

	Height	%	Comment
<u>Dominants</u>	(m)	cover	S
Eucalyptus marginata	14	10	
Corymbia calophylla	11	20	
Xanthorrhoea preissii	0.5	5	
Additional Species			
Hibbertia hypericoides			
Boronia dichotoma			
Daucus glochidiatus			
Johnsonia lupulina			
Tetraria sp. Jarrah Forest			
Desmocladus fasciculatus			
Briza maxima			
Leschenaultia biloba			
Banksia dallanneyi subsp. dallanneyi			
Burchardia congesta			
Aira cupaniana			Weed
Goodenia eatoniana			
Macrozamia riedlei			
Acacia iteaphylla			Weed

APPENDIX C: NATUREMAP SEARCH RESULTS FOR THREATENED AND PRIORITY SPECIES THAT HAVE POTENTIAL TO OCCUR WITHIN SURVEY AREA



NatureMap Species Report

Created By Guest user on 07/11/2018

Kingdom Plantae

Current Names Only Yes

Core Datasets Only Yes

Method 'By Circle'

Centre 115° 44' 26" E,33° 31' 07" S

Buffer 10km

Group By Family

Family	Species	Records
Amaranthaceae	3	
Amaryllidaceae	3	3
Anarthriaceae	2	9
Apiaceae	10	36
Apocynaceae	2	2
Apodanthaceae Aponogetonaceae	1	23
Araliaceae	3	2
Asparagaceae	25	58
Asteraceae	26	32
Bignoniaceae	1	
Boraginaceae	1	•
Brassicaceae	4	:
Bryaceae	1	
Campanulaceae	2	:
Caprifoliaceae	1	
Caryophyllaceae	5 3	
Casuarinaceae Celastraceae	3	(
Centrolepidaceae	3	
Chenopodiaceae	2	
Colchicaceae	3	
Cupressaceae	1	:
Cyperaceae	24	4:
Dasypogonaceae	4	
Dennstaedtiaceae	1	;
Dicranaceae	2	:
Dilleniaceae	14	38
Droseraceae	11	14
Elaeocarpaceae	5	1
Elatinaceae Ericaceae	1 25	7 [.]
Encaceae Euphorbiaceae	8	,
Fabaceae	81	220
Gentianaceae	2	22
Geraniaceae	2	3
Goodeniaceae	8	46
Haemodoraceae	12	37
Haloragaceae	3	7
Hemerocallidaceae	8	1
Hydatellaceae	2	1
Hydrocharitaceae	1	
Hypoxidaceae Iridaceae	1 21	5 ⁻
Juncaceae	3	3
Lamiaceae	4	
Lauraceae	4	
Linaceae	1	
Lindsaeaceae	1	;
Loganiaceae	2	:
Loranthaceae	1	;
Malvaceae	5	
Marsileaceae	2	
Menyanthaceae	2	
Myrtaceae	43	10
Olacaceae	1	:
Onagraceae Orabidaaaa	1 31	5
Orchidaceae Orobanchaceae	1	3
Orobanchaceae Oxalidaceae	1	
Phytolaccaceae	1	
Pittosporaceae	3	
Plantaginaceae	2	
Poaceae	41	5
Podocarpaceae	1	:
Polygalaceae	1	
Polygonaceae	3	;
Pottiaceae	1	
Primulaceae	1	45
Proteaceae	46	15
Disciplination	1	
Pteridaceae		
Racopilaceae	1	
		2





	O
4	6
7	22
2	3
1	1
7	13
22	39
1	1
1	1
2	4
9	42
2	6
	9 2 1 1 22 7 1





Amaranthacea	lame ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Quer Area
	ae				
1.	2648	Alternanthera denticulata (Lesser Joyweed)			
2.	2652	Alternanthera nodiflora (Common Joyweed)			
3.	2655	Amaranthus albus (Tumbleweed)	Υ		
Amaryllidacea	ae				
4.		Leucojum aestivum (Snowflake)	Υ		
5.		Narcissus pseudonarcissus	Y		
6.		Narcissus tazetta subsp. italicus	Y		
A t l		•			
Anarthriaceae		Assertation and Utom			
7.		Anarthria prolifera			
8.	1097	Lyginia barbata			
Apiaceae					
9.	6203	Actinotus glomeratus			
10.	6245	Pentapeltis peltigera			
11.	6249	Platysace compressa (Tapeworm Plant)			
12.	6253	Platysace filiformis			
13.		Platysace tenuissima			
14.		Schoenolaena juncea			
15.		Xanthosia atkinsoniana			
16.		Xanthosia candida			
17.		Xanthosia ciliata			
18.	6289	Xanthosia huegelii			
Apocynaceae					
19.	6587	Gomphocarpus fruticosus (Narrowleaf Cottonbush)	Υ		
20.		Vinca major (Blue Periwinkle)	Y		
			·		
Apodanthacea	ae				
21.	2408	Pilostyles hamiltonii			
Aponogetona	ceae				
22.		Aponogeton hexatepalus (Stalked Water Ribbons)		P4	
		· • • • • • • • • • • • • • • • • • • •		• •	
Araliaceae					
23.		Hydrocotyle callicarpa (Small Pennywort)			
24.		Trachymene ornata (Spongefruit)			
25.	6280	Trachymene pilosa (Native Parsnip)			
Asparagaceae	•				
26.		Asparagus asparagoides (Bridal Creeper)	Υ		
27.	1217	Chamaexeros serra (Little Fringe-leaf)			
28.	43505	Hyacinthoides non-scripta	Υ		
29.	13562	Lachenalia aloides	Υ		
30.	11464	Laxmannia sessiliflora subsp. australis			
31.	1223	Lomandra caespitosa (Tufted Mat Rush)			
32.		Lomandra drummondii			
33.	1228	Lomandra hermaphrodita			
34.		Lomandra nigricans			
35.		Lomandra pauciflora			
36.		Lomandra preissii			
37.		Lomandra purpurea (Purple Mat Rush)			
38.		Lomandra sericea (Silky Mat Rush)			
		Lomandra sonderi			
39.		Lomandra spartea			
39. 40.	1245	•			
		Lomandra suaveolens			
40. 41.	1246	Lomandra suaveolens Lomandra whicherensis		P3	
40. 41. 42.	1246 33298	Lomandra whicherensis	Υ	P3	
40. 41. 42. 43.	1246 33298 1372	Lomandra whicherensis Ornithogalum arabicum (Lesser Cape Lily)	Y	P3	
40. 41. 42. 43. 44.	1246 33298 1372 1318	Lomandra whicherensis Ornithogalum arabicum (Lesser Cape Lily) Thysanotus arbuscula	Y	P3	
40. 41. 42. 43.	1246 33298 1372 1318 1319	Lomandra whicherensis Ornithogalum arabicum (Lesser Cape Lily) Thysanotus arbuscula Thysanotus arenarius	Y	P3	
40. 41. 42. 43. 44. 45.	1246 33298 1372 1318 1319 1328	Lomandra whicherensis Ornithogalum arabicum (Lesser Cape Lily) Thysanotus arbuscula Thysanotus arenarius Thysanotus dichotomus (Branching Fringe Lily)	Y	P3	
40. 41. 42. 43. 44. 45. 46.	1246 33298 1372 1318 1319 1328 1339	Lomandra whicherensis Ornithogalum arabicum (Lesser Cape Lily) Thysanotus arbuscula Thysanotus arenarius Thysanotus dichotomus (Branching Fringe Lily) Thysanotus multiflorus (Many-flowered Fringe Lily)	Y	P3	
40. 41. 42. 43. 44. 45. 46. 47.	1246 33298 1372 1318 1319 1328 1339 1344	Lomandra whicherensis Ornithogalum arabicum (Lesser Cape Lily) Thysanotus arbuscula Thysanotus arenarius Thysanotus dichotomus (Branching Fringe Lily) Thysanotus multiflorus (Many-flowered Fringe Lily) Thysanotus pauciflorus (Few Flowered Fringe Lily)	Y	P3	
40. 41. 42. 43. 44. 45. 46. 47. 48.	1246 33298 1372 1318 1319 1328 1339 1344	Lomandra whicherensis Ornithogalum arabicum (Lesser Cape Lily) Thysanotus arbuscula Thysanotus arenarius Thysanotus dichotomus (Branching Fringe Lily) Thysanotus multiflorus (Many-flowered Fringe Lily) Thysanotus pauciflorus (Few Flowered Fringe Lily) Thysanotus sparteus	Y	P3	
40. 41. 42. 43. 44. 45. 46. 47.	1246 33298 1372 1318 1319 1328 1339 1344	Lomandra whicherensis Ornithogalum arabicum (Lesser Cape Lily) Thysanotus arbuscula Thysanotus arenarius Thysanotus dichotomus (Branching Fringe Lily) Thysanotus multiflorus (Many-flowered Fringe Lily) Thysanotus pauciflorus (Few Flowered Fringe Lily)	Y	P3	
40. 41. 42. 43. 44. 45. 46. 47. 48.	1246 33298 1372 1318 1319 1328 1339 1344	Lomandra whicherensis Ornithogalum arabicum (Lesser Cape Lily) Thysanotus arbuscula Thysanotus arenarius Thysanotus dichotomus (Branching Fringe Lily) Thysanotus multiflorus (Many-flowered Fringe Lily) Thysanotus pauciflorus (Few Flowered Fringe Lily) Thysanotus sparteus	Y	P3	
40. 41. 42. 43. 44. 45. 46. 47. 48. 49.	1246 33298 1372 1318 1319 1328 1339 1344 1351	Lomandra whicherensis Ornithogalum arabicum (Lesser Cape Lily) Thysanotus arbuscula Thysanotus arenarius Thysanotus dichotomus (Branching Fringe Lily) Thysanotus multiflorus (Many-flowered Fringe Lily) Thysanotus pauciflorus (Few Flowered Fringe Lily) Thysanotus sparteus	Y	P3	
40. 41. 42. 43. 44. 45. 46. 47. 48. 49. 50.	1246 33298 1372 1318 1319 1328 1339 1344 1351 1354	Lomandra whicherensis Ornithogalum arabicum (Lesser Cape Lily) Thysanotus arbuscula Thysanotus arenarius Thysanotus dichotomus (Branching Fringe Lily) Thysanotus multiflorus (Many-flowered Fringe Lily) Thysanotus pauciflorus (Few Flowered Fringe Lily) Thysanotus sparteus Thysanotus tenellus		P3	

Department of Parks and Wildlife





54.		Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Query
150	54.	13354	Craspedia variabilis			700
5-7,	55.	19893	Cynara cardunculus subsp. flavescens (Artichoke Thistle, Wild Artichoke, Cardoon)	Υ		
10.00 10.0	56.	16759	Hyalosperma simplex subsp. simplex			
5.8. 3122/ Muserbarrang packetaum Y				Υ		
610						
				Y		
10. 13. 13. Clambo chicapyable						
14.1. 15.0						
64. 1776 Osteopormum cokkens Y						
15.5 15.552 Procupting process process of the				٧		
66. 1517 Profutepage granuling (Samorier Profusionina)				•		
1915 Careeria Lucialist						
6.8. 13312 Richardente pyreintuma*	67.					
17. 28/03 Senoto disachelias 17. 28/05 Senoto disachelias 18. 28/05 Senoto disachelias 28/05 Senoto di	68.	13300	Rhodanthe citrina			
17. 2085 Service multicaulis subseq multicaulis 17. 17. 17. 18.	69.	13312	Rhodanthe pyrethrum			
1908	70.	8203	Senecio diaschides			
73. 85.88 Topic barbaine (*Velour Fewinwerd) 74. 74. 82.55 Transmiser imperations (Asima Periodece) 75. 82.55 Velicorophytan Geobatum (White Cudwerd) 75. 82.55 Velicorophytan Geobatum (White Cudwerd) 77. 71.77 Pandovea pandorama	71.	20663	Senecio multicaulis subsp. multicaulis			
75. 825 Trincolous equal-vision (Abeive Centering) 9	72.	8226	Siloxerus pygmaeus			
15. 8255 Visionia antiremotoise (Unitaria) Y	73.	8248	Tolpis barbata (Yellow Hawkweed)	Υ		
Bignoniacesa	74.	8251	Trichocline spathulata (Native Gerbera)			
Bignoniaceae						
Boraginaceae 73. 6710 Helicoroplum curapaeum (Common Helicoropae) Y	76.	8257	Vellereophyton dealbatum (White Cudweed)	Υ		
Boraginaceae 73. 6710 Helicoropium curcipaeum (Common Helicoropi) Y	Bignoniace	eae				
Borasinaceae	_		Pandorea pandorana			
Prassicacese			,			
79. 3000 Brassica tourneforial (Mediterranean Tumip) Y			Heliotropium europaeum (Common Heliotrope)	Υ		
79. 3000 Brassica tourneforial (Mediterranean Tumip) Y	Draceisas					
80. 2995 Brassica x napus Y 81. 3071 Sisymbrium officinale (Hodge Mustard) Y 82. 3072 Sisymbrium orientale (Indian Hodge Mustard) Y Bryaccae 83. 32426 Rosulabryum campyliothacium Campanulaceae 84. 7405 Lobelia rarifolia *** 85. 7407 Lobelia mytidosperma (Wrinkled-seeded Lobelia) *** Caryfoliaceae 86. 7366 Centranthus macrosphon Y Caryophyllaceae 87. 2894 Monochia arecta (Erect Chickweed) Y 88. 18925 Porthologia dubla Y 89. 18935 Spenydiar avensis (Com Spurry) Y 90. 2912 Spenydiar avensis (Com Spurry) Y 91. 2915 Spenydiaria tubra (Sand Spurry) Y Casuarina eae 92. 1722 Allocasuarina humilis (Dwaf Sheoak) Celastraceae 95. 4733 Stackhousia scoparia 97. 4737 Triptercoccus brunonis (Winged Stackhousia) Centrolepia aristata (Poirted Centr			Purania to unafastii (Maditassanaan Tussia)	.,		
Bi						
Bryaceae						
Bryaceae 83. 32426 Rosulabryum campylothecium						
83 32426 Rosulebryum campylothacium	02.	0072	Giognisham Giornale (malair rieage mastara)	'		
Ref	Bryaceae					
Ref. 7405 Lobeila rayfidola Ref. 7407 Lobeila rhytidosperma (Winkled-seeded Lobeila) Ref. 7407 Lobeila rhytidosperma (Winkled-seeded Lobeila) Ref. 7366 Centranithus macrosiphon Y Ref. 7366 Centranithus macrosiphon Y Ref. 7366 Ref. 7366 Centranithus macrosiphon Y Ref. 7366	83.	32426	Rosulabryum campylothecium			
85. 7407 Lobella rhytridosperma (Wrinkled-seeded Lobelia)	Campanula	aceae				
Caryophyllaceae	84.	7405	Lobelia rarifolia			
Ref. 7366 Centranthus macrosiphon Y Caryophyllaceae 87. 2894 Moenchia erecta (Erect Chickweed) Y 88. 19825 Perorhagia dubia Y 89. 11803 Silene gallica var. quinquevulnera Y 90. 2912 Spergula arvensis (Com Spurry) Y 91. 2915 Spergularia rubra (Sand Spurry) Y Casuarinaceae 92. 1728 Allocasuarina traseriana (Sheoak, Kondil) 93. 1732 Allocasuarina thumilis (Dwarf Sheoak) 94. 1739 Allocasuarina thuycides (Horned Sheoak) 95. 4733 Stackhousia monogyna 96. 4735 Stackhousia monogyna 97. 4737 Tripterococus brunonis (Winged Stackhousia) Centrolepiaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum Y 102. 3340 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra unilfora Y 104. 12770 Burchardia congesta Y	85.	7407	Lobelia rhytidosperma (Wrinkled-seeded Lobelia)			
Ref. 7366 Centranthus macrosiphon Y Caryophyllaceae 87. 2894 Moenchia erecta (Erect Chickweed) Y 88. 19825 Perorhagia dubia Y 89. 11803 Silene gallica var. quinquevulnera Y 90. 2912 Spergula arvensis (Com Spurry) Y 91. 2915 Spergularia rubra (Sand Spurry) Y Casuarinaceae 92. 1728 Allocasuarina traseriana (Sheoak, Kondil) 93. 1732 Allocasuarina thumilis (Dwarf Sheoak) 94. 1739 Allocasuarina thuycides (Horned Sheoak) 95. 4733 Stackhousia monogyna 96. 4735 Stackhousia monogyna 97. 4737 Tripterococus brunonis (Winged Stackhousia) Centrolepiaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum Y 102. 3340 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra unilfora Y 104. 12770 Burchardia congesta Y	Caprifoliac	.020				
Recomposition Recompositio	•		Centranthus macrosinhon	v		
87. 2894 Moenchia erecta (Erect Chickweed) Y 88. 19825 Fetrorhagia dubia Y 99. 2912 Spergula arvensis (Com Spurry) Y 91. 2915 Spergularia rubra (Sand Spurry) Y 91. 2915 Spergularia rubra (Sand Spurry) Y 728 Allocasuarina fraseriana (Sheoak, Kondil) 93. 1732 Allocasuarina humilis (Dwarf Sheoak) 94. 1739 Allocasuarina humilis (Dwarf Sheoak) 95. 4733 Stackhousia monogyna 96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum Y 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba	00.	7000	Contrarting made approxi	,		
88. 19825 Petrorhagia dubia Y 89. 11803 Silene gallica var. quinquevulnera Y 90. 2912 Spergula arvensis (Corn Spury) Y 91. 2915 Spergularia rubra (Sand Spury) Y Casuarinaceae 92. 1728 Allocasuarina fraseriana (Sheoak, Kondil) 93. 1732 Allocasuarina thuyoides (Homed Sheoak) 94. 1733 Allocasuarina thuyoides (Homed Sheoak) Celastraceae 95. 4733 Stackhousia monogyna 96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepitaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodium macrospermum Y 102. 3348 Dysphania pumilio (Clammy Goosefoot) Colspan="3">Chenopodium macrospermum Y <tr< td=""><td>Caryophyll</td><td></td><td></td><td></td><td></td><td></td></tr<>	Caryophyll					
89. 11803 Silene gallica var. quinquevulnera Y 90. 2912 Spergularia arvensis (Com Spurry) Y 91. 2915 Spergularia rubra (Sand Spurry) Y Y Casuarinaceae 92. 1728 Allocasuarina fraseriana (Sheoak, Kondil) 93. 1732 Allocasuarina humilis (Dwarf Sheoak) 94. 1739 Allocasuarina humilis (Dwarf Sheoak) Celastraceae 95. 4733 Stackhousia monogyna 96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba			, ,			
90. 2912 Spergula arvensis (Corn Spurry) Y 91. 2915 Spergularia rubra (Sand Spurry) Y Casuarinaceae 92. 1728 Allocasuarina fraseriana (Sheoak, Kondil) 93. 1732 Allocasuarina humilis (Dwarf Sheoak) 94. 1739 Allocasuarina thuryoides (Horned Sheoak) Celastraceae 95. 4733 Stackhousia monogyna 96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis drummondiana 100. 134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 249 Chenopodium macrospermum 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba						
91. 2915 Spergularia rubra (Sand Spurry) Y			• • •			
Casuarinaceae 92. 1728 Allocasuarina fraseriana (Sheoak, Kondil) 93. 1732 Allocasuarina humilis (Dwarf Sheoak) 94. 1739 Allocasuarina thuyoides (Horned Sheoak) Celastraceae 95. 4733 Stackhousia monogyna 96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum y 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba						
92. 1728 Allocasuarina fraseriana (Sheoak, Kondil) 93. 1732 Allocasuarina humilis (Dwarf Sheoak) 94. 1739 Allocasuarina thuyoides (Horned Sheoak) Celastraceae 95. 4733 Stackhousia monogyna 96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba	91.	2915	Spergularia rubra (Sand Spurry)	Υ		
93. 1732 Allocasuarina humilis (Dwarf Sheoak) 94. 1739 Allocasuarina thuyoides (Horned Sheoak) Celastraceae 95. 4733 Stackhousia monogyna 96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba	Casuarina	ceae				
94. 1739 Allocasuarina thuyoides (Horned Sheoak) Celastraceae 95. 4733 Stackhousia monogyna 96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum 102. 33480 Dysphania pumillo (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora 105. 12072 Wurmbea dioica subsp. alba	92.	1728	Allocasuarina fraseriana (Sheoak, Kondil)			
Celastraceae 95. 4733 Stackhousia monogyna 96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba	93.	1732	Allocasuarina humilis (Dwarf Sheoak)			
95. 473 Stackhousia monogyna 96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba	94.	1739	Allocasuarina thuyoides (Horned Sheoak)			
95. 473 Stackhousia monogyna 96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba	Celastraco	26				
96. 4735 Stackhousia scoparia 97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum Y 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba			Stackhousia monogyna			
97. 4737 Tripterococcus brunonis (Winged Stackhousia) Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum Y 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba						
Centrolepidaceae 98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum Y 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba						
98. 1121 Centrolepis aristata (Pointed Centrolepis) 99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum Y 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba						
99. 1125 Centrolepis drummondiana 100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum Y 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba						
100. 1134 Centrolepis polygyna (Wiry Centrolepis) Chenopodiaceae 101. 2491 Chenopodium macrospermum Y 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba						
Chenopodiaceae 101. 2491 Chenopodium macrospermum Y 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba						
101. 2491 Chenopodium macrospermum Y 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba	100.	1134	Centrolepis polygyna (Wiry Centrolepis)			
101. 2491 Chenopodium macrospermum Y 102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba	Chenopodi	iaceae				
102. 33480 Dysphania pumilio (Clammy Goosefoot) Colchicaceae 103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba	-		Chenopodium macrospermum	Υ		
103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba	102.					
103. 1382 Baeometra uniflora Y 104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba	Colchiosos	20				
104. 12770 Burchardia congesta 105. 12072 Wurmbea dioica subsp. alba			Pagamatra uniflara	V		
105. 12072 Wurmbea dioica subsp. alba				Y		
			-			
	100.	12012				







Name ID Species Name

Cupressaceae 36520 Callitris acuminata (Dwarf Cypress) 106. Cyperaceae 107. 740 Baumea arthrophylla 108 13766 Caustis sp. Boyanup (G.S. McCutcheon 1706) Р3 109. 16245 Cyathochaeta teretifolia РЗ 110 792 Cyperus eragrostis (Umbrella Sedge) 822 Eleocharis acuta (Common Spikerush) 111. 112. 17605 Eleocharis keigheryi 113. 20200 Isolepis cernua var. setiformis 114. 917 Isolepis marginata (Coarse Club-rush) 919 Isolepis oldfieldiana 115. 116. 925 Lepidosperma angustatum 117. 930 Lepidosperma costale 118. 940 Lepidosperma pubisquameum 119. 944 Lepidosperma scabrum 945 Lepidosperma squamatum 120. 121. 948 Lepidosperma tetraquetrum 953 Mesomelaena graciliceps 122. 123. 11473 Mesomelaena stygia subsp. stygia 124 973 Schoenus asperocarpus (Poison Sedge) 975 Schoenus bifidus 125. 126. 978 Schoenus brevisetis 127. 984 Schoenus curvifolius 128. 1017 Schoenus subbulbosus 129. 1036 Tetraria octandra 130. 35579 Tetraria sp. Jarrah Forest (R. Davis 7391) Dasypogonaceae 131. 19309 Calectasia narragara 1218 Dasypogon bromeliifolius (Pineapple Bush) 132. 133. 1219 Dasypogon hookeri (Pineapple Bush) 134. 1221 Kingia australis (Kingia, Pulonok) Dennstaedtiaceae 41651 Pteridium esculentum subsp. esculentum 135. Dicranaceae 136. 32334 Campylopus australis 137. 32338 Campylopus introflexus Dilleniaceae 138. 5108 Hibbertia acerosa (Needle Leaved Guinea Flower) 139. 5109 Hibbertia amplexicaulis 140 5112 Hibbertia aurea 141. 5114 Hibbertia commutata 5117 Hibbertia cuneiformis (Cutleaf Hibbertia) 142. 143. 20051 Hibbertia diamesogenos 144. 5125 Hibbertia ferruginea 145. 5129 Hibbertia glomerata 5134 Hibbertia huegelii 146. 147. 5135 Hibbertia hypericoides (Yellow Buttercups) 45534 Hibbertia hypericoides subsp. hypericoides 148. 149. 5161 Hibbertia quadricolor 150 5162 Hibbertia racemosa (Stalked Guinea Flower) 5176 Hibbertia vaginata 151. Droseraceae 152. 3090 Drosera barbigera 153. 3095 Drosera erythrorhiza (Red Ink Sundew) 154. 13217 Drosera erythrorhiza subsp. erythrorhiza 155. 3102 Drosera huegelii (Bold Sundew) 48691 Drosera huegelii var. huegelii 156 157. 3108 Drosera marchantii 13209 Drosera marchantii subsp. marchantii 158 159. 3110 Drosera microphylla (Golden Rainbow) 160 3112 Drosera myriantha (Star Rainbow) 161. 8911 Drosera rosulata 162. 3131 Drosera stolonifera (Leafy Sundew) Elaeocarpaceae 33377 Platytheca anasima 163.



Conservation Code ¹Endemic To Query Area

Naturalised





164.	Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Que Area
	4524	Platytheca galioides			
165.	4535	Tetratheca hirsuta (Black Eyed Susan)			
166.	48341	Tetratheca hirsuta subsp. viminea			
167.		Tremandra diffusa			
latinaceae		-			
168.	5187	Elatine gratioloides (Waterwort)			
ricaceae					
169.	6306	Andersonia caerulea (Foxtails)			
170.		Andersonia ferricola		P1	
				PI	
171.		Andersonia involucrata			
172.		Andersonia lehmanniana			
173.		Astroloma ciliatum (Candle Cranberry)			
174.	6325	Astroloma drummondii			
175.	6334	Astroloma pallidum (Kick Bush)			
176.	6348	Conostephium pendulum (Pearl Flower)			
177.	6360	Leucopogon australis (Spiked Beard-heath)			
178.	6367	Leucopogon capitellatus			
179.	6374	Leucopogon conostephioides			
180.		Leucopogon cordatus			
181.		Leucopogon glabellus			
182.		Leucopogon obovatus			
		· -			
183.		Leucopogon oxycedrus			
184.		Leucopogon pendulus			
185.		Leucopogon pulchellus (Beard-heath)			
186.		Leucopogon reflexus (Heart-leaf Beard-heath)			
187.	29492	Leucopogon sp. Busselton (D. Cooper 243)		P2	
188.	6454	Leucopogon verticillatus (Tassel Flower)			
189.	6456	Lysinema ciliatum (Curry Flower)			
190.	34736	Lysinema pentapetalum			
191.	6464	Needhamiella pumilio			
192.	31931	Sphenotoma capitata			
193.		Styphelia tenuiflora (Common Pinheath)			
.00.	00	Stypholia tohamora (Common Filmodally			
uphorbiac	eae				
194.	4585	Amperea ericoides			
195.	16493	Calycopeplus oligandrus			
196.	4662	Monotaxis grandiflora (Diamond of the Desert)			
197.		Monotaxis occidentalis			
198.		Ricinocarpos cyanescens			
199.		Ricinus communis (Castor Oil Plant)	Υ		
200.			ı		
		Stachystemon vermicularis			
201.	20537	Stachystemon virgatus			
abaceae					
	15466	Acacia applanata			
202.		Acacia applanata			
202. 203.	3247	Acacia browniana			
202. 203. 204.	3247 11377	Acacia browniana Acacia browniana var. obscura			
202.203.204.205.	3247 11377 11229	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis		P3	
202.203.204.205.206.	3247 11377 11229 11192	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans		Р3	
202.203.204.205.	3247 11377 11229 11192	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis		P3	
202.203.204.205.206.	3247 11377 11229 11192 3331	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans		P3 P4	
202. 203. 204. 205. 206. 207.	3247 11377 11229 11192 3331 3339	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle)			
202. 203. 204. 205. 206. 207. 208.	3247 11377 11229 11192 3331 3339 3374	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis	Y		
202. 203. 204. 205. 206. 207. 208. 209.	3247 11377 11229 11192 3331 3339 3374 18217	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii	Y		
202. 203. 204. 205. 206. 207. 208. 209. 210.	3247 11377 11229 11192 3331 3339 3374 18217 3410	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliiformis Acacia huegelli Acacia iteaphylla Acacia lateriticola	Y		
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliiformis Acacia huegelli Acacia iteaphylla Acacia lateriticola Acacia mooreana	Y		
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliiformis Acacia huegelli Acacia iteaphylla Acacia lateriticola Acacia mooreana Acacia myrtifolia	Y		
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia mooreana Acacia myrtifolia Acacia nervosa (Rib Wattle)	Y		
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia mooreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata	Y		
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia mooreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata Acacia preissiana	Y		
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia mooreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata	Y		
203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464 3496	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia mooreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata Acacia preissiana	Y		
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464 3496 3502	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia mooreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata Acacia preissiana Acacia pulchella (Prickly Moses)	Y		
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464 3496 3502 15481 15483	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia mooreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata Acacia preissiana Acacia pulchella (Prickly Moses) Acacia pulchella var. glaberrima	Y		
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464 3496 3502 15481 15483 3537	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia moreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata Acacia pulchella (Prickly Moses) Acacia pulchella var. glaberrima Acacia pulchella var. pulchella Acacia semitrullata	Y	P4	
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464 3496 3502 15481 15483 3537 3557	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia moreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata Acacia preissiana Acacia pulchella (Prickly Moses) Acacia pulchella var. glaberrima Acacia semitrullata Acacia semitrullata Acacia stenoptera (Narrow Winged Wattle)	Y	P4	
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464 3496 3502 15481 15483 3537 3557	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia moreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata Acacia preissiana Acacia pulchella (Prickly Moses) Acacia pulchella var. glaberrima Acacia semitrullata Acacia semitrullata Acacia stenoptera (Narrow Winged Wattle) Acacia teretifolia	Y	P4	
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221. 222.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464 3496 3502 15481 15483 3537 3557 3574	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia mooreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata Acacia preissiana Acacia pulchella (Prickly Moses) Acacia pulchella var. glaberrima Acacia semitrullata Acacia semitrullata Acacia teratifolia Acacia teratifolia Acacia teratifolia Acacia teratifolia Acacia teratifolia Acacia teragonocarpa	Y	P4	
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221. 222. 223. 224.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464 3496 3502 15481 15483 3537 3557 3574 3576 3591	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia moreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata Acacia preissiana Acacia pulchella (Prickly Moses) Acacia pulchella var. glaberrima Acacia semitrullata Acacia semitrullata Acacia tertifolia Acacia tertifolia Acacia tertifolia Acacia tertifolia Acacia tertifolia Acacia tertigonocarpa Acacia urophylla	Y	P4	
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221. 222. 223. 224. 225.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464 3496 3502 15481 15483 3537 3557 3574 3576 3591	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia mooreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata Acacia preissiana Acacia pulchella (Prickly Moses) Acacia pulchella var. glaberrima Acacia semitrullata Acacia semitrullata Acacia teratifolia Acacia teratifolia Acacia teratifolia Acacia teratifolia Acacia teratifolia Acacia teragonocarpa	Y	P4	
202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221. 222. 223. 224.	3247 11377 11229 11192 3331 3339 3374 18217 3410 3448 3453 3454 3464 3496 3502 15481 15483 3537 3557 3574 3576 3591 15487	Acacia browniana Acacia browniana var. obscura Acacia drummondii subsp. affinis Acacia drummondii subsp. elegans Acacia extensa (Wiry Wattle) Acacia flagelliformis Acacia huegelii Acacia iteaphylla Acacia lateriticola Acacia moreana Acacia myrtifolia Acacia nervosa (Rib Wattle) Acacia obovata Acacia preissiana Acacia pulchella (Prickly Moses) Acacia pulchella var. glaberrima Acacia semitrullata Acacia semitrullata Acacia tertifolia Acacia tertifolia Acacia tertifolia Acacia tertifolia Acacia tertifolia Acacia tertigonocarpa Acacia urophylla	Y	P4	







	ame ID	Species Name N	laturalised	Conservation Code	¹ Endemic To Query Area
228.	3689	Aotus intermedia			
229.	3710	Bossiaea eriocarpa (Common Brown Pea)			
230.	3714	Bossiaea ornata (Broad Leaved Brown Pea)			
231.	3717	Bossiaea pulchella			
232.	3718	Bossiaea rufa			
233.	8971	Chorizema cordatum			
234.	3757	Chorizema glycinifolium			
235.	13107	Chorizema retrorsum			
236.	3761	Chorizema rhombeum			
237.	19747	Daviesia decurrens subsp. decurrens			
238.	3808	Daviesia elongata		T	
239.	11879	Daviesia hakeoides subsp. hakeoides			
240.	3817	Daviesia inflata			
241.	3832	Daviesia physodes			
242.	3835	Daviesia preissii			
243.	3839	Daviesia rhombifolia			
244.	19852	Dillwynia sp. Capel (P.A. Jurjevich 1771)		P1	
245.	3880	Eutaxia virgata			
246.	3891	Gastrolobium bilobum (Heart Leaf Poison)			
247.	20512	Gastrolobium praemorsum			
248.	19733	Gastrolobium retusum			
249.	30453	Gastrolobium sp. Yoongarillup (S.Dilkes s.n. 1/9/1969)		P1	
250.	20474	Gastrolobium whicherense		P2	
251.	3936	Genista linifolia (Flaxleaf Broom)	Υ		
252.	3948	Gompholobium capitatum			
253.	10909	Gompholobium confertum			
254.	19216	Gompholobium cyaninum			
255.	3950	Gompholobium knightianum			
256.	3951	Gompholobium marginatum			
257.	3954	Gompholobium polymorphum			
258.	3955	Gompholobium preissii			
259.	3956	Gompholobium shuttleworthii			
260.	3957	Gompholobium tomentosum (Hairy Yellow Pea)			
261.	3964	Hovea chorizemifolia (Holly-leaved Hovea)			
262.	3968	Hovea trisperma (Common Hovea)			
263.	12907	Hovea trisperma var. grandiflora			
264.		Hovea trisperma var. trisperma			
265.		Jacksonia horrida			
266.	4018	Jacksonia lehmannii			
267.	4036	Kennedia carinata			
268.	4037	Kennedia coccinea (Coral Vine)			
269.	4044	Kennedia prostrata (Scarlet Runner)			
270.		Paraserianthes lophantha subsp. lophantha			
271.	4177	Pultenaea ochreata			
272.	4180	Pultenaea radiata			
273.	4183	Pultenaea skinneri (Skinner's Pea)		P4	
274.		Pultenaea verruculosa			
275.		Sphaerolobium drummondii			
276.		Sphaerolobium macranthum			
277.		Sphaerolobium medium			
278.		Sphaerolobium scabriusculum			
279.		Sphaerolobium vimineum (Leafless Globe Pea)			
280.		Trifolium ligusticum (Ligurian Clover)	Υ		
281.		Ulex europaeus (Gorse)	Y		
282.		Vicia sativa subsp. nigra	Y		
		• •			
Gentianaceae					
283.		Centaurium erythraea (Common Centaury)	Υ		
284.	6543	Cicendia filiformis (Slender Cicendia)	Υ		
Geraniaceae					
285.	4332	Erodium botrys (Long Storksbill)	Υ		
		Geranium dissectum (Cutleaf Cranesbill)	Y		
286.		,	•		
286.					
Goodeniaceae		Dampiera linearis (Common Dampiera)			
Goodeniaceae 287.					
Goodeniaceae	7505	Goodenia eatoniana			
Goodeniaceae 287. 288. 289.	7505 19285	Goodenia pulchella subsp. Wheatbelt (L.W. Sage & F. Hort 795)			
Goodeniaceae 287. 288. 289. 290.	7505 19285				
Goodeniaceae 287. 288. 289.	7505 19285 13165 7568	Goodenia pulchella subsp. Wheatbelt (L.W. Sage & F. Hort 795) Goodenia pusilla Lechenaultia biloba (Blue Leschenaultia)			
Goodeniaceae 287. 288. 289. 290. 291. 292.	7505 19285 13165 7568 7574	Goodenia pulchella subsp. Wheatbelt (L.W. Sage & F. Hort 795) Goodenia pusilla Lechenaultia biloba (Blue Leschenaultia) Lechenaultia floribunda (Free-flowering Leschenaultia)			
Goodeniaceae 287. 288. 289. 290. 291.	7505 19285 13165 7568 7574	Goodenia pulchella subsp. Wheatbelt (L.W. Sage & F. Hort 795) Goodenia pusilla Lechenaultia biloba (Blue Leschenaultia)			



	Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Query Area
294.	7665	Velleia trinervis			
Haemodora	ceae				
295.	1411	Anigozanthos manglesii (Mangles Kangaroo Paw, Kurulbrang)			
296.		Conostylis aculeata (Prickly Conostylis)			
297.		Conostylis serrulata			
298.		Conostylis setigera (Bristly Cottonhead)			
299.		Conostylis setigera subsp. setigera			
300.		Haemodorum laxum			
301. 302.		Haemodorum sparsiflorum Haemodorum apiactum (Mardia)			
302.		Haemodorum spicatum (Mardja) Phlebocarya ciliata			
304.		Phlebocarya filifolia			
305.		Tribonanthes brachypetala			
306.		Tribonanthes longipetala			
		3,7			
Haloragace					
307.		Glischrocaryon angustifolium			
308.		Gonocarpus paniculatus			
309.	6189	Myriophyllum crispatum			
Hemerocalli	idaceae				
310.	23474	Agrostocrinum hirsutum			
311.		Agrostocrinum scabrum (Blue Grass Lily)			
312.		Caesia micrantha (Pale Grass Lily)			
313.		Corynotheca micrantha var. elongata			
314.		Hodgsoniola junciformis			
315.		Johnsonia acaulis			
316. 317.		Johnsonia lupulina (Hooded Lily)			
		Tricoryne tenella			
Hydatellace	ae				
318.	1139	Trithuria bibracteata			
319.	1141	Trithuria submersa			
Hydrocharit	aceae				
320.		Ottelia ovalifolia (Swamp Lily)			
Uvnovidooo					
Hypoxidace 321.		Pauridia occidentalis var. quadriloba			
	43702	r adridia occidentalis var. quadriloba			
Iridaceae					
322.		Babiana angustifolia	Υ		
323.		Ferraria crispa (Black Flag)	Y		
324.		Freesia alba x leichtlinii	Y		.,
325. 326.		Gladiolus communis subsp. byzantinus	Y		Υ
320.		Gladiolus tristis (Largeflower Gladiolus) Gladiolus undulatus (Wild Gladiolus)	Y		
328.		Ixia maculata (Yellow Ixia)	Y		
329.		Ixia paniculata	Y		
330.		Ixia polystachya (Variable Ixia)	Y		
331.		Moraea flaccida (One-leaf Cape Tulip)	Y		
332.		Orthrosanthus laxus var. laxus (Morning Iris)			
333.		Patersonia babianoides			
334.	1550	Patersonia occidentalis (Purple Flag, Koma)			
335.	1553	Patersonia umbrosa (Yellow Flags)			
336.	11550	Patersonia umbrosa var. xanthina (Yellow Flags)			
337.		Romulea rosea var. communis	Υ		
338.		Sisyrinchium exile	Υ		
339.		Sparaxis bulbifera	Y		
340.		Sparaxis pillansii (Harlequin Flower)	Y		
341.		Tritonia crocata	Y		
342.	13103	Watsonia borbonica	Υ		
Juncaceae					
343.	1180	Juncus capitatus (Capitate Rush)	Υ		
344.	1186	Juncus microcephalus	Υ		
345.	1198	Luzula meridionalis (Field Woodrush)			
Lamiaceae					
346.	6855	Hemigenia humilis			
347.		Hemigenia pritzelii			
348.		Lavandula stoechas subsp. stoechas	Υ		
349.	6883	Mentha pulegium (Pennyroyal)	Υ		







	Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Que
Lauraceae					
350.	2952	Cassytha glabella (Tangled Dodder Laurel)			
351.	2957	Cassytha racemosa (Dodder Laurel)			
352.	11242	Cassytha racemosa forma pilosa			
353.	11799	Cassytha racemosa forma racemosa			
		,			
Linaceae					
354.	4363	Linum trigynum (French Flax)	Υ		
Lindsaeacea					
355.		Lindsaea linearis (Screw Fern)			
000.	00	Emadada imodno (Gorow i Giri)			
Loganiaceae	•				
356.	46316	Orianthera serpyllifolia subsp. angustifolia			
357.	46256	Orianthera wendyae		P1	
	_				
Loranthacea					
358.	2401	Nuytsia floribunda (Christmas Tree, Mudja)			
Malvaceae					
359.	10915	Brachychiton populneus (Kurrajong)	Υ		
360.		Lasiopetalum laxiflorum	•	P3	
361.				r o	
		Lasiopetalum occidentale Thomasia grandiflora // argo Flowored Thomasia)			
362.		Thomasia grandiflora (Large Flowered Thomasia)			
363.	5086	Thomasia macrocalyx			
Marsileaceae	•				
364.		Marsilea drummondii (Common Nardoo)			
365.		Pilularia novae-hollandiae (Austral Pillwort)			
000.		Thatana notae nonanalae (Hadaan minory)			
Menyanthace	eae				
366.	36181	Ornduffia parnassifolia			
367.	36200	Ornduffia submersa		P4	
Myrtaceae					
368.	5315	Actinodium cunninghamii (Albany Daisy)			
369.	17202	Agonis flexuosa var. flexuosa			
370.	36441	Babingtonia camphorosmae (Camphor Myrtle)			
371.	5415	Calothamnus lateralis			
372.	5429	Calothamnus sanguineus (Silky-leaved Blood flower, Pindak)			
373.		Calytrix flavescens (Summer Starflower)			
374.		Calytrix tetragona (Common Fringe-myrtle)			
375.		Corymbia calophylla (Marri)			
376.		Corymbia haematoxylon (Mountain Marri)	V		
377.		Corymbia maculata	Y	_	
378.		Darwinia whicherensis		Т	
379.	13950	Eremaea asterocarpa subsp. asterocarpa			
380.	14104	Eremaea pauciflora var. pauciflora			
381.	5688	Eucalyptus laeliae (Darling Range Ghost Gum)			
382.	5708	Eucalyptus marginata (Jarrah, Djara)			
383.	13547	Eucalyptus marginata subsp. marginata (Jarrah)			
384.	44858	Eucalyptus resinifera subsp. resinifera	Υ		Υ
385.		Eucalyptus rudis (Flooded Gum, Kulurda)			
386.		Eucalyptus wandoo subsp. wandoo			
387.		Homalospermum firmum			
388.					
		Hypocalymma angustifolium (White Myrtle, Kudjid)			
389.		Hypocalymma cordifolium			
390.		Hypocalymma ericifolium			
391.		Hypocalymma robustum (Swan River Myrtle)			
392.		Kunzea glabrescens (Spearwood)			
393.	5841	Kunzea recurva			
394.	14776	Kunzea rostrata			
395.	5921	Melaleuca incana (Grey Honeymyrtle)			
396.	5926	Melaleuca lateritia (Robin Redbreast Bush)			
397.		Melaleuca parviceps			
398.		Melaleuca thymoides			
399.		Melaleuca trichophylla			
400.					
		Paragonis grandiflora Pariochumno ollinticum vor. ellinticum			
401.		Pericalymma ellipticum var. ellipticum			
402.		Pericalymma ellipticum var. floridum			
	15501	Pericalymma spongiocaule			
403.					
403. 404.	20135	Taxandria linearifolia			
		Taxandria linearifolia Taxandria parviceps			
404.	20133				







	Name ID	Species Name	Naturalised C	Conservation Code	¹ Endemic To Que Area
407.	6076	Verticordia densiflora (Compacted Featherflower)			
408.	12411	Verticordia densiflora var. cespitosa			
409.	12412	Verticordia densiflora var. pedunculata		Т	
410.	15618	Verticordia plumosa var. plumosa			
Dlacaceae					
411.	2365	Olax benthamiana			
)nograces					
Onagraceae	44000	F 71 1 1 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7			
412.	11992	Epilobium billardiereanum subsp. intermedium			
Orchidaceae	•				
413.	15332	Caladenia attingens subsp. attingens			
414.	1592	Caladenia flava (Cowslip Orchid)			
415.	15372	Caladenia nana subsp. unita			
416.	18026	Caladenia pendens subsp. pendens			
417.	15377	Caladenia reptans subsp. reptans			
418.		Corybas recurvus			
419.		Cryptostylis ovata (Slipper Orchid)			
420.		Cyanicula sericea			
421.		Disa bracteata	Υ		
422.		Drakaea elastica (Glossy-leaved Hammer Orchid)	•	Т	
422.		Eriochilus dilatatus (White Bunny Orchid)		'	
423. 424.		Eriochilus dilatatus subsp. magnus			
424.		Eriochilus dilatatus subsp. magnus Eriochilus dilatatus subsp. multiflorus			
		•			
426.		Leporella fimbriata (Hare Orchid) Microtic cupularis			
427.		Microtis cupularis			
428.		Microtis media subsp. media			
429.		Praecoxanthus aphyllus			
430.		Prasophyllum elatum (Tall Leek Orchid)			
431.		Prasophyllum fimbria (Fringed Leek Orchid)			
432.		Prasophyllum parvifolium (Autumn Leek Orchid)			
433.	1686	Pterostylis barbata (Bird Orchid)			
434.	11118	Pterostylis pyramidalis (Snail Orchid)			
435.	1693	Pterostylis recurva (Jug Orchid)			
436.	18655	Pterostylis sp. crinkled leaf (G.J. Keighery 13426)			
437.	10998	Pterostylis turfosa (Bird Orchid)			
438.	1698	Pterostylis vittata (Banded Greenhood)			
439.	16367	Pyrorchis nigricans (Red beaks, Elephants ears)			
440.	1705	Thelymitra crinita (Blue Lady Orchid)			
441.	1707	Thelymitra flexuosa (Twisted Sun Orchid)			
442.	11053	Thelymitra macrophylla			
443.	1717	Thelymitra variegata (Queen of Sheba)		P2	
) rahanahaa					
robanchac					
444.					
	/122	Orobanche minor (Lesser Broomrape)	Υ		
		Orobanche minor (Lesser Broomrape)	Υ		
xalidaceae					
xalidaceae 445.	4352	Orobanche minor (Lesser Broomrape) Oxalis glabra	Y		
xalidaceae 445.	4352				
xalidaceae 445.	4352 eae				
445. hytolaccac	4352 eae 2793	Oxalis glabra	Y		
exalidaceae 445. hytolaccac 446. ittosporace	4352 eae 2793	Oxalis glabra Phytolacca octandra (Red Ink Plant)	Y		
exalidaceae 445. hytolaccac 446. ittosporace 447.	4352 eae 2793 eae 25798	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell)	Y		
xalidaceae 445. hytolaccac 446. ittosporace 447. 448.	4352 eae 2793 eae 25798 3165	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia	Y		
xalidaceae 445. hytolaccac 446. ittosporace 447.	4352 eae 2793 eae 25798 3165	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell)	Y		
Avalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449.	4352 eae 2793 eae 25798 3165 17630	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia	Y		
exalidaceae 445. hytolaccac 446. ittosporace 447. 448.	4352 eae 2793 eae 25798 3165 17630	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia	Y		
exalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace	4352 eae 2793 eae 25798 3165 17630 eae 4717	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis	Y		
xalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace 450. 451.	4352 eae 2793 eae 25798 3165 17630 eae 4717	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort)	Y Y		
xalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace 450. 451. oaceae	4352 eae	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain)	Y Y Y Y		
xalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace 450. 451. oaceae 452.	4352 eae	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass)	Y Y Y Y		
xalidaceae 445. hytolaccac 446. iittosporace 447. 448. 449. lantaginace 450. 451. oaceae 452. 453.	4352 eae	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass) Aira cupaniana (Silvery Hairgrass)	Y Y Y Y		
xalidaceae 445. hytolaccac 446. iittosporace 447. 448. 449. lantaginace 450. 451. oaceae 452. 453. 454.	4352 eae 2793 26ae 25798 3165 17630 eae 4717 7303 184 185 13380	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass) Aira cupaniana (Silvery Hairgrass) Amphibromus nervosus	Y Y Y Y		
xalidaceae 445. hytolaccac 446. iittosporace 447. 448. 449. lantaginace 450. 451. Oaceae 452. 453. 454. 455.	4352 eae 2793 eae 25798 3165 17630 eae 4717 7303 184 185 13380 194	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass) Aira cupaniana (Silvery Hairgrass) Amphibromus nervosus Amphipogon amphipogonoides	Y Y Y Y		
2xalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace 450. 451. Oaceae 452. 453. 454. 455. 456.	4352 eae 2793 eae 25798 3165 17630 eae 4717 7303 184 185 13380 194 20184	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass) Aira cupaniana (Silvery Hairgrass) Amphibromus nervosus Amphipogon amphipogonoides Amphipogon laguroides subsp. laguroides	Y Y Y Y		
xalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace 450. 451. Oaceae 452. 453. 454. 455.	4352 eae 2793 eae 25798 3165 17630 eae 4717 7303 184 185 13380 194 20184	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass) Aira cupaniana (Silvery Hairgrass) Amphibromus nervosus Amphipogon amphipogonoides	Y Y Y Y		
xalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace 450. 451. oaceae 452. 453. 454. 455. 456.	4352 eae 2793 eae 25798 3165 17630 eae 4717 7303 184 185 13380 194 20184 200	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass) Aira cupaniana (Silvery Hairgrass) Amphibromus nervosus Amphipogon amphipogonoides Amphipogon laguroides subsp. laguroides	Y Y Y Y		
xalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace 450. 451. oaceae 452. 453. 454. 455. 456. 457.	4352 eae 2793 260 25798 3165 17630 260 4717 7303 184 185 13380 194 20184 200 202	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass) Aira cupaniana (Silvery Hairgrass) Amphibromus nervosus Amphipogon amphipogonoides Amphipogon laguroides subsp. laguroides Amphipogon turbinatus	Y Y Y Y Y Y		
xalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace 450. 451. oaceae 452. 453. 454. 455. 456. 457. 458.	4352 eae 2793 26ae 25798 3165 17630 26ae 4717 7303 184 185 13380 194 20184 200 202 17234	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass) Aira cupaniana (Silvery Hairgrass) Amphibromus nervosus Amphipogon amphipogonoides Amphipogon laguroides subsp. laguroides Amphipogon turbinatus Anthoxanthum odoratum (Sweet Vernal Grass)	Y Y Y Y Y Y		
xalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace 450. 451. oaceae 452. 453. 454. 455. 456. 457. 458. 459.	4352 eae 2793 260 25798 3165 17630 260 4717 7303 184 185 13380 194 20184 200 202 17234 17240	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass) Aira cupaniana (Silvery Hairgrass) Amphibromus nervosus Amphipogon amphipogonoides Amphipogon laguroides subsp. laguroides Amphipogon turbinatus Anthoxanthum odoratum (Sweet Vernal Grass) Austrostipa compressa	Y Y Y Y Y Y		
xalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace 450. 451. oaceae 452. 453. 454. 455. 456. 457. 458. 459. 460.	4352 eae 2793 266 25798 3165 17630 266 4717 7303 184 185 13380 194 20184 200 202 17234 17240 17253	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass) Aira cupaniana (Silvery Hairgrass) Amphibromus nervosus Amphipogon amphipogonoides Amphipogon laguroides subsp. laguroides Amphipogon turbinatus Anthoxanthum odoratum (Sweet Vernal Grass) Austrostipa compressa Austrostipa flavescens	Y Y Y Y Y Y		
xalidaceae 445. hytolaccac 446. ittosporace 447. 448. 449. lantaginace 450. 451. oaceae 452. 453. 454. 455. 456. 457. 458. 459. 460. 461.	4352 eae 2793 3165 17630 eae 4717 7303 184 185 13380 194 20184 200 202 17234 17240 17253 244	Oxalis glabra Phytolacca octandra (Red Ink Plant) Billardiera fusiformis (Australian Bluebell) Billardiera variifolia Marianthus tenuis Callitriche stagnalis (Common Starwort) Plantago lanceolata (Ribwort Plantain) Aira caryophyllea (Silvery Hairgrass) Aira cupaniana (Silvery Hairgrass) Amphibromus nervosus Amphipogon amphipogonoides Amphipogon laguroides subsp. laguroides Amphipogon turbinatus Anthoxanthum odoratum (Sweet Vernal Grass) Austrostipa Compressa Austrostipa semibarbata	Y Y Y Y Y Y		



	Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Query Area
			Υ		
464.	41564	Cenchrus clandestinus (Kikuyu Grass)	Υ		
465.	41566	Cenchrus longisetus (Feathertop)	Υ		
466.	41567	Cenchrus macrourus (African Feather Grass)	Υ		
467.	299	Deyeuxia quadriseta (Reed Bentgrass)			
468.		Digitaria sanguinalis (Crab Grass)	Υ		
469.		Echinochloa crus-galli	Υ		
470.		Ehrharta erecta (Panic Veldt Grass)	Y		
471.		Eragrostis brownii (Brown's Lovegrass)			
472.		Eragrostis elongata (Clustered Lovegrass)	.,		
473.		Glyceria declinata	Y		
474.		Glyceria maxima (Water Meadowgrass)	Υ		
475. 476.		Hemarthria uncinata (Matgrass) Hemarthria uncinata var. uncinata			
470.		Lachnagrostis filiformis			
478.		Neurachne alopecuroidea (Foxtail Mulga Grass)			
479.		Paspalum dilatatum	Υ		
480.		Paspalum distichum (Water Couch)	Y		
481.		Phalaris angusta	Y		
482.		Phalaris aquatica (Phalaris)	Y		
483.		Phalaris minor (Lesser Canary Grass)	Y		
484.		Poa annua (Winter Grass)	Y		
485.		Polypogon monspeliensis (Annual Beardgrass)	Y		
486.		Polypogon tenellus	,		
487.		Rytidosperma acerosum			
488.		Rytidosperma pilosum			
489.		Rytidosperma setaceum			
490.		Setaria verticillata (Whorled Pigeon Grass)	Υ		
491.		Sorghum halepense (Johnson Grass)	Υ		
492.		Tetrarrhena laevis (Forest Ricegrass)			
Dadasarnasa					
Podocarpace		Dedicarra duranticario (Mild Diago IV de)			
493.	86	Podocarpus drouynianus (Wild Plum, Kula)			
Polygalaceae		Comesperma calymega (Blue-spike Milkwort)			
		Comcopornia dalymoga (Elado apino minimorty			
Polygonacea					
495.		Persicaria decipiens			
496.		Persicaria maculosa	Υ		
497.	11052	Persicaria prostrata			
Pottiaceae					
498.	32315	Barbula calycina			
Primulaceae					
499.	36375	Lysimachia arvensis (Pimpernel)	Υ		
433.	30373	Lysimacina arvensis (i imperior)	'		
Proteaceae					
500.	1790	Adenanthos meisneri			
501.		Adenanthos obovatus (Basket Flower)			
502.	28281	Adenanthos sp. Whicher Range (G.J. Keighery 9736)			
503.	1800	Banksia attenuata (Slender Banksia, Piara)			
504.		Banksia dallanneyi var. dallanneyi			
505.		Banksia grandis (Bull Banksia, Pulgarla)			
506.		Banksia littoralis (Swamp Banksia, Pungura)			
507.		Banksia sessilis var. sessilis			
508.		Banksia sphaerocarpa var. sphaerocarpa (Fox Banksia)			
509.		Banksia squarrosa subsp. argillacea		T	
510.		Conospermum capitatum			
511.		Conospermum flexuosum subsp. laevigatum		5.	
512. 513		Franklandia triaristata (Lanoline Bush)		P4	
513. 514		Grevillea bronwenae Grevillea centristirma		P3	
514. 515.		Grevillea centristigma Grevillea diversifolia subsp. diversifolia			
515. 516.		Grevillea diversiiolia subsp. diversiiolia Grevillea pilulifera (Woolly-flowered Grevillea)			
516.		Grevillea pulchella (Beautiful Grevillea)			
517.		Grevillea pulchella subsp. ascendens			
519.		Grevillea pulchella subsp. ascendens Grevillea pulchella subsp. pulchella			
520.		Grevillea quercifolia (Oak-leaf Grevillea)			
521.		Grevillea vestita subsp. vestita			
522.		Hakea amplexicaulis (Prickly Hakea)			
523.		Hakea cyclocarpa (Ramshorn)			
		- , , , ,			-111/00
				OPP December 1	- correct to







N	Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Query
524.	45207	Hakea dactyloides	Υ		Area
525.		Hakea lissocarpha (Honey Bush)			
526.		Hakea stenocarpa (Narrow-fruited Hakea)			
		Isopogon formosus subsp. dasylepis		DO.	
527.				P3	
528.		Isopogon sphaerocephalus (Drumstick Isopogon)			
529.		Lambertia multiflora var. darlingensis			
530.	2267	Persoonia longifolia (Snottygobble)			
531.	2299	Petrophile linearis (Pixie Mops)			
532.	2312	Petrophile striata			
533.	2316	Stirlingia latifolia (Blueboy)			
534.	15529	Synaphea floribunda			
535.		Synaphea gracillima			
536.		Synaphea hians		P3	
537.		Synaphea odocoileops		P1	
				FI	
538.		Synaphea petiolaris (Synaphea)			
539.		Synaphea petiolaris subsp. simplex		P3	
540.	16863	Synaphea petiolaris subsp. triloba			
541.	31767	Synaphea polypodioides		P3	
542.	30751	Synaphea sp. Pinjarra Plain (A.S. George 17182)		T	
543.	16749	Synaphea stenoloba		T	
544.	15535	Synaphea whicherensis			
545.		Xylomelum occidentale (Woody Pear, Djandin)			
		, ————————————————————————————————————			
Pteridaceae 546.	25	Adiantum aethiopicum (Common Maidenhair)			
Racopilaceae					
547.		Paganilum ayanidigarum yar aanyalutaaayum			
547.	32480	Racopilum cuspidigerum var. convolutaceum			
Restionaceae					
548.	17692	Cytogonidium leptocarpoides			
549.		Desmocladus fasciculatus			
550.		Desmocladus flexuosus			
551.		Desmocladus virgatus			
552.		Hypolaena exsulca			
553.	17841	Hypolaena pubescens			
554.	1085	Lepyrodia glauca			
555.	1088	Lepyrodia macra (Large Scale Rush)			
556.	1090	Lepyrodia muirii			
557.	1092	Loxocarya cinerea			
Rhamnaceae					
558.	19704	Stenanthemum sublineare		P2	
Deceses					
Rosaceae					
559.		Acaena novae-zelandiae	Y		
560.		Prunus cerasifera	Υ		
561.	46201	Prunus persica	Υ		
562.	18391	Pyrus communis	Υ		
D. I. I					
Rubiaceae					
563.		Opercularia apiciflora			
564.	17273	Richardia brasiliensis	Υ		
Rutaceae					
	4445	Parania dafaliata			
565.		Boronia defoliata			
566.		Boronia denticulata			
567.	4417	Boronia dichotoma			
568.	4420	Boronia fastigiata (Bushy Boronia)			
569.	16618	Boronia humifusa		P1	
570.		Boronia megastigma (Scented Boronia)			
571.		Boronia ramosa			
572.		Boronia spathulata (Boronia)			
573.	18529	Philotheca spicata (Pepper and Salt)			
Santalaceae					
574.	2342	Leptomeria cunninghamii			
575.		Leptomeria ellytes			
070.	11103	zoptomona oujtou			
Selaginellacea	ae				
576.	6	Selaginella gracillima (Tiny Clubmoss)			
		· · · · · · · · · · · · · · · · · · ·			
Sematophylla					
577.	32433	Sematophyllum homomallum			







	Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Query Area
Stylidiaceae					
578.	7674	Levenhookia preissii (Preiss's Stylewort)			
579.	7676	Levenhookia pusilla (Midget Stylewort)			
580.	7677	Levenhookia stipitata (Common Stylewort)			
581.	40480	Stylidium acuminatum subsp. acuminatum		P2	
582.	7684	Stylidium amoenum (Lovely Triggerplant)			
583.	30278	Stylidium androsaceum			
584.	39880	Stylidium angustifolium subsp. glaucifolium			
585.	7688	Stylidium barleei (Tooth-leaved Triggerplant)			
586.	7693	Stylidium brunonianum (Pink Fountain Triggerplant)			
587.	7696	Stylidium calcaratum (Book Triggerplant)			
588.	7699	Stylidium carnosum (Fleshy-leaved Triggerplant)			
589.	7702	Stylidium ciliatum (Golden Triggerplant)			
590.	7745	Stylidium junceum (Reed Triggerplant)			
591.	7752	Stylidium lineatum (Sunny Triggerplant)			
592.	25829	Stylidium neurophyllum (Coastal Plain Triggerplant)			
593.	7773	Stylidium petiolare (Horn Triggerplant)			
594.	7774	Stylidium piliferum (Common Butterfly Triggerplant)			
595.	7782	Stylidium pulchellum (Thumbelina Triggerplant)			
596.	7785	Stylidium repens (Matted Triggerplant)			
597.	7798	Stylidium schoenoides (Cow Kicks)			
598.		Stylidium sp.			
599.	7799	Stylidium spathulatum (Creamy Triggerplant)			
Thymelaeac	220				
600.		Pimelea ciliata subsp. ciliata			
601.		Pimelea lanata			
602.		Pimelea lehmanniana subsp. nervosa			
603.		Pimelea preissii			
604.		Pimelea rosea (Rose Banjine)			
605.		Pimelea rosea subsp. rosea			
606.		Pimelea suaveolens subsp. suaveolens			
606.	12041	rimeiea suaveolens subsp. suaveolens			
Verbenaceae	9				
607.	36096	Verbena incompta (Purple-top Verbena)	Υ		
Violaceae					
608.	12007	Hybanthus floribundus subsp. floribundus			
609.		Viola odorata (Common Violet)	Υ		
609.	3223	Viola odorata (Common Violet)	Ť		
Xanthorrhoe	aceae				
610.	1280	Chamaescilla corymbosa (Blue Squill)			
611.	19338	Chamaescilla gibsonii		P3	
612.	1249	Xanthorrhoea acanthostachya			
613.	14544	Xanthorrhoea brunonis subsp. brunonis			
614.	14545	Xanthorrhoea brunonis subsp. semibarbata			
615.	1253	Xanthorrhoea gracilis (Graceful Grass Tree, Mimidi)			
616.	1256	Xanthorrhoea preissii (Grass tree, Palga)			
7amiassas					
Zamiaceae	0.5	Managamia riadla: /Zamia Dividi:)			
617.	85	Macrozamia riedlei (Zamia, Djiridji)			


Conservation Codes
T. Rare or likely to become extinct
Y. Prounned extinct
A. Prounned extinct
A. Prounned extinct
A. Proceeding protected fauna
1. Priority
2. Priority
3. Priority
4. Priority
5. Priority
5. Priority
5.





¹ For NatureMap's purposes, species flagged as endemic are those whose records are wholely contained within the search area. Note that only those records complying with the search criterion are included in the calculation. For example, if you limit records to those from a specific datasource, only records from that datasource are used to determine if a species is restricted to the query area.

APPENDIX D: EPBC PROTECTED MATTERS SEARCH REPORT FOR THREATENED AND PRIORITY SPECIES THAT HAVE POTENTIAL TO OCCUR WITHIN SURVEY AREA



EPBC Act Protected Matters Report

This report provides general guidance on matters of national environmental significance and other matters protected by the EPBC Act in the area you have selected.

Information on the coverage of this report and qualifications on data supporting this report are contained in the caveat at the end of the report.

Information is available about <u>Environment Assessments</u> and the EPBC Act including significance guidelines, forms and application process details.

Report created: 07/11/18 23:50:05


Summary

Details

Matters of NES
Other Matters Protected by the EPBC Act
Extra Information


Caveat

Acknowledgements



This map may contain data which are ©Commonwealth of Australia (Geoscience Australia), ©PSMA 2010

Coordinates
Buffer: 10.0Km



Summary

Matters of National Environmental Significance

This part of the report summarises the matters of national environmental significance that may occur in, or may relate to, the area you nominated. Further information is available in the detail part of the report, which can be accessed by scrolling or following the links below. If you are proposing to undertake an activity that may have a significant impact on one or more matters of national environmental significance then you should consider the <u>Administrative Guidelines on Significance</u>.

World Heritage Properties:	None
National Heritage Places:	None
Wetlands of International Importance:	None
Great Barrier Reef Marine Park:	None
Commonwealth Marine Area:	None
Listed Threatened Ecological Communities:	1
Listed Threatened Species:	30
Listed Migratory Species:	10

Other Matters Protected by the EPBC Act

This part of the report summarises other matters protected under the Act that may relate to the area you nominated. Approval may be required for a proposed activity that significantly affects the environment on Commonwealth land, when the action is outside the Commonwealth land, or the environment anywhere when the action is taken on Commonwealth land. Approval may also be required for the Commonwealth or Commonwealth agencies proposing to take an action that is likely to have a significant impact on the environment anywhere.

The EPBC Act protects the environment on Commonwealth land, the environment from the actions taken on Commonwealth land, and the environment from actions taken by Commonwealth agencies. As heritage values of a place are part of the 'environment', these aspects of the EPBC Act protect the Commonwealth Heritage values of a Commonwealth Heritage place. Information on the new heritage laws can be found at http://www.environment.gov.au/heritage

A <u>permit</u> may be required for activities in or on a Commonwealth area that may affect a member of a listed threatened species or ecological community, a member of a listed migratory species, whales and other cetaceans, or a member of a listed marine species.

Commonwealth Land:	1
Commonwealth Heritage Places:	None
Listed Marine Species:	15
Whales and Other Cetaceans:	None
Critical Habitats:	None
Commonwealth Reserves Terrestrial:	None
Australian Marine Parks:	None

Extra Information

This part of the report provides information that may also be relevant to the area you have nominated.

State and Territory Reserves:	3
Regional Forest Agreements:	1
Invasive Species:	27
Nationally Important Wetlands:	None
Key Ecological Features (Marine)	None

Details

Matters of National Environmental Significance

Listed Threatened Ecological Communities

Listed Tilleateried Ecological Communities		[Tresource information]
For threatened ecological communities where the distriplans, State vegetation maps, remote sensing imagery community distributions are less well known, existing vegetation produce indicative distribution maps.	and other sources. Where	threatened ecological
Name	Status	Type of Presence
Banksia Woodlands of the Swan Coastal Plain ecological community	Endangered	Community likely to occur within area
Listed Threatened Species		[Resource Information]
Name	Status	Type of Presence
Birds		
Calidris canutus Red Knot, Knot [855]	Endangered	Species or species habitat may occur within area
Calidris ferruginea Curlew Sandpiper [856]	Critically Endangered	Species or species habitat may occur within area
Calyptorhynchus banksii naso Forest Red-tailed Black-Cockatoo, Karrak [67034]	Vulnerable	Species or species habitat known to occur within area
Calyptorhynchus baudinii Baudin's Cockatoo, Long-billed Black-Cockatoo [769]	Endangered	Breeding known to occur within area
Calyptorhynchus latirostris Carnaby's Cockatoo, Short-billed Black-Cockatoo [59523]	Endangered	Species or species habitat known to occur within area
Numenius madagascariensis Eastern Curlew, Far Eastern Curlew [847]	Critically Endangered	Species or species habitat may occur within area
Mammals		
Dasyurus geoffroii Chuditch, Western Quoll [330]	Vulnerable	Species or species habitat known to occur within area
Pseudocheirus occidentalis Western Ringtail Possum, Ngwayir, Womp, Woder, Ngoor, Ngoolangit [25911]	Critically Endangered	Species or species habitat known to occur within area
Setonix brachyurus Quokka [229]	Vulnerable	Species or species habitat known to occur within area
Other <u>Westralunio carteri</u> Carter's Freshwater Mussel, Freshwater Mussel [86266]	Vulnerable	Species or species habitat known to occur within area
Plants		

[Resource Information]

Name	Status	Type of Presence
Andersonia gracilis Slender Andersonia [14470]	Endangered	Species or species habitat may occur within area
Banksia nivea subsp. uliginosa Swamp Honeypot [82766]	Endangered	Species or species habitat likely to occur within area
Banksia squarrosa subsp. argillacea Whicher Range Dryandra [82769]	Vulnerable	Species or species habitat known to occur within area
Brachyscias verecundus Ironstone Brachyscias [81321]	Critically Endangered	Species or species habitat may occur within area
Caladenia hoffmanii Hoffman's Spider-orchid [56719]	Endangered	Species or species habitat may occur within area
Chamelaucium sp. S coastal plain (R.D.Royce 4872) Royce's Waxflower [87814]	Vulnerable	Species or species habitat may occur within area
Daviesia elongata subsp. elongata Long-leaved Daviesia [64883]	Vulnerable	Species or species habitat known to occur within area
<u>Diuris micrantha</u> Dwarf Bee-orchid [55082]	Vulnerable	Species or species habitat likely to occur within area
<u>Diuris purdiei</u> Purdie's Donkey-orchid [12950]	Endangered	Species or species habitat may occur within area
<u>Drakaea elastica</u> Glossy-leafed Hammer Orchid, Glossy-leaved Hammer Orchid, Warty Hammer Orchid [16753]	Endangered	Species or species habitat known to occur within area
<u>Drakaea micrantha</u> Dwarf Hammer-orchid [56755]	Vulnerable	Species or species habitat known to occur within area
Eleocharis keigheryi Keighery's Eleocharis [64893]	Vulnerable	Species or species habitat known to occur within area
Gastrolobium papilio Butterfly-leaved Gastrolobium [78415]	Endangered	Species or species habitat may occur within area
Lambertia echinata subsp. occidentalis Western Prickly Honeysuckle [64528]	Endangered	Species or species habitat may occur within area
Petrophile latericola Laterite Petrophile [64532]	Endangered	Species or species habitat may occur within area
Sphenotoma drummondii Mountain Paper-heath [21160]	Endangered	Species or species habitat may occur within area
Synaphea sp. Fairbridge Farm (D. Papenfus 696) Selena's Synaphea [82881]	Critically Endangered	Species or species habitat likely to occur within area
Synaphea sp. Serpentine (G.R. Brand 103) [86879]	Critically Endangered	Species or species habitat may occur within area

Name	Status	Type of Presence
Synaphea stenoloba		
Dwellingup Synaphea [66311]	Endangered	Species or species habitat known to occur within area
Verticordia densiflora var. pedunculata		
Long-stalked Featherflower [55689]	Endangered	Species or species habitat likely to occur within area
Listed Migratory Species		[Resource Information]
* Species is listed under a different scientific name on t	he EPBC Act - Threatened	Species list.
Name	Threatened	Type of Presence
Migratory Marine Birds		71
Apus pacificus		_
Fork-tailed Swift [678]		Species or species habitat likely to occur within area
Migratory Terrestrial Species		
Motacilla cinerea		
Grey Wagtail [642]		Species or species habitat may occur within area
Migratory Wetlands Species		
Actitis hypoleucos		
Common Sandpiper [59309]		Species or species habitat likely to occur within area
Calidris acuminata		
Sharp-tailed Sandpiper [874]		Species or species habitat may occur within area
Calidris canutus		
Red Knot, Knot [855]	Endangered	Species or species habitat may occur within area
Calidris ferruginea		
Curlew Sandpiper [856]	Critically Endangered	Species or species habitat may occur within area
Calidris melanotos		
Pectoral Sandpiper [858]		Species or species habitat may occur within area
Numenius madagascariensis		
Eastern Curlew, Far Eastern Curlew [847]	Critically Endangered	Species or species habitat may occur within area
Pandion haliaetus		
Osprey [952]		Species or species habitat likely to occur within area
Tringa nebularia		
Common Greenshank, Greenshank [832]		Species or species habitat likely to occur within area
Other Matters Protected by the EPBC Act		

Commonwealth Land [Resource Information]

The Commonwealth area listed below may indicate the presence of Commonwealth land in this vicinity. Due to the unreliability of the data source, all proposals should be checked as to whether it impacts on a Commonwealth area, before making a definitive decision. Contact the State or Territory government land department for further information.

Name

Commonwealth Land -

Listed Marine Species

[Resource Information]

* Species is listed under a different scientific name on the EPBC Act - Threatened Species list.

Name Threatened Type of Presence

Name	Threatened	Type of Presence
Birds		
Actitis hypoleucos Common Sandpiper [59309]		Species or species habitat likely to occur within area
Apus pacificus Fork-tailed Swift [678]		Species or species habitat likely to occur within area
Ardea alba Great Egret, White Egret [59541]		Breeding known to occur within area
Ardea ibis Cattle Egret [59542]		Species or species habitat may occur within area
Calidris acuminata Sharp-tailed Sandpiper [874]		Species or species habitat may occur within area
Calidris canutus Red Knot, Knot [855]	Endangered	Species or species habitat may occur within area
Calidris ferruginea Curlew Sandpiper [856]	Critically Endangered	Species or species habitat may occur within area
Calidris melanotos Pectoral Sandpiper [858]		Species or species habitat may occur within area
Haliaeetus leucogaster White-bellied Sea-Eagle [943]		Species or species habitat known to occur within area
Merops ornatus Rainbow Bee-eater [670]		Species or species habitat may occur within area
Motacilla cinerea Grey Wagtail [642]		Species or species habitat may occur within area
Numenius madagascariensis Eastern Curlew, Far Eastern Curlew [847]	Critically Endangered	Species or species habitat may occur within area
Pandion haliaetus Osprey [952]		Species or species habitat likely to occur within area
Thinornis rubricollis Hooded Plover [59510]		Species or species habitat may occur within area
Tringa nebularia Common Greenshank, Greenshank [832]		Species or species habitat likely to occur within area

Extra Information

Name

State and Territory Reserves	[Resource Information]
Name	State
Dardanup	WA
NTWA Bushland covenant (0107)	WA
Unnamed WA49857	WA

Regional Forest Agreements

Note that all areas with completed RFAs have been included.

South West WA RFA Western Australia

Invasive Species

Weeds reported here are the 20 species of national significance (WoNS), along with other introduced plants that are considered by the States and Territories to pose a particularly significant threat to biodiversity. The following feral animals are reported: Goat, Red Fox, Cat, Rabbit, Pig, Water Buffalo and Cane Toad. Maps from Landscape Health Project, National Land and Water Resouces Audit, 2001.

Landscape Health Project, National Land and Water Resouces Audit, 2001.		
Name	Status	Type of Presence
Birds		
Anas platyrhynchos		
Mallard [974]		Species or species habitat likely to occur within area
Columba livia		
Rock Pigeon, Rock Dove, Domestic Pigeon [803]		Species or species habitat likely to occur within area
Passer domesticus		
House Sparrow [405]		Species or species habitat likely to occur within area
Passer montanus		
Eurasian Tree Sparrow [406]		Species or species habitat likely to occur within area
Streptopelia chinensis		
Spotted Turtle-Dove [780]		Species or species habitat likely to occur within area
Streptopelia senegalensis		
Laughing Turtle-dove, Laughing Dove [781]		Species or species habitat likely to occur within area
Sturnus vulgaris		
Common Starling [389]		Species or species habitat likely to occur within area
Mammals		
Bos taurus		
Domestic Cattle [16]		Species or species habitat likely to occur within area
Canis lupus familiaris		
Domestic Dog [82654]		Species or species habitat likely to occur within area
Felis catus		
Cat, House Cat, Domestic Cat [19]		Species or species habitat

likely to occur within area

Feral deer

Feral deer species in Australia [85733] Species or species habitat

likely to occur within area

[Resource Information]

[Resource Information]

State

Mus musculus

House Mouse [120] Species or species habitat

likely to occur within area

Name	Status	Type of Presence
Oryctolagus cuniculus		
Rabbit, European Rabbit [128]		Species or species habitat likely to occur within area
Rattus rattus		
Black Rat, Ship Rat [84]		Species or species habitat likely to occur within area
Sus scrofa		
Pig [6]		Species or species habitat likely to occur within area
Vulpes vulpes		
Red Fox, Fox [18]		Species or species habitat likely to occur within area
Plants		
Asparagus asparagoides		
Bridal Creeper, Bridal Veil Creeper, Smilax, Florist's Smilax, Smilax Asparagus [22473]		Species or species habitat likely to occur within area
Brachiaria mutica		
Para Grass [5879]		Species or species habitat may occur within area
Cenchrus ciliaris		
Buffel-grass, Black Buffel-grass [20213]		Species or species habitat may occur within area
Chrysanthemoides monilifera		
Bitou Bush, Boneseed [18983]		Species or species habitat may occur within area
Genista linifolia		
Flax-leaved Broom, Mediterranean Broom, Flax Broom, [2800]	om	Species or species habitat likely to occur within area
Genista sp. X Genista monspessulana		
Broom [67538]		Species or species habitat may occur within area
Lycium ferocissimum		
African Boxthorn, Boxthorn [19235]		Species or species habitat likely to occur within area
Olea europaea		
Olive, Common Olive [9160]		Species or species habitat may occur within area
Pinus radiata		
Radiata Pine Monterey Pine, Insignis Pine, Wilding Pine [20780]		Species or species habitat may occur within area
Rubus fruticosus aggregate		
Blackberry, European Blackberry [68406]		Species or species habitat likely to occur within area
Salix spp. except S.babylonica, S.x calodendron & S	S.x reichardtii	
Willows except Weeping Willow, Pussy Willow and Sterile Pussy Willow [68497]		Species or species habitat likely to occur within area

Caveat

The information presented in this report has been provided by a range of data sources as acknowledged at the end of the report.

This report is designed to assist in identifying the locations of places which may be relevant in determining obligations under the Environment Protection and Biodiversity Conservation Act 1999. It holds mapped locations of World and National Heritage properties, Wetlands of International and National Importance, Commonwealth and State/Territory reserves, listed threatened, migratory and marine species and listed threatened ecological communities. Mapping of Commonwealth land is not complete at this stage. Maps have been collated from a range of sources at various resolutions.

Not all species listed under the EPBC Act have been mapped (see below) and therefore a report is a general guide only. Where available data supports mapping, the type of presence that can be determined from the data is indicated in general terms. People using this information in making a referral may need to consider the gualifications below and may need to seek and consider other information sources.

For threatened ecological communities where the distribution is well known, maps are derived from recovery plans, State vegetation maps, remote sensing imagery and other sources. Where threatened ecological community distributions are less well known, existing vegetation maps and point location data are used to produce indicative distribution maps.

Threatened, migratory and marine species distributions have been derived through a variety of methods. Where distributions are well known and if time permits, maps are derived using either thematic spatial data (i.e. vegetation, soils, geology, elevation, aspect, terrain, etc) together with point locations and described habitat; or environmental modelling (MAXENT or BIOCLIM habitat modelling) using point locations and environmental data layers.

Where very little information is available for species or large number of maps are required in a short time-frame, maps are derived either from 0.04 or 0.02 decimal degree cells; by an automated process using polygon capture techniques (static two kilometre grid cells, alpha-hull and convex hull); or captured manually or by using topographic features (national park boundaries, islands, etc). In the early stages of the distribution mapping process (1999-early 2000s) distributions were defined by degree blocks, 100K or 250K map sheets to rapidly create distribution maps. More reliable distribution mapping methods are used to update these distributions as time permits.

Only selected species covered by the following provisions of the EPBC Act have been mapped:

- migratory and
- marine

The following species and ecological communities have not been mapped and do not appear in reports produced from this database:

- threatened species listed as extinct or considered as vagrants
- some species and ecological communities that have only recently been listed
- some terrestrial species that overfly the Commonwealth marine area
- migratory species that are very widespread, vagrant, or only occur in small numbers

The following groups have been mapped, but may not cover the complete distribution of the species:

- non-threatened seabirds which have only been mapped for recorded breeding sites
- seals which have only been mapped for breeding sites near the Australian continent

Such breeding sites may be important for the protection of the Commonwealth Marine environment.

Coordinates

-33.51874 115.74069

Acknowledgements

This database has been compiled from a range of data sources. The department acknowledges the following custodians who have contributed valuable data and advice:

- -Office of Environment and Heritage, New South Wales
- -Department of Environment and Primary Industries, Victoria
- -Department of Primary Industries, Parks, Water and Environment, Tasmania
- -Department of Environment, Water and Natural Resources, South Australia
- -Department of Land and Resource Management, Northern Territory
- -Department of Environmental and Heritage Protection, Queensland
- -Department of Parks and Wildlife, Western Australia
- -Environment and Planning Directorate, ACT
- -Birdlife Australia
- -Australian Bird and Bat Banding Scheme
- -Australian National Wildlife Collection
- -Natural history museums of Australia
- -Museum Victoria
- -Australian Museum
- -South Australian Museum
- -Queensland Museum
- -Online Zoological Collections of Australian Museums
- -Queensland Herbarium
- -National Herbarium of NSW
- -Royal Botanic Gardens and National Herbarium of Victoria
- -Tasmanian Herbarium
- -State Herbarium of South Australia
- -Northern Territory Herbarium
- -Western Australian Herbarium
- -Australian National Herbarium, Canberra
- -University of New England
- -Ocean Biogeographic Information System
- -Australian Government, Department of Defence
- Forestry Corporation, NSW
- -Geoscience Australia
- -CSIRO
- -Australian Tropical Herbarium, Cairns
- -eBird Australia
- -Australian Government Australian Antarctic Data Centre
- -Museum and Art Gallery of the Northern Territory
- -Australian Government National Environmental Science Program
- -Australian Institute of Marine Science
- -Reef Life Survey Australia
- -American Museum of Natural History
- -Queen Victoria Museum and Art Gallery, Inveresk, Tasmania
- -Tasmanian Museum and Art Gallery, Hobart, Tasmania
- -Other groups and individuals

The Department is extremely grateful to the many organisations and individuals who provided expert advice and information on numerous draft distributions.

Please feel free to provide feedback via the Contact Us page.

APPENDIX 3: FAUNA SURVEY



Fauna Assessment Lot 287



South Western Highway Gwindinup

March 2019 *V1*

On behalf of:
Mario Michel Giacci
C/- MBS ENVIRONMENTAL
4 Cook Street
WEST PERTH WA 6005

Prepared by:

Greg Harewood Zoologist PO Box 755 BUNBURY WA 6231 M: 0402 141 197 E: gharewood@iinet.net.au

TABLE OF CONTENTS

SUMMARY

1.	INTRODUCTION	1
2.	SCOPE OF WORKS	1
3.	METHODS	1
3.1	POTENTIAL FAUNA INVENTORY - LITERATURE REVIEW	1
	3.1.1 Database Searches	1
	3.1.2 Previous Fauna Surveys in the Area	2
	3.1.3 Existing Publications	3
	3.1.4 Fauna of Conservation Significance	4
	3.1.5 Invertebrate Fauna of Conservation Significance	6
	3.1.6 Likelihood of Occurrence – Fauna of Conservation Significance	6
	3.1.7 Taxonomy and Nomenclature	7
3.2	SITE SURVEYS	7
	3.2.1 Fauna Habitat Assessment	7
	3.2.2 Opportunistic Fauna Observations	8
	3.2.3 Black Cockatoo Habitat Assessment	8
	3.2.3.1 Black Cockatoo Breeding Habitat	9
	3.2.3.2 Black Cockatoo Foraging Habitat	10
	3.2.3.3 Black Cockatoo Roosting Habitat	10
	3.2.4 Other Species of Conservation Significance	10
4.	SURVEY CONSTRAINTS	10
5.	RESULTS	12
5.1	POTENTIAL FAUNA INVENTORY – LITERATURE REVIEW	12
5.2	SITE SURVEYS	12

	5.2.1 Fau	na Habitat Assessment
	5.2.2 Opp	portunistic Fauna Observations
	5.2.3 Blad	ck Cockatoo Habitat Assessment
	5.2.3.1 Bla	ack Cockatoo Breeding Habitat
	5.2.3.2 Bla	ack Cockatoo Foraging Habitat16
	5.2.3.3 Bla	ack Cockatoo Roosting Habitat17
	5.2.4 Oth	er Species of Conservation Significance
5.3	FAUNA IN	IVENTORY – SUMMARY
	5.3.1 Ver	tebrate Fauna17
	5.3.2 Ver	tebrate Fauna of Conservation Significance
	5.3.3 Inve	ertebrate Fauna of Conservation Significance
6.	CONCLU	SION
7.	REFEREN	NCES5
TABL	ES	
TABL	E 1:	Main Fauna Habitats within the Subject Site
TABL	E 2:	Summary of Potential Black Cockatoo Habitat Trees within the Subject Site
TABL	E 3:	Summary of Potential Vertebrate Fauna Species (as listed in Appendix B)
TABL	E 4:	Likelihood of Occurrence – Fauna Species of Conservation Significance
FIGUI	RES	
FIGUE	RE 1:	Subject Site & Surrounds
FIGUE	RE 2:	Subject Site – Aerial Photograph
FIGURE 3:		Vegetation Units (Courtesy DMBC 2019)
FIGUE	RE 4:	Habitat Trees (DBH ≥50cm)

APPENDICES

APPENDIX A: Conservation Categories

APPENDIX B: Fauna Observed or Potentially Present

APPENDIX C: DBCA & EPBC Database Search Results

APPENDIX D: Black Cockatoo Habitat Tree Details

Acronyms/Abbreviations:

ALA: Atlas of Living Australia www.ala.org.au

BA: Birdlife Australia (Formerly RAOU, Birds Australia).

BC Act: Biodiversity Conservation Act 2016. WA Government.

°C: Degrees Celsius.

CALM: Department of Conservation and Land Management (now DPaW), WA Government.

CAMBA: China Australia Migratory Bird Agreement 1998.

CBD: Central Business District.

DBH: Diametre at Breast Height – tree measurement.

DEC: Department of Environment and Conservation (now DPaW), WA Government.

DEH: Department of Environment and Heritage (now DotEE), Australian Government.

DEP: Department of Environment Protection (now DER), WA Government.

DER: Department of Environment Regulation (formerly DEC, DoE), WA Government.

DEWHA: Department of the Environment, Water, Heritage and the Arts (now DotEE), Australian Government

DMP: Department of Mines and Petroleum (formerly DoIR), WA Government.

DoE: Department of Environment (now DER/DPaW), WA Government.

DoP: Department of Planning, WA Government.

DotE: Department of the Environment (now DotEE), Australian Government.

DotEE: Department of the Environment and Energy (formerly SEWPaC, DWEHA, DEH & DotE), Australian Government.

DoIR: Department of Industry and Resources (now DMP), WA Government.

DPaW: Department of Parks and Wildlife (formerly DEC, CALM, DoE), WA Government.

EP Act: *Environmental Protection Act 1986*, WA Government.

EPA: Environmental Protection Authority, WA Government.

EPBC Act: Environment Protection and Biodiversity Conservation Act 1999, Australian Government.

ha: Hectare (10,000 square metres).

IBRA: Interim Biogeographic Regionalisation for Australia.

IUCN: International Union for the Conservation of Nature and Natural Resources – commonly known as the World Conservation Union.

JAMBA: Japan Australia Migratory Bird Agreement 1981.

km: Kilometre.

m: Metre.

mm: Millimetre.

P: Priority - DPaW fauna conservation ranking.

POS: Public Open Space.

RAOU: Royal Australia Ornithologist Union.

ROKAMBA: Republic of Korea-Australia Migratory Bird Agreement 2007.

S: Schedule - Western Australian *Wildlife Conservation Act (1950)* Threatened Fauna Category.

SEWPaC: Department of Sustainability, Environment, Water, Population and Communities (now DotEE), Australian Government.

SRE: Short Range Endemic.

SSC: Species Survival Commission, International.

WA: Western Australia.

WAM: Western Australian Museum, WA Government.

WAPC: Western Australian Planning Commission, WA Government.

WC Act: Wildlife Conservation Act 1950, WA Government.

WRP: Western Ringtail Possum

SUMMARY

This report details the results of a fauna assessment Lot 287, South Western Highway Gwindinup (the subject site). Lot 287 has a total area of about 60 ha. About 31 ha of the subject site was historically cleared and subsequently used for an extraction industry operation and bluegum plantations. The balance of the area (~19 ha) contains remnant native vegetation (~19 ha).

It is understood that the landowner (Mr Mario Giacci) is investigating the potential to expand the existing extractive industry operation within the subject site. The fauna assessment reported on here represents one of several technical reports that will be used to provide an understanding of the suite of environmental values present within the subject site which will be used during the ongoing planning and approval process.

The scope of works was to conduct a level 1 fauna survey as defined by the EPA (EPA 2016). Because some listed threatened species (i.e. three species of black cockatoo) are known to occur in the general area, the scope of the survey work was expanded to include targeted assessment of the site's significance to these particular species. The assessment has included a literature review ("desktop study"), a series of day time surveys carried out in February 2018.

With respect to native vertebrate fauna, 29 mammal (including nine bat species), 92 bird, 36 reptile and three frog species have previously been recorded in the general area, some of which have the potential to occur in or utilise sections of the subject site at times, a conclusion largely based on the presence of apparently suitable habitat.

Descriptions and example images of the main fauna habitats/dominant vegetation present within the subject site are provided in Table 1, with the location and extent of each unit being depicted in Figure 3.

The remnant native vegetation remaining within the subject site is in general terms comprised of various densities of jarrah, marri/mountain marri and banksia over shrubland on pisolitic gravel or sandy pisolitic gravel. The majority appears to have been subject to historical logging with most trees being relatively young in age. Groundcover is generally sparse suggesting historical clearing, grazing and/or frequent fires. Some small areas have been subject to gravel extraction in the past and subsequently partially regenerated.

Overall fauna habitat quality appears to be good and it can be expected that a high percentage of the predicted species (Appendix B) would utilise the subject site.

Opportunistic fauna observations made during the survey period are listed in Appendix B. A total of 25 fauna species were observed (or positively identified from foraging evidence, scats, tracks, skeletons or calls) within the subject site during the day time surveys.

The black cockatoo habitat assessment identified 405 trees within the subject site with a DBH of >50cm. Most (330 - 81.5%) of these trees did not appear to contain hollows of any size. Forty nine (\sim 12.1%) were assessed as possibly having hollows, but of a likely size or orientation

that was deemed unsuitable for black cockatoos to utilise. Twenty six (6.4%) appeared to contain hollows possibly large enough for black cockatoos to use for nesting, though this assessment was based on the size of the entrance into an apparent hollow only. No conclusive evidence of any hollows being used by black cockatoos for nesting (currently or previously) was seen though two hollows appeared to have significant rub marks which is indicates use by fauna of some type, possibly common brushtail possums.

Additional details on each habitat tree observed can be found in Appendix D.

Evidence of all two species of black cockatoos foraging within the subject site was observed. The main foraging evidence left was in the form of chewed marri/mountain fruits, with most of this evidence being attributed to the forest red-tailed black-cockatoo. A small number of examples of Baudin's foraging on marri was also seen.

Almost all (~19 ha) of the remnant native vegetation within the subject site can be regarded as foraging habitat for black cockatoos given the presence of the marri, jarrah and banksia in various concentrations in all remnants. No existing roosting trees (trees used at night by black cockatoos to rest) were positively identified during the survey.

Besides the two species of black cockatoo recorded, evidence of one additional fauna species of conservation significance was observed during the survey period, this being the western ringtail possum. Evidence of this species was found in the form of some scats under a tree and a nearby drey (unoccupied).

In summary three vertebrate fauna species of conservation significance were positively identified as utilising the subject site for some purpose during the survey period, these being:

- forest red-tailed black cockatoo Vulnerable (WA/Federal);
- Baudin's black cockatoo Endangered (WA/Federal); and
- western ringtail possum Critically Endangered (WA/Federal).

An additional nine species of conservation significance may also utilise the subject site, though, as no evidence of these species presence was identified during the field survey, the status of some in the area remains uncertain. These species are:

- coastal plains skink P3 (DBCA Priority Species);
- masked owl P3 (DBCA Priority Species);
- south-western brush-tailed phascogale S6 (WC Act);
- Carnaby's cockatoo Endangered (WA/Federal);
- peregrine falcon Schedule 7 (WA);
- quenda Priority 4 (WA);

- western brush wallaby Priority 4 (WA); and
- western false pipistrelle P4 (DBCA Priority Species).

One invertebrate species of conservation significance has also been assessed as possibly occurring based on available information. The western pygmy trapdoor spider (Priority 3) has been collected in a state forest near the subject site (DBCA 2019) so it must be regarded as a potential species though its actual status within the subject site is unknown.

The exact location of proposed development within the subject site is yet to be finalise. Ongoing planning will need to take into account the potential presence of habitat used by some species of conservation significance and fauna in general so that any direct and indirect impacts can be avoided or minimised. Management plans and protocols that aim to minimise impact on fauna and fauna habitat should be employed if considered warranted.

1. INTRODUCTION

This report details the results of a fauna assessment of Lot 287, South Western Highway Gwindinup (the subject site) (Figures 1 and 2).

Lot 287 has a total area of about 60 ha. About 14 ha of the subject site was historically cleared and subsequently used for an extraction industry operation with the balance of the area containing a bluegum plantation (~27 ha) and remnant native vegetation (~19 ha).

It is understood that the landowner (Mr Mario Giacci) is investigating the potential to expand the existing extractive industry operation within the subject site. The fauna assessment reported on here represents one of several technical reports that will be used to provide an understanding of the suite of environmental values present within the subject site which will be used during the ongoing planning and approval process.

2. SCOPE OF WORKS

The scope of works was to conduct a Level 1 fauna survey as defined by the EPA (EPA 2016). Because the general area is known to be utilised by black cockatoos the scope of the survey work was expanded to include a baseline assessment of the sites significance to these species as well. The fauna assessment has therefore included:

- 1. Level 1 fauna assessment (in accordance with EPA (2016) guidelines);
- 2. Targeted searches for black cockatoo habitat/site use (habitat trees, existing and potential nest hollows, foraging and roosting habitat);
- 3. Report summarising methods, results and conclusions.

Note: For the purposes of this report the term black cockatoo is in reference to Baudin's black cockatoo *Calyptorhynchus baudinii*, Carnaby's black cockatoo *Calyptorhynchus latirostris* and the forest red-tailed black cockatoo *Calyptorhynchus banksii naso*.

3. METHODS

3.1 POTENTIAL FAUNA INVENTORY - LITERATURE REVIEW

3.1.1 Database Searches

Searches of the following databases were undertaken to aid in the compilation of a list of conservation significant fauna potentially occurring within the subject site:

- DBCA's NatureMap Database Search (combined data from DBCA, ALA, WAM, BA and consultant's reports) (DBCA 2019); and
- Protected Matters Search Tool (DotEE 2019).

It should be noted that lists produced during the abovementioned database searches contain observations/inferred distributions from a broader area than the subject site and therefore may include species that would only ever occur as vagrants due to a lack of suitable habitat or the presence of only marginal habitat within the subject site itself. The databases also often include or are based on very old records and in some cases certain species have become locally or regionally extinct.

Information from these sources should therefore be taken as indicative only and local knowledge and information also needs to be taken into consideration when determining what actual species may be present within the specific area being investigated.

3.1.2 Previous Fauna Surveys in the Area

Fauna surveys, assessments and reviews have been undertaken in nearby areas in the past, though not all are publicly available and could not be referenced. The most significant of those available have been used as the primary reference material for compiling the potential fauna assemblage for the general area.

Those reports referred to included, but were not limited to:

- Bamford, M.J and A.R. (2000). Proposed Gwindinup Mineral Sands Mine. Fauna Surveys; August and December 1999. Unpublished report for Cable Sands WA. January 2000.
- Bancroft, W. and Bamford, M. (2008). Fauna values of Bemax's Happy Valley mineral sands deposit. Unpublished report for Bemax Resources Limited. January 2008.
- Biologic (2014). Wonnerup North Vertebrate Fauna Assessment. Unpublished report for Cristal Mining Australia Ltd.
- Biota (2009). Tutunup Fauna Assemblage and Fauna Habitat Seasonal Survey.
 Unpublished report for Iluka Resources. March 2009.
- Biota (2007a). Yoganup 215 Strand Fauna and Faunal Assemblage Survey.
 Unpublished report for Iluka Resources. February 2007.
- Biota (2007b). Tutunup South Fauna Habitat and Fauna Assemblage Seasonal Survey. Unpublished report for Iluka Resources. December 2007.
- Harewood, G. (2009). Western Ringtail Possum Baseline Assessment. Tutunup. Unpublished report for Iluka Resources. August 2009.

- Harewood, G. (2012). Phase 1 and 2 Seasonal Fauna Surveys (Level 2).
 Yoongarillup Mineral Sands Project. Unpublished report for Doral Mineral Sands Pty Ltd.
- Harewood, G. (2013). Fauna Assessment of Yoganup Extended. Unpublished report for Iluka Resources Ltd.
- Harewood, G. (2017). Fauna Assessment of Lot 3833 (Part) Hyder Road Yoganup Extended. Unpublished report for Iluka Resources Ltd.
- Harewood, G. (2018). Western Ringtail Possum 2018 Monitoring Survey, Gwindinup North Mineral Sands Mine, June/July 2018. Unpublished report for Cristal Mining Australia Limited. September 2016.
- Hart, Simpson and Assoc. (1997). Wonnerup -Tutunup Road Vertebrate Fauna.
 Unpublished report for Westralian Sands Ltd.
- Ninox (2006). A Vertebrate Fauna Assessment of the Yoganup Mineral Sands Project Area. Unpublished report for Iluka Resources. March 2006.

As with the database searches some reports refer to species that would not occur in the subject site due to a lack of suitable habitat (extent and/or quality) and this fact was taken into consideration when compiling the potential fauna species list. It should also be noted that the NatureMap database is likely to include some records from previous fauna surveys in the area, including some of those listed above.

3.1.3 Existing Publications

The following represent the main publications used to identify and refine the potential fauna species list for the subject site:

- Anstis, M. (2013). Tadpoles and Frogs of Australia. New Holland Publishers, Sydney.
- Barrett, G., Silcocks, A., Barry, S., Cunningham, R. and Poulter, R. (2003). The New Atlas of Australian Birds. Royal Australasian Ornithologists Union, Victoria.
- Bush, B., Maryan, B., Browne-Cooper, R. & Robinson, D. (2007). Reptiles and Frogs in the Bush: Southwestern Australia. UWA Press, Nedlands.
- Bush, B., Maryan, B., Browne-Cooper, R. & Robinson, D. (2010). Field Guide to Reptiles and Frogs of the Perth Region. UWA Press, Nedlands.
- Churchill, S. (2008). Australian Bats. Second Edition, Allen & Unwin.
- Cogger, H.G. (2014). Reptiles and Amphibians of Australia. 7th Edition. CSIRO Publishing.

- Johnstone, R.E. and Storr, G.M. (1998). Handbook of Western Australian Birds: Volume 1 – Non-passerines (Emu to Dollarbird). Western Australian Museum, Perth Western Australia.
- Johnstone, R.E. and Storr, G.M. (2004). Handbook of Western Australian Birds: Volume 2 – Passerines (Blue-winged Pitta to Goldfinch). Western Australian Museum, Perth Western Australia.
- Menkhorst, P. and Knight, F. (2011). A Field Guide to the Mammals of Australia.
 Oxford University Press, Melbourne.
- Morgan, D.L., Beatty, S.J., Klunzinger, M.W, Allen, M.G. and Burnham, Q.E (2011).
 Field Guide to the Freshwater Fishes, Crayfishes and Mussels of South Western Australia. Published by SERCUL.
- Storr, G.M., Smith, L.A. and Johnstone R.E. (1983). Lizards of Western Australia II: Dragons and Monitors. WA Museum, Perth.
- Storr, G.M., Smith, L.A. and Johnstone R.E. (1990). Lizards of Western Australia III: Geckos and Pygopods. WA Museum, Perth.
- Storr, G.M., Smith, L.A. and Johnstone R.E. (1999). Lizards of Western Australia I: Skinks. Revised Edition, WA Museum, Perth.
- Storr, G.M., Smith, L.A. and Johnstone R.E. (2002). Snakes of Western Australia. Revised Edition, WA Museum, Perth.
- Tyler M.J. & Doughty P. (2009). Field Guide to Frogs of Western Australia, Fourth Edition, WA Museum, Perth.
- Van Dyck, S., Gynther, I. & Baker, A. Eds (2013). Field Companion to The Mammals of Australia. Queensland Museum.
- Wilson, S. and Swan, G. (2017). A Complete Guide to Reptiles of Australia. Reed, New Holland, Sydney.
- Woinarski, J., Burbidge, A. & Harrison, P. (2014). The Action Plan for Australian Mammals 2012. CSIRO Publishing.

3.1.4 Fauna of Conservation Significance

The conservation significance of fauna species has been assessed using data from the following sources:

Environment Protection and Biodiversity Conservation Act 1999 (EPBC Act).
 Administered by the Australian Government Department of the Environment and Energy (DotEE);

- Wildlife Conservation Act 1950 (WC Act). Administered by the Western Australian DBCA (Govt. of WA 2018). Note: The Wildlife Conservation (Specially Protected Fauna) Notice 2018 has been transitioned under regulations 170, 171 and 172 of the Biodiversity Conservation Regulations 2018 to be the lists of Threatened, Extinct and Specially Protected species under Part 2 of the Biodiversity Conservation Act 2016 (BC Act);
- Red List produced by the Species Survival Commission (SSC) of the World Conservation Union (also known as the IUCN Red List - the acronym derived from its former name of the International Union for Conservation of Nature and Natural Resources). The Red List has no legislative power in Australia but is used as a framework for State and Commonwealth categories and criteria; and the
- DBCA Priority Fauna list. A non-statutory list maintained by the DBCA for management purposes (DBCA 2018).

The *EPBC Act* also requires the compilation of a list of migratory species that are recognised under international treaties including the:

- Japan Australia Migratory Bird Agreement 1981 (JAMBA);
- China Australia Migratory Bird Agreement 1998 (CAMBA);
- Republic of Korea-Australia Migratory Bird Agreement 2007 (ROKAMBA); and
- Bonn Convention 1979 (The Convention on the Conservation of Migratory Species of Wild Animals).

(Note – Some but not all species listed under JAMBA are also protected under Schedule 5 of the BC/WC Act.)

Most, but not all migratory bird species listed in the annexes to these bilateral agreements are also protected in Australia as matters of national environmental significance (NES) under the *EPBC Act*.

The conservation status of all vertebrate fauna species listed as occurring or possibly occurring in the vicinity of the subject site has been assessed using the most recent lists published in accordance with the above-mentioned instruments and is indicated as such in the fauna listings of this report. A full listing of conservation codes are provided in Appendix A.

A number of other species not listed in official lists can also be considered of local or regional conservation significance. These include species that have a restricted range, those that occur in breeding colonies and those at the limit of their range.

3.1.5 Invertebrate Fauna of Conservation Significance

For this assessment the review of potential conservation significant invertebrates has been limited to those listed by the DBCA and *EPBC Act* database searches (which rely on distribution records and known habitat preferences).

No assessment of the potential for SREs to be present has been made as it can be difficult to identify significant invertebrate species due to uncertainties in determining the range-restrictions of many species due to lack of surveys, lack of taxonomic resolutions within target taxa and problems in identifying certain life stages.

Where invertebrates are collected during surveys, a high percentage are likely to be unknown, or for known species there can be limited knowledge or information on their distribution (Harvey 2002).

3.1.6 Likelihood of Occurrence - Fauna of Conservation Significance

Fauna of conservation significance identified during the literature review as previously being recorded in the general area were assessed and ranked for their likelihood of occurrence within the subject site itself. The rankings and criteria used were:

- Would Not Occur: There is no suitable habitat for the species in the subject site and/or there is no documented record of the species in the general area since records have been kept and/or the species is generally accepted as being locally/regionally extinct (supported by a lack of recent records).
 - Locally Extinct: Populations no longer occur within a small part of the species natural range, in this case within 10 or 20km of the subject site. Populations do however persist outside of this area.
 - Regionally Extinct: Populations no longer occur in a large part of the species natural range, in this case within the southern/central forest region.
 Populations do however persist outside of this area.
- Unlikely to Occur: The subject site is outside of the currently documented distribution
 for the species in question, or no suitable habitat (type, quality and extent) was
 identified as being present during the field assessment. Individuals of some species
 may occur occasionally as vagrants/transients especially if suitable habitat is located
 nearby but the subject site itself would not support a population or part population of
 the species.
- Possibly Occurs: The subject site is within the known distribution of the species in
 question and habitat of at least marginal quality was identified as being present during
 the field assessment, supported in some cases by recent records being documented
 in literature from within or near the subject site. In some cases, while a species may
 be classified as possibly being present at times, habitat may be marginal (e.g. poor

quality, fragmented, limited in extent) and therefore the frequency of occurrence and/or population levels may be low.

• Known to Occur: The species in question was positively identified as being present (for sedentary species) or as using the subject site as habitat for some other purpose (for non-sedentary/mobile species) during the field survey. This information may have been obtained by direct observation of individuals or by way of secondary evidence (e.g. foraging debris, tracks and scats). In some cases, while a species may be classified as known to occur, habitat may be marginal (e.g. poor quality, fragmented, limited in extent) and therefore the frequency of occurrence and/or population levels may be low.

3.1.7 Taxonomy and Nomenclature

Taxonomy and nomenclature for vertebrate fauna species used in this report is generally taken from the DBCA's WA Fauna Census Database which is assumed to follow Aplin and Smith (2001) for amphibians and reptiles and Johnstone (2001) for birds. Jackson and Groves (2015) has been used for mammals.

Common names are taken from the Western Australia Museum (WAM) recognised primary common name listings when specified, though where common names are not provided, they have been acquired from other publications. Sources include Cogger (2014), Wilson and Swan (2017), Van Dyck & Strahan (2013), Christidis and Boles (2008), Bush *et al.* (2010), Bush *et al.* (2007), Tyler & Doughty (2009), and Glauret (1961). Not all common names are generally accepted.

3.2 SITE SURVEYS

Daytime field survey work at the subject site was carried out on the 27 and 28 February 2019. All survey work was done by Greg Harewood (Zoologist).

3.2.1 Fauna Habitat Assessment

The vegetation communities mapped by DMBC (DMBC 2019) during the flora and vegetation survey have been used to classify the area into broad habitat types. This information has been supplemented by observations made during the field assessment undertaken during the fauna assessment.

As part of the literature review, available information on the habitat requirements of the species of conservation significance listed as possibly occurring in the area was researched. During the daytime reconnaissance survey the habitats within the subject site were assessed and specific elements identified, if present, to determine the likelihood of listed species of conservation significance occurring and its likely overall value to them on a local and regional scale.

The vegetation communities and landforms present have been used to classify the area into broad habitat types. As part of the literature review, available information on the habitat requirements of the species of conservation significance listed as possibly occurring in the area was researched. During the daytime survey the habitats within the subject site were assessed and specific elements identified, if present, to determine the likelihood of listed species of conservation significance occurring and its likely overall value to them on a local and regional scale.

3.2.2 Opportunistic Fauna Observations

Opportunistic observations of fauna species were made during all field survey work which primarily involved a series of transects across the subject site during the day while searching microhabitats such as logs, rocks, leaf litter and observations of bird species with binoculars. Secondary evidence of a species presence such as tracks, scats, skeletal remains, foraging evidence or calls were also noted if observed/heard.

3.2.3 Black Cockatoo Habitat Assessment

The following methods were employed to comply with the defined scope of works and are based on guidelines published by the federal DotEE (Commonwealth of Australia 2012) which states that surveys for Carnaby's, Baudin's and forest red-tailed black cockatoo habitat should:

- be done by a suitably qualified person with experience in vegetation or cockatoo surveys, depending on the type of survey being undertaken;
- maximise the chance of detecting the species' habitat and/or signs of use;
- determine the context of the site within the broader landscape—for example, the amount and quality of habitat nearby and in the local region (for example, within 10 km);
- account for uncertainty and error (false presence and absences); and
- include collation of existing data on known locations of breeding and feeding birds and night roost locations.

Habitat used by black cockatoos have been placed into three categories by the DotEE (Commonwealth of Australia 2012) these being:

- Breeding Habitat;
- · Foraging Habitat; and
- Night Roosting Habitat.

So as to comply with the requested scope of works and in line with the published guidelines the following was carried out.

3.2.3.1 Black Cockatoo Breeding Habitat

The black cockatoo breeding habitat assessment has involved the identification of all suitable breeding trees species within the subject site that have a Diameter at Breast Height (DBH) of equal to or over 50cm. The DBH of each tree was estimated using a pre-made 50 cm "caliper".

Target tree species included marri and jarrah and any other *Corymbia/Eucalyptus* species of a suitable size that were present. Peppermints, *banksia*, sheoak and melaleuca tree species (for example) were not assessed as they typically do not develop hollows that are used by black cockatoos.

The location of each tree identified as being over the threshold DBH was recorded with a GPS and details on tree species, number and size of hollows (if any) noted. Trees observed to contain hollows (of any size/type) were marked with "H" using spray paint.

Potential hollows were placed into one of four categories, based on the size of the apparent hollow entrance, these being

- Small = ~<5cm diametre (i.e. entrance too small for a black cockatoo);
- Medium = ~5cm-10cm diametre (i.e. entrance too small for a black cockatoo);
- Large = ~>10cm diametre (entrance large enough for a black cockatoo but possible hollow appears to be unsuitable for nesting i.e. wrong orientation, too small, too low or too shallow); or
- Large (cockatoo) = ~>10cm diametre (entrance appears big enough to provide access to a possible hollow that may be suitable for a black cockatoo to use for nesting).

Based on this assessment trees present within the subject site have then been placed into one of four categories:

- Tree < 50cm DBH or an unsuitable species (not assessed/recorded);
- Tree >50cm DBH, no hollows seen;
- Tree >50cm DBH, one or more hollows seen, none of which were considered suitable for black cockatoos to use for nesting; or
- Tree >50cm DBH, one or more hollows seen, with at least one considered suitable or possibly for black cockatoos to use for nesting.

For the purposes of this study a tree containing a potential cockatoo nest hollow was defined as:

Generally, any tree which is alive or dead that contains one or more hollows or possible hollows (cavities within the trunk or branches) which appear suitable for occupation by black cockatoos for the purpose of nesting/breeding. Hollows or apparent hollows that had an entrance greater than about 10cm in diameter and would allow the entry of a black cockatoo into a suitably orientated and sized branch/trunk, were recorded as a "potential nest hollow".

Identified hollows were examined using binoculars for evidence of actual use by black cockatoos (e.g. chewing around hollow entrance, scarring and scratch marks on trunks and branches).

3.2.3.2 Black Cockatoo Foraging Habitat

The location and nature of black cockatoo foraging evidence (e.g. chewed fruits around the base of trees) observed during the field survey was recorded. The nature and extent of potential foraging habitat present was also documented irrespective of the presence of any actual foraging evidence.

3.2.3.3 Black Cockatoo Roosting Habitat

Direct and indirect evidence of black cockatoos roosting within trees within the subject site was noted if observed (e.g. branch clippings, droppings or moulted feathers).

3.2.4 Other Species of Conservation Significance

Evidence of the presence or likely presence of other species of conservation significance (including suitable habitat) was searched for and recorded concurrent with other field work. The aim was to obtain sufficient information to make a definitive comment on the likely significance of the subject site to other species of conservation significance which may be present.

4. SURVEY CONSTRAINTS

No seasonal sampling has been carried out as part of this fauna assessment. The conclusions presented are based upon field data and the environmental monitoring and/or testing carried out over a limited period of time and are therefore merely indicative of the environmental condition of the subject site at the time of the field assessments. It should also be recognised that site conditions can change with time.

Some fauna species are reported as potentially occurring within the subject site based on there being suitable habitat (quality and extent) within the subject site or immediately adjacent. With respect to opportunistic observations, the possibility exists that certain species may not have been detected during field investigations due to:

- seasonal inactivity during the field survey;
- species present within micro habitats not surveyed;
- cryptic species able to avoid detection; and
- transient wide-ranging species not present during the survey period.

Lack of observational data on some species should therefore not necessarily be taken as an indication that a species is absent from the subject site.

The habitat requirements and ecology of many of the species known to occur in the wider area are often not well understood or documented. It can therefore be difficult to exclude species from the potential list based on a lack of a specific habitat or microhabitat within the subject site. As a consequence of this limitation the potential fauna list produced is most likely an overestimation of those species that actually utilise the subject site for some purpose. Some species may be present in the general area but may only use the subject site itself on rare occasions or as vagrants/transients.

In recognition of survey limitations, a precautionary approach has been adopted for this assessment. Any fauna species that would possibly occur within the subject site (or immediately adjacent), as identified through ecological databases, publications, discussions with local experts/residents and the habitat knowledge of the Author, has been assumed to potentially occur in the subject site.

During the black cockatoo habitat survey a search for trees containing hollows was completed. It should be noted that identifying hollows suitable for fauna species from ground level has limitations. Generally, the full characteristics of any hollow seen are not fully evident (e.g. internal dimensions). It is also difficult to locate all hollows within all trees as some are not observable from ground level.

The location of observations was recorded using a handheld GPS. The accuracy of the GPS cannot be guaranteed above a level of about 5 to 10 metres, though it should be noted that in some circumstance the accuracy can increase or decrease beyond this range.

5. RESULTS

5.1 POTENTIAL FAUNA INVENTORY – LITERATURE REVIEW

A list of fauna species considered most likely to occur in the subject site has been compiled from information obtained during the literature review and is presented in Appendix B. This listing was refined after information gathered during the site reconnaissance survey was assessed.

The results of some previous fauna surveys carried out in the general area are summarised in this species listing as are the DBCA NatureMap database search results. Species considered unlikely to occur with the subject site but previously recorded in other surveys and/or which appear in the DBCA database search are not listed. The raw database search results from NatureMap (DBCA 2019) and the Protected Matters Search Tool (DotEE 2019) are contained within Appendix C.

The list of potential fauna takes into consideration that firstly the species in question is not known to be locally extinct and secondly that suitable habitat for each species, as identified during the habitat assessment, is present within the subject site. Compiling an accurate fauna list has limitations (see Section 4 above) and therefore the listing is likely to be an overestimation of the fauna species actually present within the subject site at any one time.

With respect to native vertebrate fauna, 29 mammals (includes nine bat species), 92 bird, 36 reptile and three frog species have previously been recorded in the general area, some of which have the potential to occur in or utilise sections of the subject area at times. Nine species of introduced animals could also frequent the area.

Of the 154 native animals that are listed as potentially occurring in the area, seven are considered to be endangered/vulnerable or in need of special protection under State and/or Federal law. In addition, five DBCA priority species have also been listed as potentially present.

5.2 SITE SURVEYS

5.2.1 Fauna Habitat Assessment

The western section of the subject site located on the upper slope of the Whicher Scarp which is an arcuate north-facing scarp formed during the late Tertiary and early Pleistocene by marine erosion of underlying sedimentary rocks and in this area marks the inland limit of the Swan Coastal Plain (Note: in some documents the Whicher Scarp is referred to as being entirely within the Southern Jarrah Forest Biogeographic Sub-region e.g. EPA 2009). The eastern section of Lot 287 slopes down to a valley created by the Preston River.

The Swan Coastal Plain (SWA) was classified as part of the Interim Biogeographical Regionalisation for Australia and is in broad terms described as a:

"Low lying coastal plain mainly covered with Woodlands. It is dominated by Banksia or Tuart on sandy soils, Allocasuarina obesa on outwash plains, and paperbark in swampy areas. In the east, the plain rises to duricrusted Mesozoic sediments dominated by Jarrah Woodland. Warm Mediterranean. Three phases of marine sand dune development provide relief. The outwash plains, once dominated by A. obesa – Marri Woodlands and Melaleuca shrublands, are extensive only in the south." (Thackway and Cresswell, 1996; IBRA, 2000).

The subject site itself is within a further defined subregion of the SWA referred to as the Swan Coastal Plan subregion or the Perth subregion (SWA2). This is defined as:

"Colluvial and aeolian sands, alluvial river flats, coastal limestone. Heath and/or Tuart woodlands on limestone, Banksia and Jarrah - Banksia woodlands on Quaternary marine dunes of various ages, Marri on colluvial and alluvials. Includes a complex series of seasonal wetlands and also includes Rottnest, Carnac and Garden Islands etc. Rainfall ranges between 600 and 1000 mm annually and the climate is Mediterranean". The subregion has an area of about 1, 333,900 ha (Mitchell et al. 2002).

The remnant native vegetation remaining within the subject site is in general terms comprised of various densities of jarrah, marri/mountain marri and *banksia* over shrubland on pisolitic gravel or sandy pisolitic gravel. The majority appears to have been subject to historical logging with most trees being relatively young in age. Groundcover is generally sparse suggesting historical clearing, grazing and/or frequent fires. Some small areas have been subject to gravel extraction in the past and subsequently partially regenerated.

Descriptions and example images of the main fauna habitats/dominant vegetation present within the subject site are provided in Table 1. The location and extent of each of the identified habitat/vegetation units is shown in Figure 3 (data courtesy DMBC 2019).

Table 1: Main Fauna Habitats within the Subject Site

Unit	Fauna Habitat Description	Example Image					
VT1	Tall woodland of jarrah (Eucalyptus marginata) and marri (Corymbia calophylla) over low woodland of Banksia grandis over tall sparse shrubland of Kunzea glabrescens over low sparse shrubland of Xanthorrhoea preissii. Total Area = ~0.79 ha (1.7%)						

Unit	Fauna Habitat Description	Example Image
VT2	Tall woodland of jarrah (<i>E. marginata</i>) and marri (<i>C. calophylla</i>) over tall sparse shrubland of <i>Kunzea glabrescens</i> over low sparse shrubland of <i>Xanthorrhoea preissii</i> and <i>Xanthorrhoea gracilis</i> . Total Area = ~0.84 ha (~1.4%)	
VT3	Tall woodland of jarrah (<i>E. marginata</i>) and (<i>C. calophylla</i>) over low sparse shrubland of <i>Xanthorrhoea preissii</i> and <i>Hibbertia hypericoides</i> Total Area = ~17.39 ha (~28.6%)	
D	Disturbed: Bluegum plantations, tracks and clearings Total Area = 40.98 ha (~68.3%)	

Overall fauna habitat quality in areas of natural bushland appears to be good and it can be expected that a high percentage of the predicted species would utilise the subject site. For some species the habitat may however be marginal in quality, mainly due to the sparse nature of the ground cover generally present and also due to a lack of canopy connectivity, particularly in the midstorey vegetation.

Based on available vegetation mapping it is estimated that there is approximately 21,500 ha of native vegetation within 12 km the subject site. Remnant native vegetation present within the subject site (total ~19 ha) makes up ~0.088% of this total.

5.2.2 Opportunistic Fauna Observations

Opportunistic fauna observations are listed in Appendix B. A total of 25 native fauna species were observed (or positively identified from foraging evidence, scats, tracks, skeletons or calls) within the subject site during the course of site surveys. Most of the fauna species recorded were common, widespread bird species.

Evidence of three listed threatened species was observed (forest red-tailed (Vulnerable) and Baudin's black-cockatoo (Endangered) - chewed marri fruits at several locations and the western ringtail possum (Critically Endangered) – scats and a drey at one location). No evidence of any listed migratory or priority fauna species was found.

5.2.3 Black Cockatoo Habitat Assessment

5.2.3.1 Black Cockatoo Breeding Habitat

Trees considered potentially suitable for black cockatoos to use as nesting habitat (using DotEE criteria i.e. DBH ≥50cm (Commonwealth of Australia 2012) but ultimately subject to a suitable hollow being present or developing and a range of other factors) which were found within the subject site comprised the following species:

- Jarrah Eucalyptus marginata;
- Marri Corymbia calophylla;
- Mountain Marri Corymbia haematoxylon; and
- Dead unidentified species.

A summary of the potential black cockatoo habitat trees observed within the subject site area is provided in Table 2 below and their location shown in Figure 4.

Table 2: Summary of Potential Black Cockatoo Habitat Trees (DBH ≥50cm) within the Subject Site

		Number of	Number of	Tree Species			
Total Number of Habitat Trees Recorded	Number of Trees with No Hollows Observed	Trees with Hollows Considered Unsuitable for Nesting Black Cockatoos	Trees with Hollows Considered Possibly Suitable for Nesting Black Cockatoos	Jarrah	Marri/Mountain Marri	Dead Unknown	
405	330	49	26	249	141	15	

The assessment identified 405 trees within the subject site with a DBH of ≥50cm. Most (330 – 81.5%) of these trees did not appear to contain hollows of any size. Forty nine (~12.1%) were assessed as possibly having hollows, but of a likely size or orientation that was deemed unsuitable for black cockatoos to utilise. Twenty six (6.4%) appeared to contain hollows possibly large enough for black cockatoos to use for nesting, though this assessment was based on the size of the entrance into an apparent hollow only. No conclusive evidence of any hollows being used by black cockatoos for nesting (currently or previously) was seen though two hollows appeared to have significant rub marks which is indicates use by fauna of some type, possibly common brushtail possums.

Additional details on each habitat tree observed can be found in Appendix D.

Based on available mapping, there is approximately 21,500 ha of remnant native vegetation within 12 kilometres of the subject site. Much of this is likely to contain "potential" breeding habitat (i.e. suitable tree species with a DBH ≥50cm).

5.2.3.2 Black Cockatoo Foraging Habitat

Following is a list of the main plant species observed within the subject site that are known to be used as a direct food source (i.e. fruits or flowers) by one or more species of black cockatoo:

- Jarrah Eucalyptus marginata;
- Marri Corymbia calophylla;
- Bull Banksia Banksia grandis;
- Couch Honeypot Dryandra Banksia dallanneyi;
- Honeybush Hakea lissocarpa (and possibly H. amplexicaulis); and
- Balga Xanthorrhoea preissii (and possibly X. gracilis

Evidence of two species of black cockatoos foraging within the subject site was observed. The main foraging evidence left was in the form of chewed marri/mountain fruits, with most of this evidence being attributed to the forest red-tailed black-cockatoo. A small number of examples of Baudin's foraging on marri was also seen.

Almost all (~19 ha) of the remnant native vegetation within the subject site can be regarded as foraging habitat for black cockatoos given the presence of the abovementioned plant species in various concentrations in all remnants.

Based on available vegetation mapping it is estimated that there is approximately 21,500 ha of native vegetation within 12 km the subject site, much of which is very likely to represent potential black cockatoo foraging habitat of some type.

5.2.3.3 Black Cockatoo Roosting Habitat

No existing roosting trees (trees used at night by black cockatoos to rest) were positively identified during the survey.

A review of the 2018 Great Cocky Count database shows no documented roost sites within the subject site. The closest active roost is located approximately 500 m north east of the subject site. This roost was in use by 193 White-tailed Black Cockatoos during the 2018 count (Peck *et al.* 2018). Another seven documented roost sites (but not necessarily in current use) occur within 12 km of the subject site.

5.2.4 Other Species of Conservation Significance

As indicated above and besides the two species of black cockatoo, evidence of one additional fauna species of conservation significance was observed during the survey period, this being the western ringtail possum. Evidence of this species was found in the form of some scats under a tree and a nearby drey (unoccupied).

No direct evidence of any other species of conservation significance being present was found however based on the habitats present an additional seven species are considered as potentially present though their actual status in the subject site is unknown. These species are discussed in more detail in the following sections.

5.3 FAUNA INVENTORY – SUMMARY

5.3.1 Vertebrate Fauna

Table 3 summarises the number of vertebrate fauna species potentially occurring within or utilising at times the subject site, based on results from the literature review and observations made during the field assessment. A complete list of vertebrate fauna possibly inhabiting or frequenting the subject site is located in Appendix B.

As previously discussed, despite the omission of some species it should be noted that the list provided is still very likely an over estimation of the fauna species utilising the subject site (either on a regular or infrequent basis) as a result of the precautionary approach adopted for the assessment. At any one time only a subset of the listed potential species are likely to be present within the bounds of the subject site.

Table 3: Summary of Potential Vertebrate Fauna Species (as listed in Appendix B)

Group	Total number of <u>Potential</u> species	Potential number of Specially Protected species	Potential number of <u>Migratory</u> species	Potential number of <u>Priority</u> species	Number of species recorded during field survey
Amphibians	3	0	0	0	0
Reptiles	36	0	0 0		1
Birds	95³	4	0	1	21
Non-Volant Mammals	20 ⁶	3	0	2	3
Volant Mammals (Bats)	9 0		0	1	0
Total	163 ⁹	7	0	5	25

Superscript = number of introduced species included in total.

5.3.2 Vertebrate Fauna of Conservation Significance

A review of the *EPBC Act* threatened fauna list, DBCA's Threatened Fauna Database and Priority List, unpublished reports and scientific publications identified a number of specially protected, priority or migratory vertebrate fauna species as potentially occurring in the general vicinity of the subject site. Of these species, most that have no potential whatsoever to utilise the subject site for any purpose have been omitted from the potential list (Appendix B), principally due to lack of suitable habitat (including extent and/or quality) or known local extinction.

Table 4 below listed those species previously recorded or considered potentially present in the wider area along with an assessment of their likelihood of occurrence within the subject site itself.

Table 4: Likelihood of Occurrence – Fauna Species of Conservation Significance (continues on following pages).

Species	Conservation Status		Habitat Preferences	Habitat Present	Likelihood of Occurrence	Comments	
	BC Act/ DBCA EPBC Act Priority						
Swan Coastal Plain Shield-backed Trapdoor Spider Idiosoma sigillatum	P3	-	Burrows of this species usually found in banksia woodland and heathland on sandy soils.	No/Marginal	Unlikely to Occur.	Habitat appears unsuitable.	
Western Pygmy Trapdoor Spider Bertmainius opimus	P3	-	Poorly documented - Lives in shallow burrows on eucalyptus bark or in topsoil.	?	Possibly occurs	Previously recorded in nearby state forest (DBCA 2019).	
Vasse Pachysaga (cricket) Pachysaga strobila	P1	-	Not documented.	?	Unlikely to Occur	Given the lack of published records and apparent knowledge on this species, its status within the subject site is difficult to determine, however the probability of it being present can be regarded as being extremely low	
Carter's Freshwater Mussel Westralunio carteri	\$3	VU	Occurs in greatest abundance in slower flowing streams with stable sediments that are soft enough for burrowing amongst woody debris and exposed tree roots.	No	Would Not Occur.	No suitable habitat.	
Pouched Lamprey Geotria australis	S3	VU	This species lives in mud burrows in the upper reaches of coastal streams for the first 4 years of life until migrating to the sea. Adults migrate up to 60km upstream during spawning.	No	Would Not Occur.	No suitable habitat.	
Coastal Plains Skink Ctenotus ora	P3	-	Sandy substrates with low vegetation (including heath) in open <i>Eucalyptus/Corymbia</i> woodland over <i>Banksia</i> .	Yes	Possibly occurs	Previously recorded at several locations along the Whicher Scarp (See Appendix B).	
Blue-billed Duck Oxyura australis	P4	-	Well vegetated freshwater swamps, large dams and lakes, winters on more open water. Occasionally salt lakes and estuaries freshened by floodwaters.	No	Would Not Occur.	No suitable habitat.	
Migratory Shorebirds/Wetland Species/Marine Species (various reptiles, birds and mammals)	S5, Various	Ma, Mig, Various	Varies between species but includes open ocean, beaches and permanent/temporary wetlands varying from billabongs, swamps, lakes, floodplains, sewerage farms, saltwork ponds, estuaries, lagoons, mudflats sandbars, pastures, airfields, sports fields and lawns.	No	Would Not Occur.	No suitable habitat.	
Eastern Osprey Pandion haliaetus	S5	Ma, Mig	Coasts, estuaries, bays, inlets, islands, and surrounding waters, coral atolls, reefs, lagoons, rock cliffs and stacks. Ascends larger rivers.	No	Would Not Occur.	May very occasionally fly along the nearby Preston River	

Species	Conservation Status		Habitat Preferences	Habitat Present	Likelihood of Occurrence	Comments	
	BC Act/ DBCA Priority	EPBC Act					
Peregrine Falcon Falco peregrinus	S7	-	Diverse from rainforest to arid shrublands, from coastal heath to alpine Mainly about cliffs along coasts, rivers and ranges and about wooded watercourses and lakes.	Yes	Possibly Occurs.	Uncommon but the subject site may represent part of a larger home range used by individuals of this species.	
Masked Owl (SW population) Tyto n. novaehollandiae	P3	-	Roosts and nests in heavy forest, hunts over open woodlands and farmlands.	Yes	Possibly Occurs.	Uncommon but may occur, if only occasionally.	
Barking Owl (SW population) Ninox connivens connivens	P2	-	Dense vegetation, especially forest and thickets of waterside vegetation such as <i>melaleucas</i> . Roosts in tree hollows.	No	Would Not Occur.	Habitat appears unsuitable and rarely recorded in his part of the south west.	
Australasian Bittern Botaurus poiciloptilus	S1	EN	Freshwater wetlands, occasionally estuarine; prefers heavy vegetation such as beds of tall dense <i>Typha, Baumea</i> and sedges in freshwater swamps.	No	Would Not Occur.	No suitable habitat.	
Black Bittern Ixobrychus flavicollis	P1	-	Freshwater pools, swamps and lagoons well screened with trees. Shelters in dense waterside vegetation.	No	Would Not Occur.	No suitable habitat.	
Little Bittern Ixobrychus minutus	P4	-	Dense vegetation surrounding/within freshwater pools, swamps and lagoons, well screened with trees. Shelters in dense beds of <i>Typha, Baumea</i> and tall rushes in freshwater swamps around lakes and along rivers.	No	Would Not Occur.	No suitable habitat.	
Carnaby`s Black Cockatoo Calyptorhynchus latirostris	S2	EN	Forests, woodlands, heathlands, farms; feeds on Banksia, Hakea and Marri.	Yes	Possibly Occurs.	Subject site contains areas of foraging habitat and potential breeding habitat.	
Baudin`s Black Cockatoo Calyptorhynchus baudinii	S2	EN	Mainly eucalypt forests where it feeds primarily on the marri seeds.	Yes	Known to Occur	Subject site contains areas of foraging habitat and potential breeding habitat.	
Forest Red-tailed Black Cockatoo Calyptorhynchus banksii naso	S3	VU	Eucalypt forests, feeds on marri, jarrah, blackbutt, karri, sheoak and snottygobble.	Yes	Known to Occur	Subject site contains areas of foraging habitat and potential breeding habitat.	
Fork-tailed Swift Apus pacificus	S5	Ma, Mig	Low to very high airspace over varied habitat from rainforest to semi desert.	Yes	Unlikely to Occur, Flyover only on very rare occasions.	May occur very occasionally for brief periods.	
Grey Wagtail Motacilla cinerea	S5	Mig, Ma	In Australia, near running water in disused quarries, sandy, rocky streams in escarpments and rainforest, sewerage ponds, ploughed fields and airfields.	No	Would Not Occur.	Never recorded in this area.	

Species	Conservation Status		Habitat Preferences	Habitat Present	Likelihood of Occurrence	Comments	
	BC Act/ DBCA Priority	EPBC Act					
Chuditch Dasyurus geoffroii	S3	VU	Forest, mallee shrublands, woodland and desert. The densest populations have been found in riparian jarrah forest.	Yes	Possibly Occurs.	Recorded during several surveys in nearby areas (see Appendix B).	
South-western Brush- tailed Phascogale Phascogale tapoatafa wambenger	S6	-	Dry sclerophyll forests and open woodlands that contain hollow-bearing trees but a sparse ground cover.	Yes	Possibly Occurs.	Recorded during several surveys in nearby areas (see Appendix B).	
Quenda Isoodon fusciventer	P4	-	Dense scrubby, often swampy, vegetation with dense cover.	Yes/Marginal	Possibly Occurs.	Recorded during several surveys in nearby areas (see Appendix B).	
Western Ringtail Possum Pseudocheirus occidentalis	S1	VU	Coastal peppermint, coastal peppermint-tuart, jarrah-marri associations, sheoak woodland, and eucalypt woodland and mallee.	Yes	Known to Occur.	Present, but likely to be in low densities as habitat in some areas is marginal in quality. Recorded during several surveys in nearby areas (see Appendix B).	
Quokka Setonix brachyurus	S3	VU	Currently restricted to densely vegetated coastal heaths, swamps, riverine habitats including teatree thickets on sandy soils along creek systems.	No	Would Not Occur. Locally extinct.	Locally extinct and habitat unsuitable.	
Woylie Bettongia penicillata ogilbyi	S1	EN	Open forest and woodland with a low, dense, understorey of tussock grasses or woody scrub. Formerly occurred in a wider range of habitats including spinifex hummock grasslands.	Yes/Marginal	Would Not Occur. Locally extinct.	Locally extinct.	
Western Brush Wallaby Notamacropus irma	P4	-	Open forest or woodland, particularly favouring open, seasonally wet flats with low grasses and open scrubby thickets.	Yes	Possibly Occurs.	Recorded during several surveys in nearby areas (see Appendix B).	
Western False Pipistrelle Falsistrellus mackenziei	P4	-	Wet sclerophyll forest dominated by karri and in high rainfall zones of the jarrah and marri forest.	Yes	Possibly Occurs.	Uncommon but recorded during some surveys in nearby areas (see Appendix B).	
Water Rat Hydromys chrysogaster	P4	-	Permanent water, fresh, brackish or marine.	No	Would Not Occur.	No suitable habitat.	

Note: see Appendix A for conservation codes

The following vertebrate fauna species of conservation significance were positively identified as utilising the subject site for some purpose during the survey period:

- Forest Red-tailed Black-Cockatoo Calyptorhynchus banksii naso S3 (WC Act), Vulnerable (EPBC Act)
 Foraging evidence attributed to this species were observed during the survey period (numerous chewed marri fruits). A high percentage of the remnant vegetation within the subject site represents foraging habitat. No evidence of actual breeding taking place was observed however all larger trees (>50cm DBH) can be considered potential breeding habitat, a number of which appear to contain large hollows. No roosting sites identified though likely to use some trees within the subject site for this
- Baudin's Black-Cockatoo Calyptorhynchus baudinii S2 (WC Act), Vulnerable (EPBC Act)
 Foraging evidence attributed to this species was observed during the survey period (chewed marri fruits). A high percentage of the remnant vegetation within the subject site represents foraging habitat. No evidence of actual breeding taking place was observed however all larger trees (≥50cm DBH) can be considered potential breeding habitat, a number of which appear to contain large hollows. No roosting sites identified though likely to use some trees within the subject site for this purpose.
- Western Ringtail Possum Pseudocheirus occidentalis S1 (WC Act), Critically Endangered (EPBC Act)
 Evidence of this species was found during the daytime survey in the form of some scats near an unoccupied drey. Overall habitat does however appear marginal due to the sparse nature of the midstorey vegetation and a lack of canopy connectivity. This suggests that this species is only present in low densities.

Based on the habitats present and current documented distributions it is considered possible that several additional vertebrate species of conservation significance may use the subject site for some purpose at times, though, as no evidence of them was found at the time of the field survey was found, the status of some in the area remains uncertain.

These species are:

purpose.

- Coastal Plains Skink Ctenotus ora P3 (DBCA Priority Species)
 Status of this species within the subject site is difficult to determine without a detailed survey, however, given the location of the subject site within its documented range, some recent nearby records and the presence of habitat that appears suitable it must be assumed to be present. Listed as a potential species based on available information.
- Carnaby's Black-Cockatoo Calyptorhynchus latirostris S2 (WC Act), Endangered (EPBC Act)
 - This species is known to frequent the general area and as suitable habitat is present it must be assumed to occur. A high percentage of the remnant vegetation within the

subject site represents foraging habitat. No evidence of actual breeding taking place was observed however all larger trees (≥50cm DBH) can be considered potential breeding habitat, a number of which appear to contain large hollows. No roosting sites identified though likely to use some trees within the subject site for this purpose. Listed as a potential species based on available information.

- Peregrine Falcon Falco peregrinus S7 (WC Act)
 This species potentially utilises some sections of the subject site as part of a much larger home range though only likely to occur infrequently. No evidence of nesting seen. Listed as a potential species based on available information.
- Masked Owl Tyto novaehollandae P3 (DBCA Priority Species)
 Status in the general area is difficult to determine. May utilise woodland areas within and near the subject site for roosting and therefore may forage in more open areas.
 Probably only present rarely. Listed as a potential species based on available information.
- South-western Brush-tailed Phascogale Phascogale tapoatafa wambenger S6 (WC Act)
 Recorded during previous surveys in the general area (Bancroft and Bamford 2008, Harewood 2014, G. Harewood pers. obs. 2013) and likely to be present in woodland areas containing tree hollows. Listed as a potential species based on available information.
- Chuditch Dasyurus geoffroii. S3 (WC Act), Vulnerable (EPBC Act))
 Without a detailed survey the status of this species within the subject site is difficult to determine however given there are some nearby records (Bancroft and Bamford 2008, G. Harewood pers. obs. 2013) it must be considered a potential species. Listed as a potential species based on available information.
- Quenda Isoodon fusciventer P4 (DBCA Priority Species)
 Habitat is general marginal for this species give the sparse nature of groundcover but it may occur in some areas where the densest vegetation occurs. Listed as a potential species based on available information.
- Western Brush Wallaby Macropus irma. P4 (DBCA Priority Species)
 This species is known to occur in the general area (G. Harewood pers. obs. 2016).
 As habitat appears suitable it must be assumed to occur, if only occasionally. Listed as a potential species based on available information.
- Western False Pipistrelle Falsistrellus mackenziei P4 (DBCA Priority Species)
 There is a lack of records of this species in the immediate vicinity but given habitat appears at least marginally suitable it must be assumed to occur, if only occasionally.
 Listed as a potential species based on available information.

As listed in Table 4, a number of other species of conservation significance, while possibly present in the wider area are not considered as potential species due to known localised

extinction (and no subsequent recruitment from adjoining areas), lack of suitable habitat and/or the presence of feral predators.

5.3.3 Invertebrate Fauna of Conservation Significance

Four conservation significant invertebrate species appeared in the DBCA database search (DBCA 2019), these being an unnamed cricket (*Pachysaga strobila*), the Swan Coastal Plain shield-backed trapdoor spider (*Idiosoma sigillatum*), the western pygmy trapdoor spider (*Bertmainius opimus*) and Carter's freshwater mussel (*Westralunio carteri*).

Both the Swan Coastal Plain shield-backed trapdoor spider and Carter's freshwater mussel have been assessed as not occurring due to a lack of suitable habitat. *Pachysaga strobila* is also considered as unlikely to occur though it is difficult to totally discount its possible presence.

The western pygmy trapdoor spider has been collected in a state forest near the subject site (DBCA 2019) so it must be regarded as a potential species though its actual status within the subject site is unknown.

6. CONCLUSION

The fauna assessment within the subject site was undertaken for the purposes of delineating and characterising the fauna habitats and faunal assemblages present. Targeted searches for black cockatoo habitat was also carried out.

With respect to native vertebrate fauna, 29 mammals (includes nine bat species), 92 bird, 36 reptile and three frog species have previously been recorded in the general area, some of which have the potential to occur in or utilise sections of the subject area at times, a conclusion largely based on the presence of apparently suitable habitat. Overall fauna habitat quality appears to be good and it can be expected that a high percentage of the predicted species would utilise the subject site.

The assessment identified the presence of "potential" black cockatoo breeding and foraging habitat within the subject site and the presence of the western ringtail possum. A number of additional federal and/or state listed threatened and DBCA priority fauna species may also occur though in most cases their use of the subject site wasn't detected during the survey period.

In summary three vertebrate fauna species of conservation significance were positively identified as utilising the subject site for some purpose during the survey period, these being:

- forest red-tailed black cockatoo Vulnerable (WA/Federal);
- Baudin's black cockatoo Endangered (WA/Federal); and

western ringtail possum – Critically Endangered (WA/Federal).

An additional nine species of conservation significance may also utilise the subject site, though, as no evidence of these species presence was identified during the field survey, the status of some in the area remains uncertain. These species are:

- coastal plains skink P3 (DBCA Priority Species);
- masked owl P3 (DBCA Priority Species);
- south-western brush-tailed phascogale S6 (WC Act);
- Carnaby's cockatoo Endangered (WA/Federal);
- peregrine falcon Schedule 7 (WA);
- quenda Priority 4 (WA);
- western brush wallaby Priority 4 (WA); and
- western false pipistrelle P4 (DBCA Priority Species).

One invertebrate species of conservation significance has also been assessed as possibly occurring based on available information. The western pygmy trapdoor spider (Priority 3) has been collected in a state forest near the subject site (DBCA 2019) so it must be regarded as a potential species though its actual status within the subject site is unknown.

The exact location of proposed development within the subject site is yet to be finalise. Ongoing planning will need to take into account the potential presence of habitat used by some species of conservation significance and fauna in general so that any direct and indirect impacts can be avoided or minimised. Management plans and protocols that aim to minimise impact on fauna and fauna habitat should be employed if considered warranted.

7. REFERENCES

Anstis, M. (2013). Tadpoles and Frogs of Australia. New Holland Publishers, Sydney.

Bamford, M.J and A.R. (2000). Proposed Gwindinup Mineral Sands Mine. Fauna Surveys; August and December 1999. Unpublished report for Cable Sands WA. January 2000.

Bancroft, W. and Bamford, M. (2008). Fauna values of Bemax's Happy Valley mineral sands deposit. Unpublished report for Bemax Resources Limited. January 2008.

Barrett, G., Silcocks, A., Barry, S., Cunningham, R. and Poulter, R. (2003). The New Atlas of Australian Birds. Royal Australasian Ornithologists Union, Victoria.

Biologic (2014). Wonnerup North Vertebrate Fauna Assessment. Unpublished report for Cristal Mining Australia Ltd.

Biota (2009). Tutunup Fauna Assemblage and Fauna Habitat Seasonal Survey. Unpublished report for Iluka Resources. March 2009.

Biota (2007a). Yoganup 215 Strand Fauna and Faunal Assemblage Survey. Unpublished report for Iluka Resources. February 2007.

Biota (2007b). Tutunup South Fauna Habitat and Fauna Assemblage Seasonal Survey. Unpublished report for Iluka Resources. December 2007.

Bush, B., Maryan, B., Browne-Cooper, R. & Robinson, D. (2007). Reptiles and Frogs in the Bush: Southwestern Australia. UWA Press, Nedlands.

Bush, B., Maryan, B., Browne-Cooper, R. & Robinson, D. (2010). Field Guide to Reptiles and Frogs of the Perth Region. UWA Press, Nedlands.

Churchill, S. (2008). Australian Bats. Second Edition, Allen & Unwin.

Cogger, H.G. (2014). Reptiles and Amphibians of Australia. 7th Edition. CSIRO Publishing.

Commonwealth of Australia (2012). *EPBC Act* Referral guidelines for three threatened black cockatoo species: Carnaby's cockatoo (endangered) *Calyptorhynchus latirostris*, Baudin's cockatoo (vulnerable) *Calyptorhynchus baudinii*, Forest red-tailed black cockatoo (vulnerable) *Calyptorhynchus banksii naso*.

Christidis, L. and Boles, W.E. (2008). Systematics and Taxonomy of Australian Birds. CSIRO Publishing, Melbourne.

Daniel March Botanical Consulting (DMBC) (2019). Desktop Study and Reconnaissance Flora and Vegetation Survey. – Lot 287 South West Hwy, Gwindinup WA. Unpublished report for Mario Michele Giacci.

Dell, J. (2000). A draft summary assessment of the fauna values of the Kemerton Bushland. Unpublished report for the Conservation Branch, Policy Division, Department of Environmental Protection.

Department of Biodiversity, Conservation and Attractions (DBCA) (2018). Threatened and Priority Fauna Rankings. 11 September 2018.

Department of Biodiversity Conservation and Attractions (DBCA) (2019). NatureMap Database search. "By Circle" 115° 44' 28" E, 33° 31' 06" S (plus 20 km buffer). http://naturemap.dec.wa.gov.au. Accessed 8 March 2019.

Department of the Environment and Energy (DotEE) (2018). *EPBC Act* Protected Matters Report: Point Search -33.51841 115.74103 (1km Buffer) Available from: http://www.environment.gov.au. Accessed 8 March 2019.

Environmental Protection Authority (EPA) (2009). Environmental Protection Bulletin No. 6, The Natural Values of the Whicher Scarp. August 2009.

EPA (2016). Technical Guidance – Terrestrial Vertebrate Fauna Surveys (replaces EPA (2004). Guidance for the Assessment of Environmental Factors No 56: Terrestrial Surveys for Environmental Impact Assessment, but not yet updated).

Government of Western Australia (2018). Wildlife Conservation Act 1950. Wildlife Conservation (Specially Protected Fauna) Notice 2017. Government Gazette, WA. 11 September 2018.

Harewood, G. (2009). Western Ringtail Possum Baseline Assessment. Tutunup. Unpublished report for Iluka Resources. August 2009.

Harewood, G. (2012). Phase 1 and 2 Seasonal Fauna Surveys (Level 2). Yoongarillup Mineral Sands Project. Unpublished report for Doral Mineral Sands Pty Ltd.

Harewood, G. (2013). Fauna Assessment of Yoganup Extended. Unpublished report for Iluka Resources Ltd.

Harewood, G. (2017). Fauna Assessment of Lot 3833 (Part) Hyder Road – Yoganup Extended. Unpublished report for Iluka Resources Ltd.

Harewood, G. (2018). Western Ringtail Possum 2018 Monitoring Survey, Gwindinup North Mineral Sands Mine, June/July 2018. Unpublished report for Cristal Mining Australia Limited. September 2016.

Hart, Simpson and Assoc. (1997). Wonnerup -Tutunup Road - Vertebrate Fauna. Unpublished report for Westralian Sands Ltd.

Harvey, M. S. (2002). Short-range endemism among the Australian fauna: some examples from non-marine environments. Invertebrate Systematics 16: 555-570.

Johnstone, R.E. and Storr, G.M. (1998). Handbook of Western Australian Birds: Volume 1 – Non-passerines (Emu to Dollarbird). Western Australian Museum, Perth Western Australia.

Johnstone, R.E. and Storr, G.M. (2004). Handbook of Western Australian Birds: Volume 2 – Passerines (Blue-winged Pitta to Goldfinch). Western Australian Museum, Perth Western Australia.

Menkhorst, P. and Knight, F. (2011). A Field Guide to the Mammals of Australia. Oxford University Press, Melbourne.

Morgan, D.L., Beatty, S.J., Klunzinger, M.W, Allen, M.G. and Burnham, Q.E (2011). Field Guide to the Freshwater Fishes, Crayfishes and Mussels of South Western Australia. Published by SERCUL.

Ninox (2006). A Vertebrate Fauna Assessment of the Yoganup Mineral Sands Project Area. Unpublished report for Iluka Resources. March 2006.

Peck, A., Barrett, G. & Williams, M. (2018). The 2018 Great Cocky Count: a community-based survey for Carnaby's Black-Cockatoo (Calyptorhynchus latirostris), Baudin's Black-Cockatoo (Calyptorhynchus baudinii) and Forest Red-tailed Black-Cockatoo (Calyptorhynchus banksii naso). BirdLife Australia, Floreat, Western Australia.

Storr, G.M., Smith, L.A. and Johnstone R.E. (1983). Lizards of Western Australia II: Dragons and Monitors. WA Museum, Perth.

Storr, G.M., Smith, L.A. and Johnstone R.E. (1990). Lizards of Western Australia III: Geckos and Pygopods. WA Museum, Perth.

Storr, G.M., Smith, L.A. and Johnstone R.E. (1999). Lizards of Western Australia I: Skinks. Revised Edition, WA Museum, Perth.

Storr, G.M., Smith, L.A. and Johnstone R.E. (2002). Snakes of Western Australia. Revised Edition, WA Museum, Perth.


Tyler M.J. & Doughty P. (2009). Field Guide to Frogs of Western Australia, Fourth Edition, WA Museum, Perth.


Van Dyck, S., Gynther, I. & Baker, A. Eds (2013). Field Companion to The Mammals of Australia. Queensland Museum.

Wilson, S. and Swan, G. (2017). A Complete Guide to Reptiles of Australia. Reed, New Holland, Sydney.


Woinarski, J., Burbidge, A. & Harrison, P. (2014). The Action Plan for Australian Mammals 2012. CSIRO Publishing.


FIGURES





Projection/Coordinate System: UTM/MGA Zone 50





APPENDIX A

CONSERVATION CATEGORIES

EPBC Act (1999) Threatened Fauna Categories

Threatened fauna may be listed under Section 178 of the *Environment Protection and Biodiversity Conservation Act 1999 (EPBC Act)* in any one of the following categories:

Category	Code	Description
Extinct	E	There is no reasonable doubt that the last member of the species has died.
*Extinct in the wild	EW	A species (a) is known only to survive in cultivation, in captivity or as a naturalised population well outside its past range; or (b) has not been recorded in its known and/or expected habitat, at appropriate seasons, anywhere in its past range, despite exhaustive surveys over a time frame appropriate to its life cycle and form.
*Critically Endangered	CE	A species is facing an extremely high risk of extinction in the wild in the immediate future.
*Endangered	EN	A species: (a) is not critically endangered; and (b) is facing a very high risk of extinction in the wild in the near future.
*Vulnerable	VU	A species (a) is not critically endangered or endangered; and (b) is facing a high risk of extinction in the wild in the medium-term future.
Conservation Dependent	CD	A species is the focus of a specific conservation program the cessation of which would result in the species becoming vulnerable, endangered or critically endangered
*Migratory	Migratory	(a) all migratory species that are: (i) native species; and (ii) from time to time included in the appendices to the Bonn Convention; and (b) all migratory species from time to time included in annexes established under JAMBA, CAMBA and ROKAMBA; and (c) all native species from time to time identified in a list established under, or an instrument made under, an international agreement approved by the Minister.
Marine	Ма	Species in the list established under s248 of the EPBC Act

Note: Only species in those categories marked with an asterix are matters of national environmental significance (NES) under the *EPBC Act*.

Wildlife Conservation (Specially Protected Fauna) Notice 2018 Categories

Published as Specially Protected under the *Wildlife Conservation Act 1950*, and listed under Schedules 1 to 7 of the Wildlife Conservation (Specially Protected Fauna) Notice.

The assessment of the conservation status of these species is based on their national extent and ranked according to their level of threat using IUCN Red List categories and criteria as detailed below.

Category	Code	Description
Schedule 1 (S1) Critically Endangered species	CR	Threatened species considered to be facing an extremely high risk of extinction in the wild in the immediate future.
Schedule 2 (S2) Endangered species	EN	Threatened species considered to be facing a very high risk of extinction in the wild in the near future.
Schedule 3 (S3) Vulnerable species	VU	Threatened species considered to be facing a high risk of extinction in the wild in the medium-term future.
Schedule 4 (S4) Presumed extinct species	EX	Species which have been adequately searched for and there is no reasonable doubt that the last member of the species has died.
Schedule 5 (S5) Migratory birds protected under an international agreement	MI	Fauna that periodically or occasionally visit Australia or an external Territory or the exclusive economic zone; or Birds that are subject to an agreement between the government of Australia and the governments of Japan (JAMBA), China (CAMBA) and The Republic of Korea (ROKAMBA), and the Bonn Convention, relating to the protection of migratory birds.
Schedule 6 (S6) Fauna that is of special conservation need as conservation dependent fauna	CD	Fauna of special conservation need being species dependent on ongoing conservation intervention to prevent it becoming eligible for listing as threatened.
Schedule 7 (S7) Other specially protected fauna.	OS	Fauna otherwise in need of special protection to ensure their conservation.

Western Australian DBCA Priority Fauna Categories

Possibly threatened species that do not meet survey criteria, or are otherwise data deficient, are added to the Priority Fauna under Priorities 1, 2 or 3. These three categories are ranked in order of priority for survey and evaluation of conservation status so that consideration can be given to their declaration as threatened flora or fauna.

Species that are adequately known, are rare but not threatened, or meet criteria for near threatened, or that have been recently removed from the threatened species or other specially protected fauna lists for other than taxonomic reasons, are placed in Priority 4. These species require regular monitoring.

Assessment of Priority codes is based on the Western Australian distribution of the species, unless the distribution in WA is part of a contiguous population extending into adjacent States, as defined by the known spread of locations.

Category	Code	Description
Priority 1 (P1) Poorly Known Species.	P1	Species that are known from one or a few locations (generally five or less) which are potentially at risk. All occurrences are either: very small; or on lands not managed for conservation, e.g. agricultural or pastoral lands, urban areas, road and rail reserves, gravel reserves and active mineral leases; or otherwise under threat of habitat destruction or degradation. Species may be included if they are comparatively well known from one or more locations but do not meet adequacy of survey requirements and appear to be under immediate threat from known threatening processes. Such species are in urgent need of further survey.
Priority 2 (P2) Poorly Known Species.	P2	Species that are known from one or a few locations (generally five or less), some of which are on lands managed primarily for nature conservation, e.g. national parks, conservation parks, nature reserves and other lands with secure tenure being managed for conservation. Species may be included if they are comparatively well known from one or more locations but do not meet adequacy of survey requirements and appear to be under threat from known threatening processes. Such species are in urgent need of further survey.
Priority 3 (P3) Poorly Known Species.	P3	Species that are known from several locations and the species does not appear to be under imminent threat, or from few but widespread locations with either large population size or significant remaining areas of apparently suitable habitat, much of it not under imminent threat. Species may be included if they are comparatively well known from several locations but do not meet adequacy of survey requirements and known threatening processes exist that could affect them. Such species are in need of further survey.
Priority 4 (P4) Rare, Near Threatened and other species in need of monitoring.	P4	 (a) Rare: Species that are considered to have been adequately surveyed, or for which sufficient knowledge is available, and that are considered not currently threatened or in need of special protection, but could be if present circumstances change. These species are usually represented on conservation lands. (b) Near Threatened: Species that are considered to have been adequately surveyed and that are close to qualifying for Vulnerable, but are not listed as Conservation Dependent.
		(c) Species that have been removed from the list of threatened species during the past five years for reasons other than taxonomy.

^{*}Species includes all taxa (plural of taxon - a classificatory group of any taxonomic rank, e.g. a family, genus, species or any infraspecific category i.e. subspecies or variety, or a distinct population).

IUCN Red List Threatened Species Categories

The *IUCN Red List of Threatened Species* $^{\text{TM}}$ is a checklist of taxa that have undergone an extinction risk assessment using the *IUCN Red List Categories and Criteria*.

Categories are summarized below.

Category	Code	Description
Extinct	EX	Taxa for which there is no reasonable doubt that the last individual has died.
Extinct in the Wild	EW	Taxa which is known only to survive in cultivation, in captivity or and as a naturalised population well outside its past range and it has not been recorded in known or expected habitat despite exhaustive survey over a time frame appropriate to its life cycle and form.
Critically Endangered	CR	Taxa facing an extremely high risk of extinction in the wild.
Endangered	EN	Taxa facing a very high risk of extinction in the wild.
Vulnerable	VU	Taxa facing a high risk of extinction in the wild.
Near Threatened	NT	Taxa which has been evaluated but does not qualify for CR, EN or VU now but is close to qualifying or likely to qualify in the near future.
Least Concern	LC	Taxa which has been evaluated but does not qualify for CR, EN, VU, or NT but is likely to qualify for NT in the near future.
Data Deficient	DD	Taxa for which there is inadequate information to make a direct or indirect assessment of its risk of extinction based on its distribution and/or population status.
Not Evaluated	NE	Taxa which has not been evaluated.

A full list of categories and their meanings are available at:

http://www.iucnredlist.org/technical-documents/categories-and-criteria/2001-categories-criteria

APPENDIX B

FAUNA OBSERVED OR POTENTIALLY PRESENT

Fauna Observed or Potentially Present

Lot 287 SW Highway.

A = Harewood, G (2019). Fauna Assessment Lot 287 South Western Highway. Unpublished report for M.Giacci. March 2019.

B = Harewood, G (2016). Fauna Assessment Lot 3833 (Part) Hyder Road - Yoganup Extended. Unpublished report for Iluka Resources Limited. December 2016

C = Harewood, G (2013). Terrestrial Fauna Assessment (Level 1) Yoganup Extended Mineral Sands Project. Unpublished report for Iluka Resources Limited. March 2013

D = Harewood, G (2014). Phase 1 and 2 Seasonal Fauna Surveys (Level 2). Yoongarillup Mineral Sands Project. Unpublished report for Doral Mineral Sands Pty Ltd.

E = Bancroft, W. and Bamford, M. (2008). Fauna values of Bemax's Happy Valley mineral sands deposit. Unpublished report for Bemax Resources Limited. January 2008 (inludes Gwindinup).

Approx. centroid = 115.74103°E, 33.51841°S Compiled by Greg Harewood - March 2019

Recorded (Captured/Sighted/Heard/Signs) = X

F = Biota (2009). Tutunup Fauna Assemblage and Fauna Habitat Seasonal Survey. Unpublished report for Iluka Resources. March 2009.

G = Biota (2007a). Yoganup 215 Strand Fauna and Faunal Assemblage Survey. Unpublished report for Iluka Resources. February 2007.

H = Biota (2007b). Tutunup South Fauna Habitat and Fauna Assemblage Seasonal Survey. Unpublished report for Iluka Resources. December 2007.

I = Ninox (2006). A Vertebrate Fauna Assessment of the Yoganup Mineral Sands Project Area. Unpublished report for Iluka Resources. March 2006.

J = Hart, Simpson and Assoc. (1997). Wonnerup -Tutunup Road - Vertebrate Fauna. Unpublished report for Westralian Sands Ltd.

K = DBCA (2019). NatureMap Database search. "By Circle" 115° 44' 28" E,33° 31' 06" S (plus 20km buffer). 8 March 2019.

Class Family Species	Common Name	Conservation Status	Α	В	С	D	Е	F	G	Н	I	J	K
Amphibia													
Myobatrachidae Ground or Burrowing Frogs													
Heleioporus eyrei	Moaning Frog	LC		X		Х	Х	Х	Х	X		Χ	X
Limnodynastes dorsalis	Western Banjo Frog	LC				Х	X			X		Х	Х
Pseudophryne guentheri	Crawling Toadlet	LC						Х				Χ	
Reptilia													
Diplodactylidae													
Diplodactylus polyophthalmus	Speckled Stone Gecko					Х	X	Х				X	

lass Family Species	Common Name	Conservation Status	A	В	С	D	E	F	G	Н	ı	J	K
Gekkonidae Geckoes													
Christinus marmoratus	Marbled Gecko					Х	X	Х	Х	Х		Х	Х
Pygopodidae Legless Lizards													
Aprasia pulchella	Pretty Worm Lizard					Х	X		Х	Х		Х	Х
Aprasia repens	Sandplain Worm Lizard						X			Х		Х	
Delma australis	Marble-faced Delma					Х							
Lialis burtonis	Burton's Legless Lizard						Х	Х	Х			Х	Х
Pygopus lepidopodus	Common Scaly Foot												
Agamidae Dragon Lizards													
Pogona minor	Western Bearded Dragon					Х	X	Х	Χ	Х		Х	Х
Varanidae Monitor's or Goanna's													
Varanus gouldii	Sand Monitor						X						Х
Varanus rosenbergi	Heath Monitor					Х	Х	Х		Х	Х	Х	

ASS Family Species	Common Name	Conservation Status	A	В	С	D	E	F	G	Н	I	J	K
Scincidae Skinks													
Acritoscincus trilineatum	Southwestern Cool Skink					Х	X	Х	Х	Х		Х	
Cryptoblepharus buchananii	Fence Skink		Х	X		Х	X	Х	Х	Х			Χ
Ctenotus impar	Odd-striped Ctenotus					Х	X	Х	Х	Х		Х	Χ
Ctenotus ora	Coastal Plains Skink	P3				Х	X	Х	Х	Х		Х	Χ
Egernia kingii	King's Skink					Х		Х	Х			Х	Χ
Egernia napoleonis	Salmon-bellied Skink					Х	X			Х	Х		Χ
Hemiergis gracilipes	Southwestern Mulch Skink								Х				Χ
Hemiergis peronii peronii	Four-toed Earless Skink									Х			
Hemiergis peronii tridactyla	Three-toed Earless Skink					Х	X	Х	Х			Х	
Hemiergis quadrilineata	Two-toed Mulch Skink												Χ
Lerista distinguenda	South West Four-toed Lerista					Х	X	Х	Х	Х		Х	Χ
Lerista elegans	West Coast Four-toed Lerista					X		Х	Х	Х			X
Menetia greyii	Dwarf Skink					X	X	Х	Х	Х		Х	X
Morethia lineoocellata	West Coast Pale-flecked More	ethia				X	X	Х	Х	Х		Х	Χ
Morethia obscura	Shrubland Pale-flecked Moreth	nia				Х	Х	Х	Х	Х			Х

ASS Family Species	Common Name	Conservation Status	A	В	С	D	E	F	G	Н	ı	J	K
Tiliqua rugosa	Bobtail			Х		Х	Х	Х	Х	X		Х	Х
Typhlopidae Blind Snakes													
Ramphotyphlops australis	Southern Blind Snake					Х	Х	Х	Χ	X		Х	
Ramphotyphlops pinguis	Fat Blind Snake					Х	X			Х			
Boidae Pythons, Boas													
Morelia spilota imbricata	Southern Carpet Python						X						
Elapidae Elapid Snakes													
Echiopsis curta	Bardick												
Elapognathus coronatus	Crowned Snake					Х							Х
Notechis scutatus	Tiger Snake						Х		Х			Х	Х
Parasuta gouldii	Gould's Hooded Snake												
Parasuta nigriceps	Black-backed Snake					Х			Х			Х	Х
Pseudonaja affinis	Dugite					Х	X					Х	Х
Simoselaps bertholdi	Jan's Banded Snake												Х

lass Family	Common	Conservation Status											
Species	Name	Status	Α	В	С	D	Е	F	G	Н	ı	J	K
ves													
Casuariidae Emus, Cassowarries													
Dromaius novaehollandiae	Emu	LC	Х	Χ	Χ	Χ	X	Χ	Χ	Χ	Χ		Х
Phasianidae Quails, Pheasants													
Coturnix pectoralis	Stubble Quail	LC			Χ	Χ	Χ						Χ
Coturnix ypsilophora	Brown Quail	LC							Х				
Anatidae Geese, Swans, Ducks													
Anas gracilis	Grey Teal	LC			Χ		Χ		Χ		Χ	Χ	Χ
Anas superciliosa	Pacific Black Duck	LC			Х		X	Х	X		Х	Х	Х
Chenonetta jubata	Australian Wood Duck	LC			Х	Х	X	Х	X		X	X	Х
Tadorna tadornoides	Australian Shelduck	LC		Х	Х	Х	Х	Х				Х	Х

lass Family Species	Common Name	Conservation Status	Α	В	С	D	E	F	G	Н	I	J	K
Accipitridae Kites, Goshawks, Eagles, Harriers													
Accipiter cirrocephalus	Collared Sparrowhawk	LC				Χ	Χ						X
Accipiter fasciatus	Brown Goshawk	LC			Х		Х			Х	X		Χ
Aquila audax	Wedge-tailed Eagle	LC				Х	X	Х	Х			Х	X
Aquila morphnoides	Little Eagle	LC			Х		X						
Circus approximans	Swamp Harrier	LC			Х				Х				Х
Elanus caeruleus	Black-shouldered Kite	LC			Х								
Haliastur sphenurus	Whistling Kite	LC			Х			Х					Х
Hamirostra isura	Square-tailed Kite	LC					Х						
Falconidae Falcons													
Falco berigora	Brown Falcon	LC		Х			X						X
Falco cenchroides	Australian Kestrel	LC			Х	Х	X		Х				Χ
Falco longipennis	Australian Hobby	LC							Х				X
Falco peregrinus	Peregrine Falcon	S7 LC					Х						X
Turnicidae Button-quails													
Turnix varia	Painted Button-quail	LC					Χ						

ASS Family Species	Common Name	Conservation Status	А	В	С	D	E	F	G	Н	ı	J	K
Columbidae Pigeons, Doves													
Ocyphaps lophotes	Crested Pigeon	LC		X	Х	Х	Х	Χ	Χ		X	Χ	X
Phaps chalcoptera	Common Bronzewing	LC	Х		Х	Х	Х	Х	Х	Х	X	Χ	X
Phaps elegans	Brush Bronzewing	LC											
Psittacidae Parrots													
Cacatua sanguinea gymnopis	Little Corella	Introduced			Х								Χ
Cacatua tenuirostris	Eatern Long-billed Corella	Introduced											
Calyptorhynchus banksii naso	Forest Red-tailed Black-Cockato	o S3 VU	Х	X	Х	Х	X	Х	Х	Х	X	Х	X
Calyptorhynchus baudinii	Baudin's Black Cockatoo	S2 EN EN A3cde	Х	Х	Х	Х	Х	Х	Х		Х	Х	Х
Calyptorhynchus latirostris	Carnaby's Black Cockatoo	S2 EN EN A2bcde		Х	Х	Х	Х	Х	Х	Х		Х	Х
Glossopsitta porphyrocephala	Purple-crowned Lorikeet	LC				Х	Х			Х			
Neophema elegans	Elegant Parrot	LC			Х	Х	Х	Х	Х	Х			Х
Platycercus icterotis icterotis	Western Rosella (western ssp)	LC					Х	Х	Х				Х
Platycercus spurius	Red-capped Parrot	LC	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х
Platycercus zonarius	Australian Ringneck	LC	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х
Polytelis anthopeplus	Regent Parrot	LC							Х			Х	Х

lass Family	Common Name	Conservation Status											
Species	Name	Status	Α	В	С	D	Е	F	G	Н	I	J	K
Cuculidae Parasitic Cuckoos													
Cacomantis flabelliformis	Fan-tailed Cuckoo	LC					Х	Х				Χ	X
Chrysococcyx basalis	Horsfield's Bronze Cuckoo	LC					Х	Х	Х				
Chrysococcyx lucidus	Shining Bronze Cuckoo	LC				Х	Х	Х	Х			Х	
Cuculus pallidus	Pallid Cuckoo	LC		Х				Х				Х	
Strigidae Hawk Owls													
Ninox novaeseelandiae	Boobook Owl	LC			Χ	Χ	Х	Χ					
Tytonidae Barn Owls													
Tyto alba	Barn Owl	LC			Х								
Tyto n. novaehollandiae	Masked Owl (SW pop)	P3											Х
Podargidae Frogmouths													
Podargus strigoides	Tawny Frogmouth	LC			Χ		Х	Х					X
Aegothelidae Owlet-nightjars													
Aegotheles cristatus	Australian Owlet-nightjar	LC					Χ						Χ

lass Family Species	Common Name	Conservation Status	А	В	С	D	E	F	G	Н	I	J	K
Halcyonidae Tree Kingfishers													
Dacelo novaeguineae	Laughing Kookaburra	Introduced		Χ	Χ	Х	X	Х	Χ	Χ	Χ	Χ	X
Todiramphus sanctus	Sacred Kingfisher	LC					Х	Х				Х	Х
Meropidae Bee-eaters													
Merops ornatus	Rainbow Bee-eater	JA LC	Х	Χ	Χ	Х	Х	Χ	Χ	Χ		Χ	Х
Climacteridae Treecreepers													
Climacteris rufa	Rufous Treecreeper	LC						Х					
Maluridae Fairy Wrens, GrassWrens													
Malurus elegans	Red-winged Fairy-wren	LC				Х	Х	Χ	Χ	Χ			X
Malurus splendens	Splendid Fairy-wren	LC		Х	Х	Х	Х	Х	Х	Х	X	Х	Х
Stipiturus malachurus	Southern Emu-wren	LC						Х	Х				Х

ASS Family Species	Common Name	Conservation Status	А	В	С	D	Е	F	G	Н	ı	J	K
Acanthizidae Thornbills, Geryones, Fieldwrens & White	efaces												
Acanthiza apicalis	Broad-tailed Thornbill	LC	Х	Χ	Χ	Χ	Χ	Х	Χ	Χ	Χ	Χ	Х
Acanthiza chrysorrhoa	Yellow-rumped Thornbill	LC	Х	X	Х	Х	Х	Х	X		X	Χ	Х
Acanthiza inornata	Western Thornbill	LC					Х		X	X	X		Х
Gerygone fusca	Western Gerygone	LC	Х	X	Х	Х	Х	Х	X	X	X	Χ	Х
Sericornis frontalis	White-browed Scrubwren	LC				Х	Х	Х	X	X	X		Х
Smicrornis brevirostris	Weebill	LC	Х	X		Х	Х	Х		X	X		Х
Pardalotidae Pardalotes													
Pardalotus punctatus	Spotted Pardalote	LC					Х	Х	Χ				X
Pardalotus striatus	Striated Pardalote	LC		Х	Х	Х	Х	Х	Х	Χ	Χ	Х	X

lass Family Species	Common Name	Conservation Status	Α	В	С	D	Е	F	G	Н	I	J	K
Meliphagidae Honeyeaters, Chats													
Acanthorhynchus superciliosus	Western Spinebill	LC				Х	X	Х	Х	Х	Х	Х	Х
Anthochaera carunculata	Red Wattlebird	LC	Х	X	Х	Х	X		Х	Х	Х	Х	X
Anthochaera lunulata	Western Little Wattlebird	LC		Х									X
Epthianura albifrons	White-fronted Chat	LC							Х				X
Lichenostomus virescens	Singing Honeyeater	LC						Х		Х			
Lichmera indistincta	Brown Honeyeater	LC		Х	Х	Х	X	Х	Х	Х	Х	Х	Х
Melithreptus chloropsis	Gilbert's Honeyeater	LC					X	Х					
Phylidonyris melanops	Tawny-crowned Honeyeater	LC						Х	Х				
Phylidonyris nigra	White-cheeked Honeyeater	LC							Х				
Phylidonyris novaehollandiae	New Holland Honeyeater	LC			Х	Х	X	Х	Х	Х	Х	X	X
Petroicidae Australian Robins													
Eopsaltria georgiana	White-breasted Robin	LC					X	Х	Х				X
Eopsaltria griseogularis	Western Yellow Robin	LC	Х			Х	X	Х	Х				
Petroica multicolor	Scarlet Robin	LC	Х	Χ		Х	Х	Χ	Х	Х			

ass Family Species	Common Name	Conservation Status	Α	В	С	D	E	F	G	Н	I	J	K
Neosittidae Sitellas													
Daphoenositta chrysoptera	Varied Sittella	LC	Х			X	X	Χ	Χ				Х
Pachycephalidae Crested Shrike-tit, Crested Bellbird, Shrike	Thrushes, Whistlers												
Colluricincla harmonica	Grey Shrike-thrush	LC	Х	Χ		Χ	X	Χ	Χ	Χ	Χ		Х
Pachycephala occidentalis	Western Whistler	LC	Χ	Х	Х	Х	Х	Х	Х	Х	Х		
Pachycephala rufiventris	Rufous Whistler	LC		Х	Х	Х	Х	Х	Х			Х	Х
Dicruridae Monarchs, Magpie Lark, Flycatchers, Fanta	ils, Drongo												
Grallina cyanoleuca	Magpie-lark	LC			Χ	Х	Х		Х			Х	Х
Rhipidura fuliginosa	Grey Fantail	LC	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	
Rhipidura leucophrys	Willie Wagtail	LC		Х	Х	X	Х	Х	Х	X		Х	X
Campephagidae Cuckoo-shrikes, Trillers													
Coracina novaehollandiae	Black-faced Cuckoo-shrike	LC		X	Χ	Χ	Х	Χ	Χ	X	Χ	Χ	Χ
Lalage tricolor	White-winged Triller	LC			Х		Х						

lass Family Species	Common Name	Conservation Status	Α	В	С	D	E	F	G	Н	I	J	K
Artamidae Woodswallows, Butcherbirds, Currawongs													
Artamus cinereus	Black-faced Woodswallow	LC		X	Х		X		Χ			Х	Х
Artamus cyanopterus	Dusky Woodswallow	LC			Х		Х	Х	Χ	X			Χ
Cracticidae Currawongs, Magpies & Butcherbirds													
Cracticus tibicen	Australian Magpie	LC	Х	Χ	Χ	Χ	Χ	Χ	Χ	Χ	Χ	Χ	Х
Cracticus torquatus	Grey Butcherbird	LC		Χ	Х	X	X	Х	X			Χ	Χ
Strepera versicolor	Grey Currawong	LC	Х			X	Х	Х					Х
Corvidae Ravens, Crows													
Corvus coronoides	Australian Raven	LC	Х	Χ	Х	Х	Х	Х	Χ	X	Χ	Χ	Χ
Motacillidae Old World Pipits, Wagtails													
Anthus australis	Australian Pipit	LC			Х	Χ	X	Χ	Χ				
Estrilidae Grass Finches & Mannikins													
Stagonopleura oculata	Red-eared Firetail	LC						Х					Х
Dicaeidae Flowerpeckers													
Dicaeum hirundinaceum	Mistletoebird	LC											X

Class Family Species	Common Name	Conservation Status	Α	В	С	D	Е	F	G	Н	ı	J	K
Hirundinidae Swallows, Martins													
Hirundo ariel	Fairy Martin	LC			Χ								
Hirundo neoxena	Welcome Swallow	LC			Х	Х	X		Х	Х		Х	Х
Hirundo nigricans	Tree Martin	LC			Х	Х	X	Х	Х		Х	Х	
Sylviidae Old World Warblers													
Cincloramphus cruralis	Brown Songlark	LC				Х							
Cincloramphus mathewsi	Rufous Songlark	LC					X					Х	
Zosteropidae White-eyes													
Zosterops lateralis	Grey-breasted White-eye	LC		Χ	Х		X	Х	Χ	Х	X	Χ	Х
/lammalia													
Tachyglossidae Echidnas													
Tachyglossus aculeatus	Echidna	LC		X			Χ	Х		Χ	Χ		

lass Family Species	Common Name	Conservation Status	А	В	С	D	E	F	G	Н	I	J	K
Dasyuridae Carnivorous Marsupials													
Antechinus flavipes	Yellow-footed Antechinus, Mard	0				Х	Х		Χ	Χ			X
Phascogale tapoatafa wambenger	SW Brush-tailed Phascogale	S6				Х	X						X
Sminthopsis gilberti	Gilbert's Dunnart	LC					X		X	Х			X
Sminthopsis griseoventer	Grey-bellied Dunnart	LC							Х	Х			
Peramelidae Bandicoots													
Isoodon fusciventer	Quenda	P4 LC		Χ	Χ	Х	Х	Χ	Χ	Χ		Χ	Х
Phalangeridae Brushtail Possums, Cuscuses													
Trichosurus vulpecula	Common Brushtail Possum	LC	Х	Х	Χ	Х	Х	Х	Χ	X	Х	Х	
Burramyidae Pygmy Possums													
Cercartetus concinnus	Western Pygmy-possum	LC				Х	Х	Χ		X			X
Tarsipedidae Honey Possum													
Tarsipes rostratus	Honey Possum, Noolbenger	LC					X			X		X	
Pseudocheiridae Ringtail Posssums													
Pseudocheirus occidentalis	Western Ringtail Possum	S1 CR CR A2bce+3bce+4	bc X	Χ	X		Χ	Х					Χ

ASS Family Species	Common Name	Conservation Status	А	В	С	D	E	F	G	Н	ı	J	K
Macropodidae Kangaroos, Wallabies													
Macropus fuliginosus	Western Grey Kangaroo	LC	Х	Χ	Χ	Х	Х	Х	Χ	Х	Χ	Х	X
Notamacropus irma	Western Brush Wallaby	P4 LC				Х	Х	Х		Х			
Molossidae Freetail Bats													
Austronomus australis	White-striped Freetail-bat	LC			Χ	Х	Х		Χ	Х			
Ozimops kitcheneri	South-western Freetail-bat	LC				Х							
Vespertilionidae Ordinary Bats													
Chalinolobus gouldii	Gould's Wattled Bat	LC				Х		Х					X
Chalinolobus morio	Chocolate Wattled Bat	LC				Х		Х		Х			Х
Falsistrellus mackenziei	Western False Pipistrelle	P4 NT							Х				Χ
Nyctophilus geoffroyi	Lesser Long-eared Bat	LC				X		Х					Х
Nyctophilus gouldi	Gould's Long-eared Bat	LC								Х			
Nyctophilus major	Western Long-eared Bat	LC											
Vespadelus regulus	Southern Forest Bat	LC				Х	Х	Х	Х	Х			Х

lass Family Species	Common Name	Conservation Status	А	В	С	D	Е	F	G	Н	I	J	K
Muridae Rats, Mice													
Mus musculus	House Mouse	Introduced				X	Х	Χ	Х			Х	Х
Rattus fuscipes	Western Bush Rat	LC				Х		Х	X				
Rattus rattus	Black Rat	Introduced				Х	Х	Х					X
Canidae Dogs, Foxes													
Vulpes vulpes	Red Fox	Introduced			Χ	Х	Х	Х			Χ	Χ	
Felidae Cats													
Felis catus	Cat	Introduced			Х			Х					
Suidae Pigs													
Sus scrofa	Pig	Introduced		Χ		Χ	Χ						
Leporidae Rabbits, Hares													
Oryctolagus cuniculus	Rabbit	Introduced		Х	Х	Χ	Χ	X	Х	Х	Χ	X	

APPENDIX C DBCA & EPBC DATABASE SEARCH RESULTS



NatureMap - Lot 287

Created By Greg Harewood on 08/03/2019

Kingdom Animalia

Current Names Only Yes

Core Datasets Only Yes

Method 'By Circle'

Centre 115° 44' 28" E,33° 31' 06" S

Buffer 20km

Group By Species Group

Species Group	Species	Records
Amphibian Bird Fish Invertebrate Mammal Reptile	10 156 7 160 30 31	134 9038 13 495 2971 143
TOTAL	394	12794

Name ID Species Name

Naturalised Conservation Code ¹Endemic To Query Area

Amphibian			
1.	25398 Crinia georgiana (Quacking Frog)		
2.	25399 Crinia glauerti (Clicking Frog)		
3.	25400 Crinia insignifera (Squelching Froglet)		
4.	25401 Crinia pseudinsignifera (Bleating Froglet)		
5.	25404 Geocrinia leai (Ticking Frog)		
6.	25410 Heleioporus eyrei (Moaning Frog)		
7.	25411 Heleioporus inornatus (Whooping Frog)		
8.	25415 Limnodynastes dorsalis (Western Banjo Frog)		
9.	25378 Litoria adelaidensis (Slender Tree Frog)		
10.	25388 Litoria moorei (Motorbike Frog)		
Bird			
11.	24260 Acanthiza apicalis (Broad-tailed Thornbill, Inland Thornbill)		
12.	24261 Acanthiza chrysorrhoa (Yellow-rumped Thornbill)		
13.	24262 Acanthiza inornata (Western Thornbill)		
14.	24560 Acanthorhynchus superciliosus (Western Spinebill)		
15.	25535 Accipiter cirrocephalus (Collared Sparrowhawk)		
16.	25536 Accipiter fasciatus (Brown Goshawk)		
17.	25537 Accipiter novaehollandiae (Grey Goshawk)		
18.	25755 Acrocephalus australis (Australian Reed Warbler)		
19.	41323 Actitis hypoleucos (Common Sandpiper)	IA	
20.	25544 Aegotheles cristatus (Australian Owlet-nightjar)		
21.	24301 Aegotheles cristatus subsp. cristatus (Australian Owlet-nightjar)		
22.	24310 Anas castanea (Chestnut Teal)		
23.	24312 Anas gracilis (Grey Teal)		
24.	24313 Anas platyrhynchos (Mallard)		
25.	Anas platyrhynchos subsp. domesticus		
26.	24315 Anas rhynchotis (Australasian Shoveler)		
27.	24316 Anas superciliosa (Pacific Black Duck)		
28.	47414 Anhinga novaehollandiae (Australasian Darter)		
29.	24561 Anthochaera carunculata (Red Wattlebird)		
30.	24562 Anthochaera lunulata (Western Little Wattlebird)		
31.	24285 Aquila audax (Wedge-tailed Eagle)		
32.	41324 Ardea modesta (great egret, white egret)		
33.	24340 Ardea novaehollandiae (White-faced Heron)		
34.	24341 Ardea pacifica (White-necked Heron)		
35.	24610 Ardeotis australis (Australian Bustard)		
36.	25566 Artamus cinereus (Black-faced Woodswallow)		
37.	24353 Artamus cyanopterus (Dusky Woodswallow)		
38.	24318 Aythya australis (Hardhead)		
39.	Barnardius zonarius	ATT.	

NatureMap is a collaborative project of the Department of Parks and Wildlife and the Western Australian Museum.







	Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Query Area
40.	24319	Biziura lobata (Musk Duck)			
41.	24345	Botaurus poiciloptilus (Australasian Bittern)		g	
42.	25714	Cacatua pastinator (Western Long-billed Corella)			
43.	25716	Cacatua sanguinea (Little Corella)			
44.		Cacomantis flabelliformis (Fan-tailed Cuckoo)			
45.		Cacomantis pallidus (Pallid Cuckoo)			
46.		Calyptorhynchus banksii (Red-tailed Black-Cockatoo)			
47. 48.		Calyptorhynchus banksii subsp. naso (Forest Red-tailed Black Cockatoo) Calyptorhynchus baudinii (Baudin's Cockatoo, White-tailed Long-billed Black		g	
40.	24133	Cockatoo)		g	
49.	24734	Calyptorhynchus latirostris (Carnaby's Cockatoo, White-tailed Short-billed Black Cockatoo)		g	
50.	48400	Calyptorhynchus sp. (white-tailed black cockatoo)		g	
51.	24377	Charadrius ruficapillus (Red-capped Plover)			
52.	24321	Chenonetta jubata (Australian Wood Duck, Wood Duck)			
53.		Chroicocephalus novaehollandiae			
54.		Circus aeruginosus			Υ
55.		Circus approximans (Swamp Harrier)			
56.		Cladorhynchus leucocephalus (Banded Stilt)			
57.		Colluricincla harmonica (Grey Shrike-thrush)	V		
58. 59.		Columba livia (Domestic Pigeon) Coracina novaehollandiae (Black-faced Cuckoo-shrike)	Υ		
60.		Corvus coronoides (Australian Raven)			
61.		Corvus coronoides subsp. perplexus (Australian Raven)			
62.		Coturnix pectoralis (Stubble Quail)			
63.		Cracticus nigrogularis (Pied Butcherbird)			
64.	25595	Cracticus tibicen (Australian Magpie)			
65.		Cracticus torquartus			
66.	25596	Cracticus torquatus (Grey Butcherbird)			
67.	24322	Cygnus atratus (Black Swan)			
68.	30901	Dacelo novaeguineae (Laughing Kookaburra)	Υ		
69.		Daphoenositta chrysoptera (Varied Sittella)			
70.		Dicaeum hirundinaceum (Mistletoebird)			
71. 72.	24470	Dromaius novaehollandiae (Emu)			
73.		Egretta garzetta Egretta novaehollandiae			
74.		Elanus axillaris			
75.	47937	Elseyornis melanops (Black-fronted Dotterel)			
76.		Eolophus roseicapillus			
77.	24652	Eopsaltria georgiana (White-breasted Robin)			
78.	24567	Epthianura albifrons (White-fronted Chat)			
79.	25621	Falco berigora (Brown Falcon)			
80.		Falco cenchroides (Australian Kestrel, Nankeen Kestrel)			
81.		Falco longipennis (Australian Hobby)			
82.		Falco peregrinus (Peregrine Falcon)		S	
83.		Falcunculus frontatus subsp. leucogaster (Western Shrike-tit, Crested Shrike-tit)			
84. 85.		Fulica atra (Eurasian Coot)			
86.		Fulica atra subsp. australis (Eurasian Coot) Gallinula tenebrosa (Dusky Moorhen)			
87.		Gallinula tenebrosa (Dusky Moorhen) Gallinula tenebrosa subsp. tenebrosa (Dusky Moorhen)			
88.		Gallirallus philippensis (Buff-banded Rail)			
89.		Gerygone fusca (Western Gerygone)			
90.		Grallina cyanoleuca (Magpie-lark)			
91.	24293	Haliaeetus leucogaster (White-bellied Sea-Eagle)			
92.	24295	Haliastur sphenurus (Whistling Kite)			
93.	47965	Hieraaetus morphnoides (Little Eagle)			
94.	25734	Himantopus himantopus (Black-winged Stilt)			
95.		Hirundo neoxena (Welcome Swallow)			
96.		Larus novaehollandiae subsp. novaehollandiae (Silver Gull)			
97.	25661	Lichmera indistincta (Brown Honeyeater)			
98. 99.	24600	Lophoictinia isura Macronectes giganteus (Southern Giant Petrel)		14	
				IA	
100. 101.		Malacorhynchus membranaceus (Pink-eared Duck) Malurus elegans (Red-winged Fairy-wren)			
101.		Malurus splendens (Splendid Fairy-wren)			
103.		Megalurus gramineus (Little Grassbird)			
104.		Melanodryas cucullata (Hooded Robin)			
105.		Merops ornatus (Rainbow Bee-eater)			
106.		Microcarbo melanoleucos			
107.	25610	Myiagra inquieta (Restless Flycatcher)			







	Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Query Area
108.	24738	Neophema elegans (Elegant Parrot)			
109.	25564	Nycticorax caledonicus (Rufous Night Heron)			
110.	24407	Ocyphaps lophotes (Crested Pigeon)			
111.	24328	Oxyura australis (Blue-billed Duck)		P4	
112.	25680	Pachycephala rufiventris (Rufous Whistler)			
113.	24692	Pachyptila belcheri (Slender-billed Prion)			
114.	24693	Pachyptila desolata (Antarctic Prion)			
115.	48591	Pandion cristatus (Osprey, Eastern Osprey)		IA	
116.		Pardalotus punctatus (Spotted Pardalote)			
117.		Pardalotus punctatus subsp. xanthopyge (Yellow-rumped Pardalote)			
118.		Pardalotus striatus (Striated Pardalote)			
119.		Pelecanus conspicillatus (Australian Pelican)			
120.		Petrochelidon nigricans (Tree Martin)			
121.		Petroica boodang (Scarlet Robin)			
122.		Petroica goodenovii (Red-capped Robin)			
123.		Phalacrocorax carbo (Great Cormorant)			
124.		Phalacrocorax melanoleucos (Little Pied Cormorant)			
125.		Phalacrocorax sulcirostris (Little Black Cormorant)			
126.		Phalacrocorax varius (Pied Cormorant)			
127.		Phaps chalcoptera (Common Bronzewing)			
128.		Phylidonyris niger (White-cheeked Honeyeater)			
129. 130.		Phylidonyris novaehollandiae (New Holland Honeyeater) Platalea flavipes (Yellow-billed Spoonbill)			
131.					
132.		Platycercus icterotis (Western Rosella) Platycercus icterotis subsp. icterotis (Western Rosella)			
133.		Platycercus spurius (Red-capped Parrot)			
134.		Platycercus zonarius subsp. semitorquatus (Twenty-eight Parrot)			
135.		Plegadis falcinellus (Glossy Ibis)		IA	
136.		Podargus strigoides (Tawny Frogmouth)		IA	
137.		Podargus strigoides subsp. brachypterus (Tawny Frogmouth)			
138.		Podiceps cristatus (Great Crested Grebe)			
139.		Poliocephalus poliocephalus (Hoary-headed Grebe)			
140.		Polytelis anthopeplus (Regent Parrot)			
141.		Porphyrio porphyrio (Purple Swamphen)			
142.		Porphyrio porphyrio subsp. bellus (Purple Swamphen)			
143.		Pterodroma lessonii (White-headed Petrel)			
144.		Purpureicephalus spurius			
145.	24776	Recurvirostra novaehollandiae (Red-necked Avocet)			
146.	48096	Rhipidura albiscapa (Grey Fantail)			
147.	25614	Rhipidura leucophrys (Willie Wagtail)			
148.	25534	Sericornis frontalis (White-browed Scrubwren)			
149.	30948	Smicrornis brevirostris (Weebill)			
150.	24645	Stagonopleura oculata (Red-eared Firetail)			
151.	24329	Stictonetta naevosa (Freckled Duck)			
152.	25655	Stipiturus malachurus (Southern Emu-wren)			
153.	25597	Strepera versicolor (Grey Currawong)			
154.	25590	Streptopelia senegalensis (Laughing Turtle-Dove)	Υ		
155.	25705	Tachybaptus novaehollandiae (Australasian Grebe, Black-throated Grebe)			
156.	24682	Tachybaptus novaehollandiae subsp. novaehollandiae (Australasian Grebe, Black-			
		throated Grebe)			
157.		Tadorna tadornoides (Australian Shelduck, Mountain Duck)			
158.		Thalassarche carteri (Indian Yellow-nosed Albatross)		g	
159.		Thalasseus bergii (Crested Tern)		IA	
160.		Threskiornis spinicollis (Straw-necked Ibis)			
161. 162		Tringa pehularia (Common Greenshank)		14	
162.		Tringa nebularia (Common Greenshank, greenshank)		IA	
163.		Turnix varius (Painted Button-quail)		D2	
164. 165.		Tyto novaehollandiae subsp. novaehollandiae (Masked Owl (southwest)) Vanellus tricolor (Banded Lapwing)		P3	
166.		Zosterops lateralis (Grey-breasted White-eye, Silvereye)			
	20700	2000 op months of the open months of the open open open open open open open ope			
□ish					
167.		Bostockia porosa			
168.		Carassius auratus			
169.		Echeneis naucrates			
170.		Edelia vittata			
171.		Galaxias occidentalis (Western Minnow)			
172.	34030	Geotria australis (Pouched Lamprey)		P3	
173.		Nannoperca vittata			
Invertebrate					

Invertebrate







	N	ame ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Query Area
	174. 175.		Acariformes sp.			
	176.		Aganippe rhaphiduca Akamptogonus novarae			
	177.		Allothereua maculata			
	178.		Aname mainae			
	179.		Aname tepperi			
	180.		Ancylidae sp.			
	181.		Anisops sp.			
	182. 183.		Antichiropus nanus Antiporus occidentalis			
	184.		Antiporus sp.			
	185.		Arachnura higginsi			
	186.		Araneus cyphoxis			
	187.		Araneus senicaudatus			
	188.		Argiope protensa			
	189. 190.		Arkys alticephala			
	190.		Arkys walckenaeri Arrenuridae sp.			
	192.		Artoria flavimana			
	193.		Artoriopsis expolita			
	194.		Athericidae sp.			
	195.		Aturidae sp.			
	196.		Austracantha minax			
	197. 198		Backobourkia brounii Radumna insignis			
	198. 199.		Badumna insignis Baetidae sp.			
	200.		Baiami tegenarioides			
2	201.		Baiami volucripes			
:	202.		Berosus discolor			
	203.		Berosus munitipennis			
	204.	47873	Bertmainius opimus (western pygmy trapdoor spider)		P3	
	205. 206.		Botryocladius freemani Coopides en			
	200.		Caenidae sp. Carabidae sp.			
	208.		Ceinidae sp.			
:	209.		Celaenia excavata			
2	210.		Ceratopogonidae sp.			
	211.		Cercophonius sulcatus			
	212.		Cherax preissii			
	213. 214.		Cherax quinquecarinatus Chironominae sp.			
	215.		Chironomus aff. alternans (V24) (CB)			
:	216.		Chironomus tepperi			
:	217.		Clynotis severus			
	218.		Coenagrionidae sp.			
	219.		Copepoda sp.			
	220. 221.		Corixidae sp. Cormocephalus hartmeyeri			
	222.		Corynoneura sp. (V49) (SAP)			
	223.		Cricotopus 'parbicinctus'			
:	224.		Cryptoerithus quobba			
	225.		Culex (Culex) australicus			
	226.		Culicidae sp.			
	227. 228.		Cyclosa trilobata Dicrotendipes sp. A (V47) (SAP)			
	226. 229.		Dicroterialpes sp. A (V41) (SAP) Dingosa serrata			
	230.		Dugesiidae sp.			
2	231.		Dytiscidae sp.			
	232.		Ecnomidae sp.			
	233.		Erigone prominens			
	234.		Eriophora biapicata Comphidae sp			
	235. 236.		Gomphidae sp. Gripopterygidae sp.			
	237.		Gyrinidae sp.			
	238.		Harrisius sp.			
:	239.		Harrisius sp. B (SFM)			
	240.		Helochares tenuistriatus			
	241.		Helpis minitabunda			
	242. 243.		Hemicorduliidae sp. Hydrobiosidae sp.			
•	_ 70.		, a. oz. oz. ado op.			
					107 x 100 x 100 m	







14. Hydrocyclotide sp. 15. Hydrocyclotide sp.		Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Query Area
246. Hydrochic pp. 247. Hydrochic pp. 248. 48955 Misconne eighburn (Swen Created Pierr al Need-besched Ireshoor groter) 249. Inspechalis called a service of the common service						
267. Hristine au. 268. Insulation Schoolson application Entotic Palva sholed Acaded repotour spoter) 269. Insulation Schoolson application Schoolson Spotery 260. Insulation Schoolson Spoten Schoolson Spotery 260. Insulation Schoolson Spoten Schoolson Spotery 261. Insulation Schoolson Spoten Schoolson Spotery 262. Lemphora Contraction 263. Kellenback Instruction 264. Lemphora Contraction 265. Lemphora Spoten Spot						
261. 46905 inflorence algorithmic (Swan Coestal Piler divisió-backet trapascor galden) pro impación la inflorence intraveción castronce intraveción castronce intraveción castronce intraveción castronce intraveción la inflorence intraveción castronce intraveción intraveción intraveción castronce intraveción in						
2020. Inappele Institutement 2021. Inappele Institutement 2022. Inappele Institutement 2023. Inappele Institutement 2024. Inappele Institutement 2025. Lampora principate 2026. Lampora principate 2026. Lampora principate 2027. Lampora principate 2027. Lampora principate 2028. Lampora principate 2029. Lampora principate 2020. Lampora principate 2021. Lampora principate 2022. Lampora principate 2023. Lampora principate 2024. Lampora principate 2024. Lampora principate 2025. Lampora principate 2026. Manuscripate 2027. Manuscripate 2028. Manuscripate 2029. Manuscripate 2029. Manuscripate 2020. Manuscripate 2021. Manuscripate 2021. Manuscripate 2022. Octobrona principate 2023. Manuscripate 2024. Manuscripate 2024. Manuscripate 2025. Octobrona principate 2026. Octobrona principate 2026. Octobrona principate 2027. Manuscripate 2028. Octobrona principate 2029. Octobrona principate 2029. Octobrona principate 2030. Manuscripate 2031. Manuscripate 2032. Octobrona principate 2033. Octobrona principate 2034. Paramora principate 2034. Paramora principate 2035. Octobrona principate 2036. Octobrona principate 2037. Paramora principate 2038. Octobrona principate 2039. Paramora principate 2039. Paramora principate 2030. Paramora principate 2031. Paramora principate 2032. Octobrona principate 2033. Octobrona principate 2034. Paramora principate 2034. Paramora principate 2035. Paramora principate 2036. Paramora principate 2037. Paramora principate 2038. Paramora principate 2039. Paramora principate 2039. Paramora principate 2030. Paramora principate 2031. Paramora principate 2032. Paramora principate 2033. Octobrona principate 2034. Paramo		48935			P3	
29.1 Isopolehis casa 120.2 Isopolehis casa 120.3 Killerious interfectue 120.4 Lampora de morpias 120.5 Lampora cylivariati 120.5 Lampora cylivariati 120.5 Lampora cylivariati 120.6 Lampora cylivariati 120.7 Micropal cylivariati 120.7 Mi	249.		Insulodrilus bifidus			
	250.		Isopeda leishmanni			
2013. Kelefinius intervendus 256. Campons cylindrale 256. Campons cylindrale 257. Campons cylindrale 258. Campons cylindrale 258. Campons cylindrale 259. Caphophebolog genus Sia AVT 250. Caphophebolog genus Sia AVI 250. Caphophebolog			Isopedella cana			
Lampons broupes						
255. Lampoons optivalish 256. Lampoons providerals 257. Lamboons providerals 258. Lamboons providerals 259. Lamboons providerals 259. Laptoprovider part 260. Laptoprovide parts 261. Laptoprovider parts 262. Laptoproviderals 262. Laptoproviderals 263. Laptoproviderals 264. Laptoproviderals 265. Lamboons parts 266. Lamboons parts 266. Lamboons parts 267. Lampoons providerals 268. Marentur providerals 269. Marentur providerals 269. Marentur providerals 269. Marentur providerals 269. Marentur providerals 267. Marentur providerals 268. Marentur providerals 268. Marentur providerals 268. Marentur providerals 269. Marentur providerals 269. Marentur providerals 260. Lampoons providerals 260. Marentur providerals 260. Marentur providerals 261. Marentur providerals 262. Marentur providerals 263. Marentur providerals 264. Marentur providerals 265. Marentur providerals 266. Optivalerals 266. Optivalerals 267. Marentur providerals 268. Optivalerals 268. Optivalerals 268. Optivalerals 269. Optivalerals 269. Optivalerals 260. Optivalerals 260. Optivalerals 261. Optivalerals 262. Providerals providerals 263. Optivalerals 264. Optivalerals 265. Providerals 266. Optivalerals 267. Providerals 268. Providerals 269. Providerals 269. Providerals 269. Providerals 269. Providerals 269. Providerals 260. Providerals 260. Providerals 260. Providerals 261. Providerals 262. Providerals 263. Providerals 264. Providerals 265. Providerals 266. Providerals 267. Providerals 268. Providerals 268. Providerals 269. Providerals 269. Providerals 260. Providerals 260. Providerals 260. Providerals 261. Providerals 262. Providerals 263. Providerals 264. Providerals 265. Providerals 266. Providerals 267. Providerals 268. Providerals 268. Providerals 269. Providerals 269. Providerals 260. Providerals 260. Providerals 260. Providerals 260. Providerals 260. Providerals 261. Providerals 261. Providerals						
267. Lamorelea Innovaleus (27. Marculas Innovaleus			• •			
258. Leptocelote hasself						
260. Lespoobeels austratives 261. Lespoobeels genus 2 ap. AV1 272. Lespoobeels genus 274. Lebuildines ap. 276. Limboolesseus innimatis 286. Limboolesseus innimatis 287. Limboolesseus deprinding 288. Mariana parvonia 288. Mariana parvonia 270. Microweels ap. 271. Microweels ap. 272. Missionen Brogil 273. Missionen Brogil 274. Missionen Brogil 275. Missionen Brogil 276. Missionen Brogil 277. Missionen Brogil 278. Missionen Brogil 279. Missionen Brogil 271. Missionen Brogil 272. Missionen Brogil 273. Missionen Brogil 274. Missionen Brogil 275. Missionen Brogil 276. Missionen Brogil 277. Missionen Brogil 278. Missionen Brogi			Latrodectus hasseltii			
281. Leaptonheider genus S. g. AV1 702. Leaptonheider genus S. g. AV1 703. Leaptoneider genus S. g. g. AV1 704. Linnoufersus inornatus 706. Linnoufersus inornatus 707. Linnoufersus inornatus 708. Marians paradurus 708. Marians paradurus 708. Marians paradurus 709. Marians paradurus 709. Marians paradurus 707. Marians granufuse 707. Marians granufuse 707. Massurian pagi 708. Massurian pagi 709. Noosian sa VIVI 709. Noosian sa VIVI 709. Noosian sa VIVI 709. Massurian pagi 709. Orioinan paradurus 709. Paramerintina pagi 709. Parame	259.		Leptoceridae sp.			
0R2. LeptphPerbitte sp 2R4. Loebilddes gp 2R5. Lomochysis vesitias (V41) 2R6. Lomochysis vesitias (V41) 2R7. Lomochysis vesitias (V41) 2R8. Marquite parentis 2R8. Marquite parentis 2R9. Miscopostiginorides sp. 271. Miscopostiginorides sp. 272. Missolens hoggi 273. Missolens hoggi 274. Missolens hoggi 275. Missolens hoggi 276. Missolens insolunts 277. Nipplie edulis 278. Nicolamus maines 279. Nicolamus maines 280. Novincia sp. AVTG 281. Nicolamus maines 282. Ovinciano parmellae 283. Opistaccia sp. 284. Orimochilians avoitellis 285. Opistaccia sp. 286. Opistaccia sp. 287. Otimochilians sp. 288. Opistaccia sp. 289. Palascon	260.		Leptoperla australica			
2003. Learbildides pn 265. Limbodessus inconstatus 266. Limbodessus inconstatus 267. Limosaverus zeitundicus 268. Milinitus parvina 269. Microscelar subusta 270. Microveciar subusta 271. Missulens ogranulosa 272. Missulens orcationa 273. Missulens orcationa 274. Missulens orcationa 275. Missulens orcational 276. Missulens orcational 277. Missulens orcational 278. Missulens orcational 279. Missulens orcational 270. Missulens orcational 271. Missulens orcational 272. Missulens orcational 273. Missulens orcational 274. Missulens orcational 275. Missulens orcational 276. Missulens orcational 277. Newtransports exists 278. Novical superins orcational 289. Oristonational superin	261.		Leptophlebiid genus S sp. AV1			
094. Lebelunidae sp. 286. Limochyee veedluuk (vl4) 207. Limochyee veedluuk (vl4) 268. Maraus pavoriis 268. Meraus pavoriis 269. Mespandignordies ep. 270. Micrometra robusta 271. Micrometra robusta 272. Missulere granviosa 273. Missulere sociationis 274. Missulere occationis 275. Missulere sociationis 276. Missulere sociationis 277. Neptinis edulis 278. Neuvernature associationis 279. Nicodamus rabinis 270. Nicodamus rabinis 281. Nucus as pavoriis 282. Ocirisona parmicine 283. Oligochiella sp. 284. Oristona parmicine 285. Opisthoperia sp. 286. Opisthoperia sp. 287. Dissectional moriestic sp. 288. 33889 Pachagas abrobal (Vasse Parthysaga (Bussetton-Domptrook), cricket) P1 28						
268. L Immobilessus information 269. L Immorphies extiliate (V41) 269. Maratus parenta 269. Maratus parenta 270. Microrrecta robusta 271. Malorine garatusa 272. Masulens garatusa 273. Masulens occatoria 274. Missulena occatoria 275. Mittorcupa insularia 276. Mistorcupa insularia 277. Negnamoperta exigua 278. Neumanoperta exigua 279. Neumanoperta exigua 279. Neumanoperta exigua 279. Neuranoperta exigua 279. Neuranoperta exigua 280. Nousia sp. AV16 281. Nuncidia sapera 282. Oristona parmeller 283. Olipichere sp. 284. Oristonata (indient) 285. Oristonata (indient) 286. Oristocation (indient) 287. Palaryrus spononi 288. 33889 Palarysage stocala (Vasa Petrysage (Bussellon-Donny						
208. Limnopryse wastaus (V41)			•			
Administration Admi						
268						
209. Maganodagrionidae sp. 271. Microvella sp. 272. Missulora granulosa 273. Missulora granulosa 274. Missulora occatoria 275. Missulora arantulnus 276. Missulora arantulnus 277. Montrouga insularia 278. Newmanoperte expus 279. Nicodaman saninae 280. Nucusia sp. AV16 281. Ocinisona parmeliae 283. Oligocheela sp. 284. Ormatolus moreleil 285. Opisthopora sp. 286. Ostrocode (unident) 287. Ostrocode (unident) 288. 3389 Perbysaga strobial (Vasse Pechysaga (Bussetton-Donnydrook), cricket) P1 289. Paleamonidae sp. 291. Paraskeffiniella vaniegatus 292. Parasinelidae sp. 293. Pertamelidae sp. 294. Paramentie levidensis 295. Pertamelidae sp. 296. Pertamentiel levidensis 296.						
271. Missulena granulosa 273. Missulena Roggi 274. Missulena Cocatoria 375. Milludori trantullurus 276. Mittoroga insularia 277. Nephire deulus 278. Newmanoperla exigua 379. Nicodamus mairiae 280. Nousa pa AVI 6 281. Nimodella asperra 282. Ocrisiona parmellae 283. Oligocheste ap 284. Ormatolulus morelelli 285. Opisthopora ap Orthocidalinee ap Orthocidalinee ap 287. Ostracoda (urident.) 288. 33989 Pachysaga strobia (Vasse Pachysaga (Busselton-Dornybrook), cricket) P1 289. Pachoragas strobia (Vasse Pachysaga (Busselton-Dornybrook), cricket) P1 289. Pachoragai strobia (Vasse Pachysaga (Busselton-Dornybrook), cricket) P1 289. Pachysaga strobia (Vasse Pachysaga (Busselton-Dornybrook), cricket) P1 289. Pachysaga strobia (Vasse Pachysaga (Busselton-Dornybrook), cricket) P1 289. Pachysaga strobia (Vasse P						
272. Missudena granulosa 273. Missudena cocatoria 274. Missudena cocatoria 275. Millulodo tararchilurus 276. Millulodo tararchilurus 277. Nephile edulus 278. Newamanoperla exigua 279. Nicodamus mainae 280. Avusus sa, AV16 281. Nunciella aspera 282. Ociristina parmellae 283. Oligocheela sa, 284. Olimina parmellae 285. Opistingora sp. 286. Orticoladinnae sp. 287. Ostracodi (mident.) 288. 33899 Pechyaaga stroliai (Visase Pachyaaga (Bussetton-Dornybrook), cricket) P1 289. Paleamonidee sp. 290. Parasiterilea variagetus 291. Parasiterilea variagetus 292. Parasiterilea variagetus 293. Paramellidae sp. 294. Parasiterilea sariagetus 295. Parasiterilea sariagetus 296. Parasiterilea sariagetus	270.		Micronecta robusta			
273. Missulena hoggi 274. Missulena occatoria 275. Mittoruga insularia 276. Mittoruga insularia 277. Neymanoperia esigua 278. Nicodamis mainae 280. Nousia sp. AV16 281. Nunciella aspera 282. Ocrisona parmeline 283. Oligochaeta sp. 284. Ormatolius moreletii 285. Opisthopora sp. 287. Ostracoda (unident.) 288. 33898 Pachysaga sirbolia (Vasse Pachysaga (Busselton-Donnybrook), cricket) P1 289. Pachyminides sp. 290. Paracymus spenceri 291. Paramerinale sviriepatus 292. Paramimonylvas pullulus (V42) 293. Paramerina levidensis 295. Parastecidies ap, 296. Pentaleurini genus V20 297. Perthilides ap, 298. Pholous phalengioides 299. Pholous phalengioides 290. Paracytidides ap, 290. <th>271.</th> <th></th> <th>Microvelia sp.</th> <th></th> <th></th> <th></th>	271.		Microvelia sp.			
274. Missulena occatoria 275. Mituniodin farantulinus 276. Mituniodin farantulinus 277. Nephilia edulis 278. Newmanoprila esigua 279. Nicodamus mainae 280. Nousia sp. AV16 281. Nunciella aspera 282. Ocrisiona parmellee 283. Oligocheeta sp. 284. Ommatoulus morielati 285. Orithocladilinae sp. 286. Orithocladilinae sp. 287. Ostracoda (unident) 288. 33389 Pachysaga strobila (Vasse Pachysaga (Busselton-Dornybrook), cricket) 289. Palaemonidae sp. 290. Paracymus spenceri 291. Parakiefferiella variegatus 292. Paralimosphyes publikus (V42) 293. Paramerina levidensis 294. Paramerina levidensis 295. Parasididae sp. 296. Perangumina esp. 297. Perthiidae sp. 298. Paramerina levidensis 298. Parasididae sp. 299. Paralimosphyes publikus (V42) 291. Paramerina levidensis 295. Parasididae sp. 296. Pentaneurin genus V20 297. Perthiidae sp. 298. Philopolamidae sp. 299. Pholius phelangioldes 299. Pholius phelangioldes 299. Pholius phelangioldes 290. Phenodridae sp. 291. Planorididae sp. 292. Planorididae sp. 293. Planorididae sp. 294. Planorididae sp. 295. Philopolamidae sp. 296. Philopolamidae sp. 297. Perthiide sp. 298. Philopolamidae sp. 299. Pholius phelangioldes 299. Pholius shelangioldes 290. Phenodrididae sp. 291. Planorididae sp. 292. Planorididae sp. 293. Planorididae sp. 294. Planorididae sp. 295. Planorididae sp. 296. Planorididae sp. 297. Perthiide sp. 298. Planorididae sp. 299. Pholius subtraits 200. Physolium vatconi 201. Scuttgerella indecisae 201. Stuttgerella indecisae 201. Stuttgerella indecisae 201. Stuttgerella indecisae						
275. Millulodon tarantulinus 276. Milzonga insularis 277. Nephila edulis 278. Newmanoparia exigua 279. Nicodamus mahae 280. Nousia sp. AV16 281. Nunciatia sapera 282. Ocrisiona parmeliae 283. Olipochaeta sp. 284. Ormatolius morietii 285. Opisthopora sp. 286. Orthocalaimae sp. 287. Ostracoda (unidant) 288. 33899 Perbysaga strobile (Vasse Pachysaga (Busselton-Donnybrook), cricket) 289. Palaemonidae sp. 280. Paranymus spenceri 281. Parakiferinalia variegatus 282. Paralimonphres pullulus (V42) 283. Parameltidies sp. 284. Paramentina levidensis 285. Paramentina levidensis 286. Paramentina levidensis 287. Paramentina levidensis 288. Perbiadea sp. 289. Perhamentina levidensis 289. Perhamentina levidensis 280. Perhamentina levidensis 281. Parakiferialia variegatus 282. Paralimonphres pullulus (V42) 283. Paramentina levidensis 284. Paramentina levidensis 285. Perhibidae sp. 286. Perhibidae sp. 287. Perhibidae sp. 288. Philopotamidae sp. 289. Philopotamidae sp. 289. Philopotamidae sp. 280. Pilapotamidae sp. 380. Philapotamidae sp. 380. Pilapotamidae sp. 380. Pilapotaetae sp. 381. Sicilitae sp.						
276. Mitzonga insularis 277. Mephila edulis 278. Newmanoperia exigua 279. Nicodamus mainae 280. Nousia şa. AV16 281. Municialia aspera 282. Ocisiona parmeliae 282. Ocisiona parmeliae 283. Olipocheela sp. 284. Ommatoiulus moreleit 285. Opistropora sp. 286. Opistropora sp. 287. Ostracoda (unident.) 288. 33989 Pachysaga strobial (Vasse Pachysaga (Busselton-Donnybrook), cricket) 289. Palaemonidae sp. 290. Paranymus spencerl 291. Parakiefferielia variegatus 292. Paralimophyes pullulus (V42) 293. Paramelitidae sp. 294. Paramerina leveldensis 295. Parastedidea sp. 296. Pentaneumi genus V2O 297. Perthidae sp. 298. Philopotamidae sp. 299. Pholous phalarojioidee 300. Pirreaticidae sp. 301. Pirreaticidae sp. 303. Pirreaticidae sp. 304. Pianymetes decempuntatus var polygrammus 305. Pilarymetes decempuntatus var polygrammus 306. Polypedilum nr. corvexum (SAP) 307. Robinsus suturalis 311. Sciridae sp.						
277. Nephila edulis 278. Newmanoperia exigua 279. Nicodamus mainae 280. Nousia sp. AV16 281. Vunciella espera 282. Ocrisiona parmeliae 283. Oligochaeta sp. 284. Ommatoluis moreletii 285. Opisthopora sp. 286. Orthocladiinne sp. 287. Ostracoda (unident.) 288. 33898 Pachysaga strobial (Vasse Pachysaga (Busselton-Donnybrook), cricket) P1 289. Parlomoridee sp. 280. Paraximus spenceri 281. Paraximus spenceri 282. Paralimnophyes pullulus (V42) 283. Paraminitidee sp. 284. Paraminitidee sp. 285. Parastacidea sp. 286. Perthidea sp. 287. Perthidea sp. 288. Philopotamidea sp. 289. Philopotamidea sp. 280. Pharatocidea sp. 301. Phreaticidea sp. 302. Plastynetice spe. <th></th> <th></th> <th></th> <th></th> <th></th> <th></th>						
278. Newmanoperte erigue 279. Nicodamus mainae 280. Nousia sp. AV16 281. Nunciella sapera 282. Ocrisiona parmellae 283. Oligocheeta sp. 284. Ommatoluku moreletii 285. Opisthopora sp. 286. Orthocladiinae sp. 287. Ostracoda (unident.) 288. 33989 Pachysaga strobila (Vasse Pachysaga (Busseiton-Donnybrook), cricket) 289. Palaemonidae sp. 290. Paracymus spenceri 291. Parakieffarielia variegatus 292. Paraminophyse pullulus (V42) 293. Paramenina levidensis 294. Paramenina levidensis 295. Parastacidae sp. 296. Pentaneunis genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Philopotamidae sp. 299. Philopotamidae sp. 290. Pinoprididee sp. 291. Philopotamidae sp. 292. Paramenina levidensis 293. Philopotamidae sp. 294. Philopotamidae sp. 295. Philopotamidae sp. 296. Philopotamidae sp. 297. Perthiidae sp. 298. Philopotamidae sp. 299. Philopotamidae sp. 299. Philopotamidae sp. 299. Philopotamidae sp. 300. Pirestoicidae sp. 301. Pireodriidae sp. 302. Planorbidee sp. 303. Pilatoris gelorup 304. Polypedilum rut convexum (SAP) 307. Polypedilum watsoni 308. Pyraldae sp. 309. Rhantus suturalis 310. Riethia v 5 311. Scribdee sp. 313. Simulisiae sp.						
279. Nicodamus mainae 280. Nousia sp. AV16 281. Nuncella aspera 282. Ocrisiona parmellae 283. Oligochaeta sp. 284. Ommatoiulus moreletii 285. Opisthiopora sp. 286. Orthocaldiinae sp. 287. Ostracoda (unident.) 288. 33989 Pachysaga strobia (Vasse Pachysaga (Busselton-Donnybrook), cricket) 289. Paletemoriidae sp. 290. Paracymus spenceri 291. Parakeferielia variegatus 292. Paralimnophyes pullulus (V42) 293. Parameliidae sp. 294. Paramenia levideniss 295. Parastacidae sp. 296. Pentaneurini genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Pholous phalangiidaes 300. Pirestoicidae sp. 299. Pholous phalangiidaes 301. Phreodriidae sp. 302. Planorbidae sp. 303. Pilatorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Pilstynectes sp. 308. Polypedillum ric convexum (SAP) 309. Rantus suturalis 310. Riethia v5 311. Scittidee sp.						
281. Nunciella aspera 282. Ocrisiona parmeliae 283. Oligocheata sp. 284. Ommatoiulus moreletii 285. Opisthopora sp. 286. Orhocaldinae sp. 287. Ostracoda (unident.) 288. 33989 Pachysaga strobila (Vasse Pachysaga (Busselton-Donnybrook), cricket) 289. Palaemonidae sp. 290. Paracymus spenceri 291. Parakiefferiella varlegatus 292. Paralimnophyes pullulus (V42) 293. Paramelitidae sp. 294. Paramenina levidensis 295. Parastacidae sp. 296. Pentaneumin genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Philopotamidae sp. 299. Philopotamidae sp. 300. Phreatoicidae sp. 301. Phreodrilidae sp. 302. Planorbidea sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygramnus 305. Platynectes decempuntatus var polygramnus 306. Polypedilum nr. convexum (SAP) 307. Polypedilum nr. convexum (SAP) 309. Rhantus suturalis 310. Riethia v3 311. Sciridae sp. 312. Scutigerelia indecisa 313. Simuliidae sp.	279.					
282. Ocrisiona parmeliae 283. Oligochaeta sp. 284. Ommatoiulus moreletii 285. Opisthopora sp. 286. Orthociadiinae sp. 287. Ostriacoda (unident) 288. 33989 Pachysaga strobiia (Vasse Pachysaga (Busselton-Donnybrook), cricket) 289. Palaemonidae sp. 290. Paracymus spenceri 291. Parakiefferiella variegatus 292. Paralimophyes pullulus (V42) 293. Paramelifidee sp. 294. Paramelifidee sp. 295. Parastacidae sp. 296. Pentaneurini genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Phocus phaliangioides 300. Phreatoicidae sp. 301. Phreadriidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygramnus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum vatsoni 308. Pyraidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Sciridae sp.	280.		Nousia sp. AV16			
283. Oligochaeta sp. 284. Ormatolulus moreletii 285. Opishopora sp. 286. Orthocladiinae sp. 287. Ostracode (unident.) 288. 33898 Pachysaga strobila (Vasse Pachysaga (Busselton-Donnybrook), cricket) P1 289. Palaemonidae sp. 290. Paracymus spenceri 291. Parademididae sp. 292. Paralimnophyes pullulus (V42) 293. Paramellidae sp. 294. Paramenina levidensis 295. Parastacidae sp. 296. Pertaneuini genus V20 297. Perthiidae sp. 299. Pholous phalangioides 300. Phrestoloidae sp. 301. Phreodriidae sp. 302. Platorishidae sp. 303. Platoryeides decempuntatus var polygrammus 304. Platynectes sp. 305. Polypedilum nr. convexum (SAP) 307. Polypedilum nr. convexum (SAP) 309. Rhantus suturalis 310. Riethia v5			Nunciella aspera			
284. Ommatolulus moreletii 285. Opishopora sp. 286. Orthocladiinae sp. 287. Ostracoda (unident.) 288. 33989 Pachysaga strobila (Vasse Pachysaga (Busselton-Donnybrook), cricket) 289. Palaemonidae sp. 290. Paracymus spenceri 291. Parakieffieilla variegatus 292. Paralimophyes pullulus (V42) 293. Paramerina levidensis 295. Parastacidae sp. 296. Pentaneurini genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 298. Philopotamidae sp. 299. Pholcus phalangioides 300. Phreatoicidae sp. 301. Phreodrilidae sp. 302. Planoribdae sp. 303. Platorish gelorup 304. Platyrectes decempuntatus var polygrammus 305. Platyrectes decempuntatus var polygrammus 306. Polypedilum nr. convexum (SAP) 307. Polypedilum mrt. convexum (SAP) 308. Pyralidae sp. 319. Simulidae sp. 310. Riethia v5 311. Scittidae sp. 312. Scittigerella indecisa 313. Simulidae sp.						
285. Opisthopora sp. 286. Orthocladinae sp. 287. Ostracoda (unident.) 288. 33989 Pachysaga strobila (Vasse Pachysaga (Busselton-Donnybrook), cricket) 289. Palaemonidae sp. 290. Paracymus spenceri 291. Parakiefferiella variegatus 292. Paralimnophyse pullulus (V42) 293. Paramellidae sp. 294. Paramellidae sp. 295. Parastacidae sp. 296. Pentaneurini genus V20 297. Perthiidee sp. 298. Philopotamidae sp. 299. Philopotamidae sp. 299. Philopotamidae sp. 300. Phreadriidae sp. 301. Phreodriidae sp. 302. Planorbidae sp. 303. Platynectes decempuntatus var polygrammus 304. Platynectes decempuntatus var polygrammus 305. Piatynectes sp. 307. Polypedilum matsoni 308. Pyraldae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simulidae sp.						
286. Orthoc/adilinae sp. 287. Ostracoda (unident.) 288. 33989 Pachysaga strobila (Vasse Pachysaga (Busselton-Donnybrook), cricket) 289. Palaemonidae sp. 290. Paracymus spenceri 291. Parakiefferiella variegatus 292. Paralimnophyes pullulus (V42) 293. Paramelitidae sp. 294. Paramerina levidensis 295. Parastacidae sp. 296. Pentaneurini genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Pholeus phalangioides 300. Phreatoricidae sp. 301. Phreadrilidae sp. 302. Planoribidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum vatsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v 5 311. Sciritidae sp. 311. Sciritidae sp. 312. Scutigerella indecisa 313. Simulidae sp.						
287. Ostracoda (unident.) 288. 33989 Pachysaga strobila (Vasse Pachysaga (Busselton-Donnybrook), cricket) P1 289. Palaemonidae sp. 290. Paracymus spenceri 291. Parakinferiella variegatus 292. Paralimnophyes pullulus (V42) 293. Paramelitidee sp. 294. Paramerina levidensis 295. Parastacidee sp. 296. Pentaneurini genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Photcus phalangioides 300. Phreatoicidae sp. 301. Phreatoicidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes decempuntatus var polygrammus 306. Polypedilum nr. convexum (SAP) 307. Polypedilum vatsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v S 311. Scritigae la in						
288. 33989 Pachysaga strobila (Vasse Pachysaga (Busselton-Donnybrook), cricket) 289. Palaemonidae sp. 290. Paracymus spenceri 291. Parakiefferiella variegatus 292. Paralimnophyes pullulus (V42) 293. Parameirina levidensis 295. Parastacidae sp. 296. Pentaneunni genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Pholcus phalangioides 300. Phreatoicidae sp. 301. Phreodrilidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum matsoni 307. Polypedilum matsoni 308. Pyraildae sp. 309. Rhantus suturalis 310. Riethia v5 311. Sciridae sp. 312. Scutigerella indecisa 313. Simullidae sp.						
290. Paracymus spenceri 291. Parakifefreileli variegatus 292. Paralimnophyes pullulus (V42) 293. Paramelitidae sp. 294. Paramelitidae sp. 295. Parastacidae sp. 296. Pentaneurini genus V20 297. Perthildae sp. 298. Philopotamidae sp. 299. Phocus phalangioides 300. Phreadrilidae sp. 301. Phreodrilidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum rr. convexum (SAP) 307. Polypedilum vatsoni 308. Pyralidae sp. 309. Rhantus suturalis 311. Sciridae sp. 312. Scutigerella indecisa 313. Simulidae sp.		33989			P1	
291. Parakiefferiella variegatus 292. Paralimnophyes pullulus (V42) 293. Paramelitidae sp. 294. Paramerina levidensis 295. Parastacidae sp. 296. Pentaneurini genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Pholcus phalangioides 300. Phreodrilidae sp. 301. Phreodrilidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Sciridae sp. 312. Scutigerella indecisa 313. Simuliidae sp.	289.		Palaemonidae sp.			
292. Paralimnophyes pullulus (V42) 293. Paramelitidae sp. 294. Paramerina levidensis 295. Parastacidae sp. 296. Pentaneurini genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Pholcus phalangioides 300. Phreotoicidae sp. 301. Phreotoilidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simulidae sp.	290.		Paracymus spenceri			
293. Paramelitidae sp. 294. Paramenna levidensis 295. Parastacidae sp. 296. Pentaneurini genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Philous phalangioides 300. Phreatoicidae sp. 301. Phreatoicidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Piatynectes decempuntatus var polygrammus 305. Platynectes decempuntatus var polygrammus 306. Polypedilum m. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 310. Riethia v5 311. Scirtidae sp. 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.						
294. Paramerina levidensis 295. Parastacidae sp. 296. Pentaneurini genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Pholous phalangioides 300. Phreatoicidae sp. 301. Phreodrilidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 310. Rientiu suturalis 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.						
295. Parastacidae sp. 296. Pentaneurini genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Pholcus phalangioides 300. Phreatoicidae sp. 301. Phreodrilidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.						
296. Pentaneurini genus V20 297. Perthiidae sp. 298. Philopotamidae sp. 299. Pholcus phalangioides 300. Phreatoicidae sp. 301. Phreodrilidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.						
297. Perthiidae sp. 298. Philopotamidae sp. 299. Pholcus phalangioides 300. Phreatoicidae sp. 301. Phreodrilidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.						
299. Pholcus phalangioides 300. Phreatoicidae sp. 301. Phreodrilidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.						
300. Phreatoicidae sp. 301. Phreodrilidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.	298.		Philopotamidae sp.			
301. Phreodrilidae sp. 302. Planorbidae sp. 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.	299.		Pholcus phalangioides			
302. Platorish gelorup 303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.						
303. Platorish gelorup 304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.			•			
304. Platynectes decempuntatus var polygrammus 305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.						
305. Platynectes sp. 306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.						
306. Polypedilum nr. convexum (SAP) 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.						
 307. Polypedilum watsoni 308. Pyralidae sp. 309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp. 						
309. Rhantus suturalis 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp.	307.					
 310. Riethia v5 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp. 	308.		Pyralidae sp.			
 311. Scirtidae sp. 312. Scutigerella indecisa 313. Simuliidae sp. 						
312. Scutigerella indecisa 313. Simuliidae sp.						
313. Simuliidae sp.						







	Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Query Area
314.		Staphylinidae sp.			
315.		Sternopriscus browni			
316.		Sternopriscus sp.			
317.		Tabanidae sp.			
318. 319.		Tamopsis distinguenda Tanypodinae sp.			
319.		Tanytarsus nr K5			
321.		Tanytarsus palmatus			
322.		Tasmanicosa leuckartii			
323.		Telephlebiidae sp.			
324.		Tetragnatha demissa			
325.		Tipulidae sp.			
326.		Triplectides sp. AV21 (SFM)			
327.		Urodacus novaehollandiae			
328.		Uvarus pictipes			
329.		Veliidae sp.			
330.		Venator immansueta			
331.	04440	Venatrix pullastra			
332. 333.	34113	Westralunio carteri (Carter's Freshwater Mussel) Zachria flavicoma		g	
		Zaoma navicoma			
Mammal					
334.		Antechinus flavipes subsp. leucogaster (Yellow-footed Antechinus, Mardo)			
335.		Bettongia penicillata subsp. ogilbyi (Woylie, Brush-tailed Bettong)		g	
336.		Bos taurus (European Cattle)	Υ		
337. 338.		Caperea marginata (Pygmy Right Whale)			
339.		Cercartetus concinnus (Western Pygmy-possum, Mundarda) Chalinolobus gouldii (Gould's Wattled Bat)			
340.		Chalinolobus morio (Chocolate Wattled Bat)			
341.		Dasyurus geoffroii (Chuditch, Western Quoll)		g	
342.		Eubalaena australis (Southern Right Whale)		g	
343.		Falsistrellus mackenziei (Western False Pipistrelle, Western Falsistrelle)		P4	
344.	24056	Grampus griseus (Risso's Dolphin)			
345.	24215	Hydromys chrysogaster (Water-rat, Rakali)		P4	
346.	48588	Isoodon fusciventer (Quenda, southwestern brown bandicoot)		P4	
347.	24132	Macropus fuliginosus (Western Grey Kangaroo)			
348.		Mesoplodon bowdoini (Andrew's Beaked Whale)			
349.		Mesoplodon grayi (Gray's Beaked Whale)			
350.		Mirounga leonina (Southern Elephant Seal)			
351. 352.		Mus musculus (House Mouse)	Υ	P4	
353.		Notamacropus irma (Western Brush Wallaby) Nyctophilus geoffroyi (Lesser Long-eared Bat)		P4	
354.		Phascogale tapoatafa (Brush-tailed Phascogale)		S	
355.		Phascogale tapoatafa subsp. wambenger (South-western Brush-tailed Phascogale,		o o	
		Wambenger)		S	
356.	24166	Pseudocheirus occidentalis (Western Ringtail Possum, ngwayir)		g	
357.	24245	Rattus rattus (Black Rat)	Υ		
358.	24145	Setonix brachyurus (Quokka)		g	
359.	24111	Sminthopsis gilberti (Gilbert's Dunnart)			
360.	25521	Trichosurus vulpecula (Common Brushtail Possum)			
361.	24158	Trichosurus vulpecula subsp. vulpecula (Common Brushtail Possum)			
362.		Tursiops aduncus (Indo-Pacific Bottlenose Dolphin)			
363.	24206	Vespadelus regulus (Southern Forest Bat)			
Reptile					
364.	42368	Acritoscincus trilineatus (Western Three-lined Skink)			
365.	24990	Aprasia pulchella (Granite Worm-lizard)			
366.	25335	Caretta caretta (Loggerhead Turtle)		g	
367.		Chelonia mydas (Green Turtle)		g	
368.		Christinus marmoratus (Marbled Gecko)			
369.		Cryptoblepharus buchananii			
370.		Ctenotus impar			
371.		Ctenotus labillardieri			
372.		Ctenotus ora (Coastal Plains Skink)		P3	
373. 374		Egernia kingii (King's Skink)			
374. 375		Egernia napoleonis Flanconathus coronatus (Crowned Snake)			
375. 376.		Elapognathus coronatus (Crowned Snake) Hemiargis gracilines (skink)			
376. 377.		Hemiergis gracilipes (skink) Hemiergis peronii subsp. tridactyla			
377. 378.		Hemiergis quadrilineata			
379.		Lerista distinguenda			
5. 5.	20.01	J		Cittle .	
				Departmen	Lot








	Name ID	Species Name	Naturalised	Conservation Code	¹ Endemic To Query Area
380.	25133	Lerista elegans			
381.	25005	Lialis burtonis			
382.	42413	Lissolepis luctuosa (Western Swamp Skink)			
383.	25184	Menetia greyii			
384.	25191	Morethia lineoocellata			
385.	25192	Morethia obscura			
386.	25252	Notechis scutatus (Tiger Snake)			
387.	25255	Parasuta nigriceps			
388.	25510	Pogona minor (Dwarf Bearded Dragon)			
389.	24907	Pogona minor subsp. minor (Dwarf Bearded Dragon)			
390.	25259	Pseudonaja affinis subsp. affinis (Dugite)			
391.	25266	Simoselaps bertholdi (Jan's Banded Snake)			
392.	25519	Tiliqua rugosa			
393.	25207	Tiliqua rugosa subsp. rugosa			
394.	25218	Varanus gouldii (Bungarra or Sand Monitor)			

Conservation Codes
g gRare or likely to become egtinct
g gPresumed egtinct
IA gProtected under international agreement
S gg ther specially protected fauna
1 gPriority 1
2 gPriority 2
3 gPriority 2
3 gPriority 4
5 gPriority 5

¹ For NatureMap's purposes, species flagged as endemic are those g hose records are gholely contained githin the search area. Note that only those records complying gith the search criterion are included in the calculation. For egample, if you limit records to those from a specific datasource, only records from that datasource are used to determine if a species is restricted to the guery area.







EPBC Act Protected Matters Report

ghis report provides general guidance on matters of national environmental significance and other matters protected by the EPBC Act in the area you have selected.

Information on the coverage of this report and gualifications on data supporting this report are contained in the caveat at the end of the report.

Information is available about <u>Environment Assessments</u> and the EPBC Act including significance guidelines, forms and application process details.

Report createdg08g03g19 14g42g56


Summary

Details

Matters of NES
g ther Matters Protected by the EPBC Act
Egtra Information

Caveat

Acknog ledgements



ghis map may contain data ghich are g Commong ealth of Australia gGeoscience Australiag g PSMA 2010

Coordinates
Bufferg1.0gm



Summary

Matters of National Environmental Significance

ghis part of the report summarises the matters of national environmental significance that may occur in, or may relate to, the area you nominated. Further information is available in the detail part of the report, g hich can be accessed by scrolling or folloging the links belog. If you are proposing to undertake an activity that may have a significant impact on one or more matters of national environmental significance then you should consider the Administrative Guidelines on Significance.

World g eritage Propertiesg	None
National geritage Placesg	None
Wetlands of International Importanceg	None
Great Barrier Reef Marine Parkg	None
Commong ealth Marine Areag	None
gisted ghreatened Ecological Communitiesg	1
gisted ghreatened Speciesg	21
gisted Migratory Speciesg	9

g ther Matters Protected by the EPBC Act

ghis part of the report summarises other matters protected under the Act that may relate to the area you nominated. Approval may be reguired for a proposed activity that significantly affects the environment on Commong ealth land, g hen the action is outside the Commong ealth land, or the environment anyghere g hen the action is taken on Commong ealth land. Approval may also be reguired for the Commong ealth or Commong ealth agencies proposing to take an action that is likely to have a significant impact on the environment anyghere.

ghe EPBC Act protects the environment on Commong ealth land, the environment from the actions taken on Commong ealth land, and the environment from actions taken by Commong ealth agencies. As heritage values of a place are part of the 'environment', these aspects of the EPBC Act protect the Commong ealth g eritage values of a Commong ealth g eritage place. Information on the neg heritage lags can be found at httpggggg. environment.gov.augheritage

A <u>permit</u> may be reguired for activities in or on a Commong ealth area that may affect a member of a listed threatened species or ecological community, a member of a listed migratory species, g hales and other cetaceans, or a member of a listed marine species.

Commong ealth gandg	None
Commong ealth g eritage Placesg	None
gisted Marine Speciesg	13
Whales and g ther Cetaceansg	None
Critical g abitatsg	None
Commong ealth Reserves gerrestrialg	None
Australian Marine Parksg	None

Egtra Information

ghis part of the report provides information that may also be relevant to the area you have nominated.

State and gerritory Reservesg	None
Regional Forest Agreementsg	1
Invasive Speciesg	22
Nationally Important Wetlandsg	None
gey Ecological Features gMarineg	None

Details

Matters of National Environmental Significance

gisted ghreatened Ecological Communities		gResource Information g
For threatened ecological communities g here the distributions, State vegetation maps, remote sensing imagery community distributions are less g ell knog n, egisting v produce indicative distribution maps.	and other sources. Where	threatened ecological
Name	Status	gype of Presence
Banksia Woodlands of the Sg an Coastal Plain ecological community	Endangered	Community likely to occur githin area
gisted ghreatened Species		gResource Information g
Name Birds	Status	gype of Presence
Calidris ferruginea		
Curleg Sandpiper <u></u> \$56g	Critically Endangered	Species or species habitat may occur g ithin area
Calyptorhynchus banksii naso		
Forest Redgailed BlackgCockatoo, garrak 67034g	gulnerable	Species or species habitat likely to occur githin area
Calyptorhynchus baudinii		
Baudin's Cockatoo, gongoilled BlackgCockatoo g769g	Endangered	Breeding likely to occur githin area
Calyptorhynchus latirostris Carnaby's Cockatoo, Shortdilled BlackgCockatoo	Endangered	Species or species habitat
ф 9523g	-	knog n to occur githin area
Numenius madagascariensis	o = .	
Eastern Curleg , Far Eastern Curleg <i>g</i> 847g	Critically Endangered	Species or species habitat may occur githin area
Mammals		
Dasyurus geoffroii		
Chuditch, Western g uoll &30g	gulnerable	Species or species habitat likely to occur githin area
Pseudocheirus occidentalis		
Western Ringtail Possum, Ngg ayir, Womp, Woder, Ngoor, Ngoolangit	Critically Endangered	Species or species habitat knog n to occur g ithin area
g ther		
Westralunio carteri		
Carter's Freshg ater Mussel, Freshg ater Mussel	gulnerable	Species or species habitat knog n to occur githin area
Plants		
Banksia nivea subsp. uliginosa		
Sg amp g oneypot &2766g	Endangered	Species or species habitat may occur g ithin area
Banksia sguarrosa subsp. argillacea		
Whicher Range Dryandra &2769g	gulnerable	Species or species habitat may occur githin area

Name	Status	gype of Presence
Brachyscias verecundus Ironstone Brachyscias &1321g	Critically Endangered	Species or species habitat may occur g ithin area
<u>Caladenia hoffmanii</u> g offman's Spidergrchid ф6719g	Endangered	Species or species habitat may occur g ithin area
Chamelaucium sp. S coastal plain gR.D.Royce 4872g Royce's Wagflog er g87814g	gulnerable	Species or species habitat may occur g ithin area
Drakaea micrantha Dg arf g ammergorchid \$6755g	gulnerable	Species or species habitat may occur g ithin area
Eleocharis keigheryi g eighery's Eleocharis £94893g	gulnerable	Species or species habitat may occur g ithin area
Gastrolobium papilio Butterflygeaved Gastrolobium & 8415g	Endangered	Species or species habitat may occur g ithin area
gambertia echinata subsp. occidentalis Western Prickly g oneysuckle	Endangered	Species or species habitat may occur g ithin area
Sphenotoma drummondii Mountain Papergheath &1160g	Endangered	Species or species habitat may occur githin area
Synaphea sp. Fairbridge Farm gD. Papenfus 696g Selena's Synaphea &2881g	Critically Endangered	Species or species habitat may occur githin area
Synaphea sp. Serpentine gG.R. Brand 103g g6879g	Critically Endangered	Species or species habitat may occur githin area
Synaphea stenoloba Dg ellingup Synaphea	Endangered	Species or species habitat may occur g ithin area
gisted Migratory Species gSpecies is listed under a different scientific name on	the EPBC Act gghreatened	gResource Information g
Name Migratory Marine Birds	ghreatened	gype of Presence
Apus pacificus Forkgailed Sg ift 678g		Species or species habitat likely to occur githin area
Migratory gerrestrial Species		
Motacilla cinerea Grey Wagtail 642g		Species or species habitat may occur g ithin area
Migratory Wetlands Species		
Actitis hypoleucos Common Sandpiper		Species or species habitat may occur g ithin area
Calidris acuminata Sharpgailed Sandpiper &74g		Species or species habitat may occur g ithin area
Calidris ferruginea Curleg Sandpiper	Critically Endangered	Species or species habitat may occur g ithin area

Name	ghreatened	gype of Presence
Calidris melanotos		
Pectoral Sandpiper		Species or species habitat may occur g ithin area
Numenius madagascariensis		
Eastern Curleg , Far Eastern Curleg \$47 g	Critically Endangered	Species or species habitat may occur g ithin area
Pandion haliaetus		
g sprey 952g		Species or species habitat may occur githin area
gringa nebularia		
Common Greenshank, Greenshank &32g		Species or species habitat likely to occur githin area

g ther Matters Protected by the EPBC Act

gisted Marine Species	5000 A /	gResource Information g
g Species is listed under a different scientific name on the Name	ghreatened	gype of Presence
Birds	grireateried	gype of i reseries
Actitis hypoleucos		
Common Sandpiper $\mathfrak{G}9309g$		Species or species habitat may occur githin area
Apus pacificus Forkgailed Sg ift g678g		Species or species habitat likely to occur githin area
Ardea alba Great Egret, White Egret		Species or species habitat likely to occur githin area
Ardea ibis Cattle Egret		Species or species habitat may occur githin area
Calidris acuminata Sharpgailed Sandpiper		Species or species habitat may occur githin area
Calidris ferruginea Curleg Sandpiper	Critically Endangered	Species or species habitat may occur githin area
Calidris melanotos Pectoral Sandpiper		Species or species habitat may occur githin area
g aliaeetus leucogaster Whitedellied SeagEagle 943g		Species or species habitat likely to occur githin area
Merops ornatus Rainbog Beegeater 670g		Species or species habitat may occur githin area
Motacilla cinerea Grey Wagtail 642g		Species or species habitat may occur githin area

Name	ghreatened	gype of Presence
Numenius madagascariensis		
Eastern Curleg , Far Eastern Curleg	Critically Endangered	Species or species habitat may occur g ithin area
Pandion haliaetus		
g sprey 952g		Species or species habitat may occur g ithin area
gringa nebularia		
Common Greenshank, Greenshank &32g		Species or species habitat likely to occur githin area

Egtra Information

Regional Forest Agreements	gResource Information g
Note that all areas gith completed RFAs have been included.	
Name	State
South West WA RFA	Western Australia
Invasive Species	gResource Information g

Weeds reported here are the 20 species of national significance gwoNSg along gith other introduced plants that are considered by the States and gerritories to pose a particularly significant threat to biodiversity. ghe follog ing feral animals are reportedgGoat, Red Fog, Cat, Rabbit, Pig, Water Buffalo and Cane goad. Maps from gandscape gealth Project, National gand and Water Resouces Audit, 2001.

Name	Status	gype of Presence
Birds		
Anas platyrhynchos		
Mallard 974g		Species or species habitat likely to occur githin area
Columba livia		
Rock Pigeon, Rock Dove, Domestic Pigeon		Species or species habitat likely to occur githin area
Streptopelia senegalensis		
gaughing gurtlegdove, gaughing Dove & 81g		Species or species habitat likely to occur githin area
Sturnus vulgaris		
Common Starling		Species or species habitat likely to occur githin area
Mammals		
Bos taurus		
Domestic Cattle gl 6g		Species or species habitat likely to occur githin area
Canis lupus familiaris		
Domestic Dog \$ 2654g		Species or species habitat likely to occur githin area
Felis catus		
Cat, gouse Cat, Domestic Cat gl9g		Species or species habitat likely to occur githin area
Mus musculus		
g ouse Mouse gl 20g		Species or species habitat likely to occur githin area

Name	Status	gype of Presence
g ryctolagus cuniculus Rabbit, European Rabbit gl28g		Species or species habitat likely to occur githin area
Rattus rattus Black Rat, Ship Rat <u>\$</u> 4g		Species or species habitat likely to occur githin area
Sus scrofa Pig ��g		Species or species habitat likely to occur githin area
gulpes vulpes Red Fog, Fog gl8g		Species or species habitat likely to occur githin area
Plants		
Asparagus asparagoides Bridal Creeper, Bridal geil Creeper, Smilag, Florist's Smilag, Smilag Asparagus &2473g		Species or species habitat likely to occur githin area
Brachiaria mutica Para Grass &879g		Species or species habitat may occur githin area
Cenchrus ciliaris Buffelggrass, Black Buffelggrass & 20213g		Species or species habitat may occur githin area
Chrysanthemoides monilifera Bitou Bush, Boneseed gl8983g		Species or species habitat may occur githin area
Genista linifolia Flaggeaved Broom, Mediterranean Broom, Flag Broo \$2800g	mo	Species or species habitat likely to occur githin area
Genista sp. g Genista monspessulana Broom <u>\$67538g</u>		Species or species habitat may occur githin area
g lea europaea g live, Common g live ⊉ 160g		Species or species habitat may occur githin area
Pinus radiata Radiata Pine Monterey Pine, Insignis Pine, Wilding Pine �0780g		Species or species habitat may occur githin area
Rubus fruticosus aggregate Blackberry, European Blackberry © 8406g		Species or species habitat likely to occur githin area
Salig spp. egcept S.babylonica, S.g calodendron g S Willogs egcept Weeping Willog, Pussy Willog and Sterile Pussy Willog \$68497g	.g reichardtii	Species or species habitat likely to occur githin area

Caveat

ghe information presented in this report has been provided by a range of data sources as acknogledged at the end of the report.

ghis report is designed to assist in identifying the locations of places g hich may be relevant in determining obligations under the Environment Protection and Biodiversity Conservation Act 1999. It holds mapped locations of World and National geritage properties, Wetlands of International and National Importance, Commong ealth and Stateggerritory reserves, listed threatened, migratory and marine species and listed threatened ecological communities. Mapping of Commong ealth land is not complete at this stage. Maps have been collated from a range of sources at various resolutions.

Not all species listed under the EPBC Act have been mapped goe belog gand therefore a report is a general guide only. Where available data supports mapping, the type of presence that can be determined from the data is indicated in general terms. People using this information in making a referral may need to consider the gualifications belog and may need to seek and consider other information sources.

For threatened ecological communities g here the distribution is g ell knog n, maps are derived from recovery plans, State vegetation maps, remote sensing imagery and other sources. Where threatened ecological community distributions are less g ell knog n, egisting vegetation maps and point location data are used to produce indicative distribution maps.

ghreatened, migratory and marine species distributions have been derived through a variety of methods. Where distributions are gell knogn and if time permits, maps are derived using either thematic spatial data gi.e. vegetation, soils, geology, elevation, aspect, terrain, etcgtogether gith point locations and described habitatgor environmental modelling gMAgENg or BIg CgIM habitat modellinggusing point locations and environmental data layers.

Where very little information is available for species or large number of maps are reguired in a short timegrame, maps are derived either from 0.04 or 0.02 decimal degree cellsgby an automated process using polygon capture techniques gratic tg o kilometre grid cells, alphaghull and conveg hullgg or captured manually or by using topographic features grational park boundaries, islands, etcg. In the early stages of the distribution mapping process g1999@early 2000sgdistributions g ere defined by degree blocks, 100g or 250g map sheets to rapidly create distribution maps. More reliable distribution mapping methods are used to update these distributions as time permits.

g nly selected species covered by the folloging provisions of the EPBC Act have been mappedg

gmigratory and

gmarine

ghe folloging species and ecological communities have not been mapped and do not appear in reports produced from this databaseg

gthreatened species listed as egtinct or considered as vagrants

gsome species and ecological communities that have only recently been listed

gsome terrestrial species that overfly the Commong ealth marine area

gmigratory species that are very gidespread, vagrant, or only occur in small numbers

ghe folloging groups have been mapped, but may not cover the complete distribution of the speciesg

gnonghreatened seabirds g hich have only been mapped for recorded breeding sites

gseals g hich have only been mapped for breeding sites near the Australian continent

Such breeding sites may be important for the protection of the Commong ealth Marine environment.

Coordinates

ф3.51841 115.74103

Acknog ledgements

ghis database has been compiled from a range of data sources. ghe department acknog ledges the folloging custodians g ho have contributed valuable data and adviceg

gg ffice of Environment and geritage, Neg South Wales

Department of Environment and Primary Industries, gictoria

Department of Primary Industries, Parks, Water and Environment, gasmania

Department of Environment, Water and Natural Resources, South Australia

Department of gand and Resource Management, Northern gerritory

Department of Environmental and geritage Protection, gueensland

Department of Parks and Wildlife, Western Australia

gEnvironment and Planning Directorate, ACq

gBrdlife Australia

gAustralian Bird and Bat Banding Scheme

gAustralian National Wildlife Collection

gNatural history museums of Australia

gMuseum gictoria

gAustralian Museum

gSouth Australian Museum

gg ueensland Museum

g nline goological Collections of Australian Museums

gg ueensland g erbarium

<u>qNational g erbarium of NSW</u>

gRoyal Botanic Gardens and National gerbarium of gictoria

ggasmanian g erbarium

gState g erbarium of South Australia

<u>dNorthern gerritory gerbarium</u>

dWestern Australian gerbarium

gAustralian National gerbarium, Canberra

gg niversity of Neg England

gg cean Biogeographic Information System

gAustralian Government, Department of Defence

Forestry Corporation, NSW

Geoscience Australia

gCSIRg

gAustralian gropical gerbarium, Cairns

geBird Australia

gAustralian Government g Australian Antarctic Data Centre

gMuseum and Art Gallery of the Northern gerritory

gAustralian Government National Environmental Science Program

gAustralian Institute of Marine Science

gReef gife Survey Australia

gAmerican Museum of Natural gistory

gg ueen gictoria Museum and Art Gallery, Inveresk, gasmania

ggasmanian Museum and Art Gallery, gobart, gasmania

gg ther groups and individuals

ghe Department is egtremely grateful to the many organisations and individuals g ho provided egpert advice and information on numerous draft distributions.

Please feel free to provide feedback via the Contact gs page.

g_Commong ealth of Australia
Department of the Environment
GPg Bog 787
Canberra ACg 2601 Australia
g61 2 6274 1111

APPENDIX D

BLACK COCKATOO HABITAT TREE DETAILS

Habitat Trees DBH >50cm Datum - GDA94

Entrance Size Ranges - Small = >5cm, Medium = 5, 10cm, Large = >10cm

Entrance Si	ze Kan	iges - Sii	<u> 1811 – 7501</u>	n, Medium = 5, 100	Jili, Large	2 – 10	CIII					
Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt001	50H	383532	6290820	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt002	50H	383525	6290809	Marri	20+	>50	0		No Signs	No Signs	No	
wpt003	50H	383342	6290819	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt004	50H	383294	6290802	Marri	20+	>50	0		No Signs	No Signs	No	
wpt005	50H	383260	6290797	Marri	20+	>50	1	Large (cockatoo)	No Signs	No Signs	Yes	Possible spout
wpt006	50H	383185	6290812	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt007	50H	383129	6290813	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt008	50H	383120	6290814	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt009	50H	383105	6290804	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt010	50H	383048	6290812	Jarrah	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt011	50H	382830	6290809	Jarrah	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt012	50H	382822	6290787	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt013	50H	382826	6290789	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt014	50H	382803	6290796	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt015	50H	382793	6290785	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt016	50H	382778	6290802	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt017	50H	382765	6290801	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt018	50H	382750	6290795	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt019	50H		6290756		15-20	>50	0		No Signs	No Signs	No	
wpt020	50H	382751	6290746	Jarrah	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt021	50H	382746	6290733	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt022	50H	382768	6290741	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt023	50H	382761	6290745	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt024	50H	382774	6290733	Marri	10-15	>50	0		No Signs	No Signs	No	
wpt025	50H	382777	6290728	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt026	50H	382790	6290738	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt027	50H	382805	6290751	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt028	50H	382811		Dead Unknown	15-20	>50	0		No Signs	No Signs	No	
wpt029	50H	382814	6290746	Marri	15-20	>50	0		No Signs	No Signs	No	

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt030	50H	382819	6290739	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt031	50H	382840	6290737	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt032	50H	382838	6290770	Dead Unknown	5-10	>50	1	Medium	No Signs	No Signs	No	
wpt033	50H	382828	6290776	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt034	50H	382803	6290785	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt035	50H	382800	6290774	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt036	50H	382781	6290759	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt037	50H	382926	6290781	Marri	20+	>50	0		No Signs	No Signs	No	
wpt038	50H	383405	6290315	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt039	50H	382927	6290793	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt040	50H	382941	6290781	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt041	50H	382955	6290773	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt042	50H	382990	6290788	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt043	50H	382994	6290799	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt044	50H	383022	6290775	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt045	50H	383037	6290762	Jarrah	15-20	>50	2+	Small-Large (cockatoo)	No Signs	No Signs	Yes	
wpt046	50H	383060	6290774	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt047	50H	383069	6290762	Jarrah	5-10	>50	0		No Signs	No Signs	No	
wpt048	50H	383109	6290784	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt049	50H	383113	6290751	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt050	50H	383134	6290737	Jarrah	15-20	>50	1	Medium	No Signs	No Signs	No	
wpt051	50H	383124	6290736	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt052	50H	383126	6290733	Marri	20+	>50	0		No Signs	No Signs	No	
wpt053	50H	383120	6290732	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt054	50H	383104	6290737	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt055	50H	383104	6290721	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt056	50H	383104	6290727	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt057	50H	383100	6290732	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt058	50H	383079	6290717	Marri	20+	>50	0		No Signs	No Signs	No	
wpt059	50H	383074	6290715	Marri	20+	>50	0		No Signs	No Signs	No	
wpt060	50H	383081	6290696	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt061	50H	383071	6290692	Marri	10-15	>50	0		No Signs	No Signs	No	

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt062	50H	383055	6290669		15-20	>50	0		No Signs	No Signs	No	
wpt063	50H	383040	6290670	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt064	50H	383037	6290638		15-20	>50	0		No Signs	No Signs	No	
wpt065	50H	383037	6290634	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt066	50H	383029	6290619	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt067	50H	383010	6290612	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt068	50H	382973	6290637	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt069	50H	382975	6290659	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt070	50H	382972	6290660	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt071	50H	382966	6290675	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt073	50H	382949	6290692	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt074	50H	382961	6290713	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt075	50H	382970	6290776	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt076	50H	383002	6290757	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt077	50H	383005	6290751	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt078	50H	383012	6290737	Jarrah	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt079	50H	383033	6290728	Marri	10-15	>50	2+	Medium	No Signs	No Signs	No	
wpt080	50H	383063	6290727	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt081	50H	383074	6290735	Jarrah	10-15	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt082	50H	383086	6290766	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt083	50H	383005	6290727	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt084	50H	383004	6290711	Marri	20+	>50	0		No Signs	No Signs	No	
wpt085	50H	382996	6290698	Jarrah	20+	>50	2+	Small	No Signs	No Signs	No	
wpt086	50H	382993	6290712	Jarrah	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt087	50H	382992	6290715	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt088	50H	382989	6290718	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt089	50H	382985	6290727	Jarrah	15-20	>50	2+	Small-Large (cockatoo)	No Signs	No Signs	Yes	Possible knot hole and spout branch
wpt090	50H	383279	6290747	Marri	20+	>50	0		No Signs	No Signs	No	
wpt091	50H	383289	6290746	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt092	50H	383296	6290721	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt093	50H	383293	6290711	Marri	20+	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt094	50H	383276	6290725	Jarrah	15-20	>50	2+	Medium-Large (cockatoo)	No Signs	No Signs	Yes	Possible knot hole - some signs of use?

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt095	50H	383265	6290683	Marri	15-20	>50	2+	Large (cockatoo)	No Signs	No Signs	Yes	Larh knot hole
wpt096	50H	383278	6290678	Dead Marri	15-20	>50	2+	Small-Large (cockatoo)	No Signs	No Signs	Yes	Possible large top opening hollow
wpt097	50H	383279	6290662	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt098	50H	383259	6290667	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt099	50H	383246	6290663	Jarrah	15-20	>50	2+	Medium-Large (cockatoo)	No Signs	No Signs	Yes	Possible large spout
wpt100	50H	383255	6290650	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt101	50H	383253	6290633	Marri	20+	>50	0		No Signs	No Signs	No	
wpt102	50H	383253	6290622	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt103	50H	383251	6290621	Marri	20+	>50	0		No Signs	No Signs	No	
wpt104	50H	383238	6290621	Jarrah	15-20	>50	1	Medium	No Signs	Rub marks	No	
wpt105	50H	383229	6290629	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt106	50H	383223	6290629	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt107	50H	383259	6290615	Marri	20+	>50	0		No Signs	No Signs	No	
wpt108	50H	383267	6290618	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt109	50H	383268	6290614	Marri	15-20	>50	1	Medium	No Signs	No Signs	No	
wpt110	50H	383275	6290610	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt111	50H	383319	6290608	Marri	20+	>50	0		No Signs	No Signs	No	
wpt112	50H	383348	6290606	Marri	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt113	50H	383361	6290598	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt114	50H	383360	6290589	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt115	50H	383373	6290594	Marri	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt116	50H	383381	6290600	Marri	20+	>50	0		No Signs	No Signs	No	
wpt117	50H	383390	6290605	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt118	50H	383400	6290612	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt119	50H	383397	6290593	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt120	50H	383423	6290584	Marri	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt121	50H	383414	6290607	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt122	50H	383474	6290601	Marri	20+	>50	0		No Signs	No Signs	No	
wpt123	50H	383476	6290614	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt124	50H	383479	6290622	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt125	50H	383475	6290638	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt126	50H	383487	6290632	Jarrah	15-20	>50	0		No Signs	No Signs	No	

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt127	50H	383525	6290672	Marri	20+	>50	0		No Signs	No Signs	No	
wpt128	50H	383524	6290681	Marri	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt129	50H	383534	6290687	Dead Marri	15-20	>50	2+	Medium-Large (cockatoo)	No Signs	No Signs	Yes	
wpt130	50H	383532	6290691	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt131	50H	383545	6290699	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt132	50H	383543	6290706	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt133	50H	383536	6290715	Marri	20+	>50	0		No Signs	No Signs	No	
wpt134	50H	383518	6290703	Dead Jarrah	15-20	>50	1	Large (cockatoo)	No Signs	No Signs	Yes	Possible spout
wpt135	50H	383522	6290724	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt136	50H	383517	6290731	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt137	50H	383517	6290749	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt138	50H	383502	6290764	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt139	50H	383481	6290756	Marri	20+	>50	0		No Signs	No Signs	No	
wpt140	50H	383463	6290767	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt141	50H	383452	6290768	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt142	50H	383440	6290772	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt143	50H	383434	6290769	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt144	50H	383430	6290764	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt145	50H	383412	6290776	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt146	50H	383397	6290772	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt147	50H	383388	6290772	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt148	50H	383374	6290767	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt149	50H	383373	6290771	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt150	50H	383370	6290758	Marri	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt151	50H	383365	6290755	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt152	50H	383362	6290767	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt153	50H	383353	6290765	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt154	50H	383348	6290765	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt155	50H	383324	6290717	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt156	50H	383316	6290749	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt157	50H	383329	6290685	Jarrah	15-20	>50	2+	Small-Medium	No Signs		No	
wpt158	50H	383319	6290671	Marri	15-20	>50	0		No Signs	No Signs	No	

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt159	50H	383305	6290655		15-20	>50	0		No Signs	No Signs	No	
wpt160	50H	383302	6290653	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt161	50H	383307	6290635	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt162	50H	383317	6290631	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt163	50H	383342	6290634	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt164	50H	383348	6290633	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt165	50H	383357	6290616	Dead Marri	20+	>50	2+	Small-Large (cockatoo)	No Signs	No Signs	Yes	
wpt166	50H	383370	6290624	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt167	50H	383376	6290624	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt168	50H	383359	6290655	Jarrah	10-15	>50	0		No Signs	No Signs	No	
wpt169	50H	383384	6290636	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt170	50H	383390	6290631	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt171	50H	383410	6290640	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt172	50H	383419	6290641	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt173	50H	383422	6290637	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt174	50H	383425	6290642	Dead Marri	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt175	50H	383436	6290657	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt176	50H	383451	6290653	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt177	50H	383455	6290655	Dead Marri	15-20	>50	0		No Signs	No Signs	No	
wpt178	50H	383453	6290655	Jarrah	10-15	>50	0		No Signs	No Signs	No	
wpt179	50H	383458	6290670	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt180	50H	383472	6290664	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt181	50H	383480	6290654	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt182	50H	383469	6290678	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt183	50H	383492	6290683	Dead Unknown	10-15	>50	1	Medium-Large (cockatoo)	No Signs	No Signs	Yes	Possible large spout
wpt184	50H	383493	6290684	Jarrah	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt185	50H	383503	6290685	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt186	50H	383507	6290693	Marri	20+	>50	0		No Signs	No Signs	No	
wpt187	50H	383510	6290703	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt188	50H	383521	6290697	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt189	50H	383503	6290717	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt190	50H	383481	6290718	Jarrah	15-20	>50	2+	Small-Large (cockatoo)	No Signs	No Signs	Yes	Possible large top opening hollow

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt191	50H	383466	6290714	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt192	50H	383476	6290744	Marri	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt193	50H	383452	6290733	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt194	50H	383419	6290731	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt195	50H	383419	6290728	Marri	15-20	>50	1	Large (cockatoo)	No Signs	Rub marks	Yes	Possible large knot hole
wpt196	50H	383409	6290723	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt197	50H	383404	6290724	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt198	50H	383397	6290748	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt199	50H	383377	6290708	Marri	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt200	50H	383402	6290670	Dead Unknown	10-15	>50	1	Large (cockatoo)	No Signs	No Signs	Yes	Possible spout
wpt201	50H	383399	6290648	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt202	50H	383417	6290681	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt203	50H	383429	6290681	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt204	50H	383430	6290685	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt205	50H	383425	6290701	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt206	50H	383420	6290702	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt207	50H	383452	6290693	Jarrah	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt208	50H	383395	6290311	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt209	50H	383385	6290313	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt210	50H	383306	6290306	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt211	50H	383243	6290304	Dead Unknown	15-20	>50	0		No Signs	No Signs	No	
wpt212	50H	383233	6290304	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt213	50H	383219	6290320	Dead Unknown	15-20	>50	2+	Small	No Signs	No Signs	No	
wpt214	50H	383200	6290330	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt215	50H	383200	6290348	Jarrah	15-20	>50	2+	Small-Large (cockatoo)	No Signs	No Signs	Yes	Numerous possible large hollows
wpt216	50H	383166	6290337	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt217	50H	383163	6290325	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt218	50H	383142	6290316	Dead Marri	20+	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt219	50H	383124	6290328	Dead Unknown	15-20	>50	2+	Medium-Large (cockatoo)	No Signs	No Signs	Yes	Possible spout
wpt220	50H	383110	6290319	Dead Jarrah	15-20	>50	2+	Small	No Signs	No Signs	No	
wpt221	50H	383108	6290309	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt222	50H	383094	6290325	Marri	5-10	>50	1	Large (cockatoo)	No Signs	No Signs	Yes	Possible spout (~4m high)

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt223	50H	383091	6290324	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt224	50H	383083	6290307	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt225	50H	383081	6290308	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt226	50H	383070	6290339	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt227	50H	383061	6290335	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt228	50H	383056	6290329	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt229	50H	383037	6290325	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt230	50H	383024	6290308	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt231	50H	382999	6290328	Jarrah	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt232	50H	382986	6290312	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt233	50H	382955	6290304	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt234	50H	382951	6290302	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt235	50H	382914	6290302	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt236	50H	382900	6290315	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt237	50H	382872	6290309	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt238	50H	382819	6290308	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt239	50H	382814	6290310	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt240	50H	382800	6290317	Dead Jarrah	10-15	>50	2+	Small-Large (cockatoo)	No Signs	No Signs	Yes	Possible hollows in large branches
wpt241	50H	382798	6290317	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt242	50H	382771	6290339	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt243	50H	382780	6290338	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt244	50H	382813	6290349	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt245	50H	382819	6290362	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt246	50H	382831	6290350	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt247	50H	382830	6290337	Marri	5-10	>50	1	Large (cockatoo)	No Signs	No Signs	Yes	Possible spout
wpt248	50H	382848	6290337	Jarrah	15-20	>50	1	Large (cockatoo)	No Signs	No Signs	Yes	Possible spout
wpt249	50H	382856	6290361	Marri	5-10	>50	1	Medium	No Signs	No Signs	No	
wpt250	50H	382919	6290342	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt251	50H	382890	6290378	Dead Unknown	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt252	50H	382908	6290388	Jarrah	15-20	>50	0		No Signs		No	
wpt253	50H	382881	6290382	Dead Unknown	15-20	>50	2+	Small-Medium	No Signs		No	
wpt254	50H	382892	6290391	Dead Unknown	15-20	>50	2+	Small-Medium	No Signs		No	

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt255	50H	382882	6290399	Jarrah	10-15	>50	0		No Signs	No Signs	No	
wpt256	50H	382906	6290414	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt257	50H	382894	6290431	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt258	50H	382886	6290483	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt259	50H	382901	6290504	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt260	50H	382953	6290514	Dead Unknown	0-5	>50	1	Large (cockatoo)	No Signs	No Signs	Yes	Possible spout
wpt261	50H	382951	6290579	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt262	50H	382944	6290584	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt263	50H	382970	6290594	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt264	50H	382990	6290602	Jarrah	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt265	50H	382998	6290597	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt266	50H	383009	6290589	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt267	50H	382989	6290571	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt268	50H	382997	6290561	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt269	50H	382981	6290519	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt270	50H	382981	6290519	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt271	50H	382978	6290519	Jarrah	15-20	>50	1	Medium	No Signs	No Signs	No	
wpt272	50H	382977	6290512	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt273	50H	382973	6290509	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt274	50H	382986	6290479	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt275	50H	383002	6290469	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt276	50H	383006	6290468	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt277	50H	383005	6290440	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt278	50H	383033	6290438	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt279	50H	383061	6290432	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt280	50H	383021	6290422	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt281	50H	383032	6290387	Jarrah	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt282	50H	383026	6290375	Jarrah	15-20	>50	2+	Small	No Signs	No Signs	No	
wpt283	50H	383038	6290378	Jarrah	15-20	>50	2+	Small	No Signs	No Signs	No	
wpt284	50H	383032	6290345	Jarrah	15-20	>50	2+	Small	No Signs	No Signs	No	
wpt285	50H	383025	6290350	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt286	50H	383022	6290350	Jarrah	15-20	>50	2+	Small	No Signs	No Signs	No	

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt287	50H	382997	6290349	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt288	50H	383000	6290366	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt289	50H	382982	6290342	Dead Unknown	15-20	>50	2+	Small	No Signs	No Signs	No	
wpt290	50H	382964	6290347	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt291	50H	382936	6290414	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt292	50H	382931	6290418	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt293	50H	382936	6290418	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt294	50H	382926	6290433	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt295	50H	382938	6290448	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt296	50H	382949	6290438	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt297	50H	382929	6290460	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt298	50H	382931	6290473	Jarrah	15-20	>50	1	Large (cockatoo)	No Signs	No Signs	Yes	Possible spout
wpt299	50H	382982	6290448	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt300	50H	382985	6290455	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt301	50H	382972	6290441	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt302	50H	382970	6290432	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt303	50H	382972	6290407	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt304	50H	382964	6290390	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt305	50H	382999	6290401	Jarrah	0-5	>50	0		No Signs	No Signs	No	
wpt306	50H	383056	6290408	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt307	50H	383062	6290418	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt308	50H	383071	6290408	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt309	50H	383097	6290418	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt310	50H	383106	6290447	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt311	50H	383099	6290462	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt312	50H	383089	6290497	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt313	50H	383099	6290500	Jarrah	15-20	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt314	50H	383106	6290498	Marri	20+	>50	0		No Signs	No Signs	No	
wpt315	50H	383120	6290491	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt316	50H	383115	6290511	Jarrah	15-20	>50	2+	Small	No Signs		No	
wpt317	50H	383167	6290516	Jarrah	20+	>50	2+	Small-Large (cockatoo)	No Signs	No Signs	Yes	Possible large fissure
wpt318	50H	383172	6290501	Jarrah	20+	>50	2+	Small-Medium	No Signs		No	

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt319	50H	383171	6290531	Jarrah	15-20	>50	2+	Small	No Signs	No Signs	No	
wpt320	50H	383197	6290539	Dead Unknown	0-5	>50	0		No Signs	No Signs	No	
wpt321	50H	383205	6290547	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt322	50H	383196	6290579	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt323	50H	383214	6290586	Marri	20+	>50	0		No Signs	No Signs	No	
wpt324	50H	383207	6290564	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt325	50H	383209	6290542	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt326	50H	383216	6290554	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt327	50H	383227	6290553	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt328	50H	383216	6290536	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt329	50H	383224	6290524	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt330	50H	383208	6290518	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt331	50H	383228	6290498	Marri	20+	>50	0		No Signs	No Signs	No	
wpt332	50H	383211	6290494	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt333	50H	383211	6290480	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt334	50H	383204	6290473	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt335	50H	383199	6290457	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt336	50H	383215	6290455	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt337	50H	383211	6290439	Marri	5-10	>50	0		No Signs	No Signs	No	
wpt338	50H	383212	6290412	Marri	20+	>50	0		No Signs	No Signs	No	
wpt339	50H	383227	6290381	Marri	20+	>50	0		No Signs	No Signs	No	
wpt340	50H	383190	6290364	Marri	20+	>50	0		No Signs	No Signs	No	
wpt341	50H	383175	6290378	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt342	50H	383173	6290382	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt343	50H	383171	6290389	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt344	50H	383161	6290369	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt345	50H	383133	6290350	Marri	15-20	>50	0	_	No Signs	No Signs	No	
wpt346	50H	383101	6290346	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt347	50H	383084	6290370	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt348	50H	383140	6290393	Marri	20+	>50	0		No Signs	No Signs	No	
wpt349	50H	383146	6290407	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt350	50H	383160	6290415	Marri	15-20	>50	0		No Signs	No Signs	No	

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt351	50H	383142	6290444	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt352	50H	383126	6290469	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt353	50H	383129	6290477	Jarrah	5-10	>50	1	Medium	No Signs	No Signs	No	
wpt354	50H	383129	6290488	Dead Unknown	5-10	>50	1	Medium	No Signs	No Signs	No	
wpt355	50H	383179	6290484	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt356	50H	383193	6290490	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt357	50H	383186	6290528	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt358	50H	383190	6290447	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt359	50H	383181	6290427	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt360	50H	383195	6290416	Marri	15-20	>50	1	Medium	No Signs	No Signs	No	
wpt361	50H	383184	6290408	Dead Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt362	50H	383193	6290384	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt363	50H	383237	6290480	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt364	50H	383260	6290494	Marri	20+	>50	0		No Signs	No Signs	No	
wpt365	50H	383265	6290498	Marri	15-20	>50	2+	Small-Large (cockatoo)	No Signs	No Signs	Yes	Possible spout
wpt366	50H	383249	6290523	Marri	20+	>50	0		No Signs	No Signs	No	
wpt367	50H	383265	6290554	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt368	50H	383270	6290554	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt369	50H	383267	6290475	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt370	50H	383276	6290464	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt371	50H	383262	6290440	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt372	50H	383275	6290434	Marri	20+	>50	0		No Signs	No Signs	No	
wpt373	50H	383253	6290405	Jarrah	20+	>50	2+	Small-Medium	No Signs	No Signs	No	
wpt374	50H	383240	6290398	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt375	50H	383232	6290389	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt376	50H	383241	6290370	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt377	50H	383250	6290339	Jarrah	15-20	>50	1	Large (cockatoo)	No Signs	No Signs	Yes	Possible spout
wpt378	50H	383269	6290353	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt379	50H	383272	6290342	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt380	50H	383268	6290342	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt381	50H	383262	6290333	Jarrah	15-20	>50	0		No Signs		No	
wpt382	50H	383278	6290354	Jarrah	15-20	>50	0		No Signs	No Signs	No	

Waypoint Number	Zone	mE	mN	Tree Species	Tree Height (m)	DBH (cm)	Number of Hollows	Estimated Hollow Entrance Size Range (cm)	Occupancy	Chew Marks	Potential Cockatoo Nest Hollow	Comments
wpt383	50H	383289	6290346	Marri	10-15	>50	0		No Signs	No Signs	No	
wpt384	50H	383303	6290328	Jarrah	5-10	>50	1	Large (cockatoo)	No Signs	No Signs	Yes	Possible spout
wpt385	50H	383312	6290326	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt386	50H	383316	6290336	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt387	50H	383328	6290339	Marri	20+	>50	0		No Signs	No Signs	No	
wpt388	50H	383356	6290328	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt389	50H	383354	6290324	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt390	50H	383351	6290343	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt391	50H	383383	6290347	Marri	20+	>50	0		No Signs	No Signs	No	
wpt392	50H	383386	6290344	Marri	20+	>50	0		No Signs	No Signs	No	
wpt393	50H	383383	6290332	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt394	50H	383389	6290328	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt395	50H	383405	6290325	Marri	20+	>50	0		No Signs	No Signs	No	
wpt396	50H	383459	6290421	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt397	50H	383461	6290427	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt398	50H	383458	6290429	Marri	20+	>50	0		No Signs	No Signs	No	
wpt399	50H	383452	6290446	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt400	50H	383437	6290459	Marri	15-20	>50	0		No Signs	No Signs	No	
wpt401	50H	383462	6290467	Marri	20+	>50	0		No Signs	No Signs	No	
wpt402	50H	383468	6290468	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt403	50H	383466	6290445	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt404	50H	383476	6290441	Jarrah	20+	>50	0		No Signs	No Signs	No	
wpt405	50H	383474	6290425	Jarrah	15-20	>50	0		No Signs	No Signs	No	
wpt406	50H	383487	6290431	Dead Unknown	15-20	>50	2+	Small	No Signs	No Signs	No	

DISCLAIMER

This fauna assessment report ("the report") has been prepared in accordance with the scope of services set out in the contract, or as otherwise agreed, between the Client and Greg Harewood ("the Author"). In some circumstances the scope of services may have been limited by a range of factors such as time, budget, access and/or site disturbance constraints. In accordance with the scope of services, the Author has relied upon the data and has conducted environmental field monitoring and/or testing in the preparation of the report. The nature and extent of monitoring and/or testing conducted is described in the report.

The conclusions are based upon field data and the environmental monitoring and/or testing carried out over a limited period of time and are therefore merely indicative of the environmental condition of the site at the time of preparing the report. Also it should be recognised that site conditions, can change with time.

Within the limitations imposed by the scope of services, the field assessment and preparation of this report have been undertaken and performed in a professional manner, in accordance with generally accepted practices and using a degree of skill and care ordinarily exercised by reputable environmental consultants under similar circumstances. No other warranty, expressed or implied, is made.

In preparing the report, the Author has relied upon data, surveys, analyses, designs, plans and other information provided by the Client and other individuals and organisations, most of which are referred to in the report ("the data"). Except as otherwise stated in the report, the Author has not verified the accuracy of completeness of the data. To the extent that the statements, opinions, facts, information, conclusions and/or recommendations in the report ("conclusions") are based in whole or part on the data, those conclusions are contingent upon the accuracy and completeness of the data. The Author will not be liable in relation to incorrect conclusions should any data, information or condition be incorrect or have been concealed, withheld, misrepresented or otherwise not fully disclosed to the Author.

The report has been prepared for the benefit of the Client and no other party. The Author assumes no responsibility and will not be liable to any other person or organisation for or in relation to any matter dealt with or conclusions expressed in the report, or for any loss or damage suffered by any other person or organisation arising from matters dealt with or conclusions expressed in the report (including without limitation matters arising from any negligent act or omission of the Author or for any loss or damage suffered by any other party relying upon the matters dealt with or conclusions expressed in the report). Other parties should not rely upon the report or the accuracy or completeness of any conclusions and should make their own enquiries and obtain independent advice in relation to such matters.

The Author will not be liable to update or revise the report to take into account any events or emergent circumstances or facts occurring or becoming apparent after the date of the report.

APPENDIX 4: HERITAGE SEARCH





List of Aboriginal Cultural Heritage (ACH) Register

For further important information on using this information please see the WA.gov.au website's Terms of Use at https://www.wa.gov.au/terms-of-use

Search Criteria

No Aboriginal Cultural Heritage (ACH) Register in Custom search area - Polygon - 115.734472636272°E, 33.5158407216949°S (GDA94) : 115.746006135035°E, 33.5158765016346°S (GDA94) : 115.747840766001°E, 33.5204114891763°S (GDA94) : 115.734418992092°E, 33.5204562117354°S (GDA94) : 115.734483365108°E, 33.5158317767077°S (GDA94) : 115.734472636272°E, 33.5158407216949°S (GDA94)

Disclaimer

Aboriginal heritage holds significant value to Aboriginal people for their social, spiritual, historical, scientific, or aesthetic importance within Aboriginal traditions, and provides an essential link for Aboriginal people to their past, present and future. In Western Australia Aboriginal heritage is protected under the *Aboriginal Heritage Act 1972*.

All Aboriginal cultural heritage in Western Australia is protected, whether or not the ACH has been reported or exists on the Register.

The information provided is made available in good faith and is predominately based on the information provided to the Department of Planning, Lands and Heritage by third parties. The information is provided solely on the basis that readers will be responsible for making their own assessment as to the accuracy of the information. If you find any errors or omissions in our records, including our maps, it would be appreciated if you provide the details to the Department via https://achknowledge.dplh.wa.gov.au/ach-enquiry-form and we will make every effort to rectify it as soon as possible.

South West Settlement ILUA Disclaimer

Your heritage enquiry is on land within or adjacent to the following Indigenous Land Use Agreement(s): Gnaala Karla Booja Indigenous Land Use Agreement.

On 8 June 2015, six identical Indigenous Land Use Agreements (ILUAs) were executed across the South West by the Western Australian Government and, respectively, the Yued, Whadjuk People, Gnaala Karla Booja, Ballardong People, South West Boojarah #2 and Wagyl Kaip & Southern Noongar groups, and the South West Aboriginal Land and Sea Council (SWALSC).

The ILUAs bind the parties (including 'the State', which encompasses all State Government Departments and certain State Government agencies) to enter into a Noongar Standard Heritage Agreement (NSHA) when conducting Aboriginal Heritage Surveys in the ILUA areas, unless they have an existing heritage agreement. It is also intended that other State agencies and instrumentalities enter into the NSHA when conducting Aboriginal Heritage Surveys in the ILUA areas. It is recommended a NSHA is entered into, and an 'Activity Notice' issued under the NSHA, if there is a risk that an activity will 'impact' (i.e. by excavating, damaging, destroying or altering in any way) an Aboriginal heritage site. The Aboriginal Heritage Due Diligence Guidelines, which are referenced by the NSHA, provide guidance on how to assess the potential risk to Aboriginal heritage.

Likewise, from 8 June 2015 the Department of Energy, Mines, Industry Regulation and Safety (DEMIRS) in granting Mineral, Petroleum and related Access Authority tenures within the South West Settlement ILUA areas, will place a condition on these tenures requiring a heritage agreement or a NSHA before any rights can be exercised.

If you are a State Government Department, Agency or Instrumentality, or have a heritage condition placed on your mineral or petroleum title by DEMIRS, you should seek advice as to the requirement to use the NSHA for your proposed activity. The full ILUA documents, maps of the ILUA areas and the NSHA template can be found at https://www.wa.gov.au/organisation/department-of-the-premier-and-cabinet/south-west-native-title-settlement.

Further advice can also be sought from the Department of Planning, Lands and Heritage via https://achknowledge.dplh.wa.gov.au/ach-enquiry-form.

Copyright

Copyright in the information contained herein is and shall remain the property of the State of Western Australia. All rights reserved. This includes, but is not limited to, information from the Register established and maintained under the *Aboriginal Heritage Act 1972*.

Location information data licensed from Western Australian Land Information Authority (WALIA) trading as Landgate. Copyright in the location information data remains with WALIA. WALIA does not warrant the accuracy or completeness of the location information data or its suitability for any particular purpose



List of Aboriginal Cultural Heritage (ACH) Register

For further important information on using this information please see the WA.gov.au website's Terms of Use at https://www.wa.gov.au/terms-of-use

not matraint the accordacy of completeness of the location information data of its contability for any particular purpose.

Coordinates

Map coordinates are based on the GDA 94 Datum.

Basemap Copyright

Map was created using ArcGIS software by Esri. ArcGIS and ArcMap are the intellectual property of Esri and are used herein under license. Copyright © Esri. All rights reserved. For more information about Esri software, please visit www.esri.com.

Satellite, Hybrid, Road basemap sources: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, HERE, DeLorme, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), MapmyIndia, NGCC, © OpenStreetMap contributors, and the GIS User Community.

Topographic basemap sources: Esri, HERE, DeLorme, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), swisstopo, MapmyIndia, © OpenStreetMap contributors, and the GIS User Community.

Map of Aboriginal Cultural Heritage (ACH) Register

For further important information on using this information please see the WA.gov.au website's Terms of Use at https://www.wa.gov.au/terms-of-use







Copyright for topographic map information shall at all times remain the property of the Commonwealth of Australia, Geoscience Australia - National Mapping Division. All

Aerial Photos, Cadastre, Local Government Authority, Native Title boundary, Roads data copyright © Western Australian Land Information Authority (Landgate).

Mining Tenement, Petroleum Application, Petroleum Title boundary data copyright © the State of Western Australia (Department of Energy, Mines, Industry Regulation and





List of Aboriginal Cultural Heritage (ACH) Historic

For further important information on using this information please see the WA.gov.au website's Terms of Use at https://www.wa.gov.au/terms-of-use

Search Criteria

No Aboriginal Cultural Heritage (ACH) Historic in Custom search area - Polygon - 115.734526280453°E, 33.5158496666812°S (GDA94) : 115.745995406199°E, 33.5158586116666°S (GDA94) : 115.747819308329°E, 33.5203936001462°S (GDA94) : 115.734483365108°E, 33.5204472672255°S (GDA94) : 115.734526280453°E, 33.5158496666812°S (GDA94)

Disclaimer

Aboriginal heritage holds significant value to Aboriginal people for their social, spiritual, historical, scientific, or aesthetic importance within Aboriginal traditions, and provides an essential link for Aboriginal people to their past, present and future. In Western Australia Aboriginal heritage is protected under the Aboriginal Heritage Act 1972.

All Aboriginal cultural heritage in Western Australia is protected, whether or not the ACH has been reported or exists on the Register.

The information provided is made available in good faith and is predominately based on the information provided to the Department of Planning, Lands and Heritage by third parties. The information is provided solely on the basis that readers will be responsible for making their own assessment as to the accuracy of the information. If you find any errors or omissions in our records, including our maps, it would be appreciated if you provide the details to the Department via https://achknowledge.dplh.wa.gov.au/ach-enquiry-form and we will make every effort to rectify it as soon as possible.

South West Settlement ILUA Disclaimer

Your heritage enquiry is on land within or adjacent to the following Indigenous Land Use Agreement(s): Gnaala Karla Booja Indigenous Land Use Agreement.

On 8 June 2015, six identical Indigenous Land Use Agreements (ILUAs) were executed across the South West by the Western Australian Government and, respectively, the Yued, Whadjuk People, Gnaala Karla Booja, Ballardong People, South West Boojarah #2 and Wagyl Kaip & Southern Noongar groups, and the South West Aboriginal Land and Sea Council (SWALSC).

The ILUAs bind the parties (including 'the State', which encompasses all State Government Departments and certain State Government agencies) to enter into a Noongar Standard Heritage Agreement (NSHA) when conducting Aboriginal Heritage Surveys in the ILUA areas, unless they have an existing heritage agreement. It is also intended that other State agencies and instrumentalities enter into the NSHA when conducting Aboriginal Heritage Surveys in the ILUA areas. It is recommended a NSHA is entered into, and an 'Activity Notice' issued under the NSHA, if there is a risk that an activity will 'impact' (i.e. by excavating, damaging, destroying or altering in any way) an Aboriginal heritage site. The Aboriginal Heritage Due Diligence Guidelines, which are referenced by the NSHA, provide guidance on how to assess the potential risk to Aboriginal heritage.

Likewise, from 8 June 2015 the Department of Energy, Mines, Industry Regulation and Safety (DEMIRS) in granting Mineral, Petroleum and related Access Authority tenures within the South West Settlement ILUA areas, will place a condition on these tenures requiring a heritage agreement or a NSHA before any rights can be exercised.

If you are a State Government Department, Agency or Instrumentality, or have a heritage condition placed on your mineral or petroleum title by DEMIRS, you should seek advice as to the requirement to use the NSHA for your proposed activity. The full ILUA documents, maps of the ILUA areas and the NSHA template can be found at https://www.wa.gov.au/organisation/department-of-the-premier-and-cabinet/south-west-native-title-settlement.

Further advice can also be sought from the Department of Planning, Lands and Heritage via https://achknowledge.dplh.wa.gov.au/ach-enquiry-form.

Copyright

Copyright in the information contained herein is and shall remain the property of the State of Western Australia. All rights reserved. This includes, but is not limited to, information from the Register established and maintained under the Aboriginal Heritage Act 1972.

Location information data licensed from Western Australian Land Information Authority (WALIA) trading as Landgate. Copyright in the location information data remains with WALIA. WALIA does not warrant the accuracy or completeness of the location information data or its suitability for any particular purpose



List of Aboriginal Cultural Heritage (ACH) Historic

For further important information on using this information please see the WA.gov.au website's Terms of Use at https://www.wa.gov.au/terms-of-use

not manant the accordacy of completeness of the location information data of its contability for any particular purpose.

Coordinates

Map coordinates are based on the GDA 94 Datum.

Basemap Copyright

Map was created using ArcGIS software by Esri. ArcGIS and ArcMap are the intellectual property of Esri and are used herein under license. Copyright © Esri. All rights reserved. For more information about Esri software, please visit www.esri.com.

Satellite, Hybrid, Road basemap sources: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, HERE, DeLorme, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), MapmyIndia, NGCC, © OpenStreetMap contributors, and the GIS User Community.

Topographic basemap sources: Esri, HERE, DeLorme, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), swisstopo, MapmyIndia, © OpenStreetMap contributors, and the GIS User Community.

Map of Aboriginal Cultural Heritage (ACH) Historic

For further important information on using this information please see the WA.gov.au website's Terms of Use at https://www.wa.gov.au/terms-of-use





Map Scale 1: 14,400



Copyright for topographic map information shall at all times remain the property of the Commonwealth of Australia, Geoscience Australia - National Mapping Division. All

Aerial Photos, Cadastre, Local Government Authority, Native Title boundary, Roads data copyright © Western Australian Land Information Authority (Landgate).

Mining Tenement, Petroleum Application, Petroleum Title boundary data copyright © the State of Western Australia (Department of Energy, Mines, Industry Regulation and



APPENDIX 5: NOISE ASSESSMENT





Lloyd George Acoustics

PO Box 717 Hillarys WA 6923 T: 9401 7770 www.lgacoustics.com.au

Environmental Noise Assessment

Gravel Pit ExpansionLot 287 South Western Highway

Reference: 18114706-01C

Prepared for:

MGM c/- MBS Environmental



Report: 18114706-01C

Lloyd George Acoustics Pty Ltd

ABN: 79 125 812 544

PO Box 717 Hillarys WA 6923

www.lgacoustics.com.au

Contacts	General	Daniel Lloyd	Terry George	Matt Moyle
E:	info@lgacoustics.com.au	daniel@lgacoustics.com.au	terry@lgacoustics.com.au	matt@lgacoustics.com.au
P:	9401 7770	0439 032 844	0400 414 197	0412 611 330
Contacts		- 1 - "		
Contacts	Accounts	Rob Connolly	Daryl Thompson	Hao Tran
E:	Accounts lisa@lgacoustics.com.au	rob@lgacoustics.com.au	daryl@lgacoustics.com.au	Hao Tran

This report has been prepared in accordance with the scope of services described in the contract or agreement between Lloyd George Acoustics Pty Ltd and the Client. The report relies upon data, surveys, measurements and results taken at or under the particular times and conditions specified herein. Any findings, conclusions or recommendations only apply to the aforementioned circumstances and no greater reliance should be assumed or drawn by the Client. Furthermore, the report has been prepared solely for use by the Client, and Lloyd George Acoustics Pty Ltd accepts no responsibility for its use by other parties.

Date:	Rev	Description	Prepared By	Verified
24-Jan-19	1	Issued to Client	Olivier Mallié	Terry George
25-Feb-19	1	Minor edits	Olivier Mallié	-
21-Jul-21	2	Included Eastern pit area	Daniel Lloyd	-
19-Apr-22	В	Pit extents changed	Daniel Lloyd	-
20-Apr-22	С	Minor text change	Terry George	-

Table of Contents

1	INTRODUCTION	1
2	CRITERIA	3
2.1	Reversing Alarms on Mobile Plant	6
3	METHODOLOGY	7
3.1	Meteorological Information	7
3.2	Topographical Data	7
3.3	Ground Absorption	8
3.4	Source Sound Levels	8
4	RESULTS	9
5	ASSESSMENT AND RECOMMENDATIONS	15
6	CONCLUSIONS	21
List	t of Tables	
Table	2-1 Adjustments Where Characteristics Cannot Be Removed	3
Table	2-2 Baseline Assigned Noise Levels	4
Table	2-3 Influencing Factor Calculation	5
Table	2-4 Assigned Noise Levels	5
Table	3-1 Modelling Meteorological Conditions	7
Table	3-2 Source Sound Power Levels	8
Table	4-1 Predicted Noise Levels, dB L _{A10}	9
Table	5-1 Predicted Noise Levels with Mitigation, dB L _{A10}	16

List of Figures

Figure 1-1 Project Locality and Closest Receivers	2
Figure 4-1 Start of Expansion Noise Contour Plot, dB L _{A10}	10
Figure 4-2 Excavation 250 metres from R1 Noise Contour Plot, dB L _{A10}	11
Figure 4-3 Excavation 200 metres from R1 Noise Contour Plot, dB L _{A10}	12
Figure 4-4 Excavation 150 metres from R1 Noise Contour Plot, dB L _{A10}	13
Figure 4-5 Excavation at Eastern Extents Noise Contour Plot, dB L _{A10}	14
Figure 5-1 Excavation 250 metres from R1 with Mitigation, dB L _{A10}	17
Figure 5-2 Excavation 200 metres from R1 with Mitigation, dB L _{A10}	18
Figure 5-3 Excavation 150 metres from R1 with Mitigation, dB L _{A10}	19
Figure 5-4 Excavation at Eastern Extents with Mitigation, dB L _{A10}	20

Appendices

A Terminology

1 INTRODUCTION

It is proposed to expand the existing gravel pit located at Lot 287 South Western Highway, Gwindinup (Shire of Capel). *Figure 1-1* shows the location of the site as well as the lot boundary, the existing pit and potential expansion footprint, and the closest receivers (referred to as R1 to R4).

The existing operations consist of gravel extraction and crushing on-site, with the crushing plant located in the south-west corner of the existing pit. Product is understood to be hauled off-site using up to 65 trucks per day accessing the site via Lowrie Road, and entering the site from the north-west corner. The site is noted to operate only during daytime hours Monday to Saturday (excluding public holidays).

This report presents the assessment of the noise emissions from gravel extraction within the potential expansion, including gravel crushing, against the allowable levels of the *Environmental Protection (Noise) Regulations 1997*. Noise emissions associated with the loading and haulage of product is not considered in this assessment as there are no changes to these activities as part of the potential expansion.

Appendix A contains a description of some of the terminology used throughout this report.




Figure 1-1 Project Locality and Closest Receivers

2 CRITERIA

Environmental noise in Western Australia is governed by the *Environmental Protection Act 1986*, through the *Environmental Protection (Noise) Regulations 1997* (the Regulations).

Regulation 7 defines the prescribed standard for noise emissions as follows:

- "7. (1) Noise emitted from any premises or public place when received at other premises -
 - (a) Must not cause or significantly contribute to, a level of noise which exceeds the assigned level in respect of noise received at premises of that kind; and
 - (b) Must be free of
 - i. tonality;
 - ii. impulsiveness; and
 - iii. modulation,

when assessed under regulation 9"

A "...noise emission is taken to significantly contribute to a level of noise if the noise emission ... exceeds a value which is 5 dB below the assigned level..."

Tonality, impulsiveness and modulation are defined in Regulation 9. Noise is to be taken to be free of these characteristics if:

- (a) The characteristics cannot be reasonably and practicably removed by techniques other than attenuating the overall level of noise emission; and
- (b) The noise emission complies with the standard prescribed under regulation 7 after the adjustments of *Table 2-1* are made to the noise emission as measured at the point of reception.

Table 2-1 Adjustments Where Characteristics Cannot Be Removed

Where	Noise Emission is Not	Where Noise Emission is Music			
Tonality	Modulation	Impulsiveness	No Impulsiveness	Impulsiveness	
+ 5 dB	+ 5 dB	+ 10 dB	+ 10 dB	+ 15 dB	

Note: The above are cumulative to a maximum of 15dB.

The baseline assigned levels (prescribed standards) are specified in Regulation 8 and are shown in *Table 2-2*.

Table 2-2	Baseline	Assigned	Noise	Levels

Premises Receiving		Assigned Level (dB)		
Noise	Time Of Day	L _{A10}	L _{A1}	L _{Amax}
Noise sensitive premises: highly sensitive area ¹	0700 to 1900 hours Monday to Saturday (Day)	45 + influencing factor	55 + influencing factor	65 + influencing factor
	0900 to 1900 hours Sunday and public holidays (Sunday)	40 + influencing factor	50 + influencing factor	65 + influencing factor
	1900 to 2200 hours all days (Evening)	40 + influencing factor	50 + influencing factor	55 + influencing factor
	2200 hours on any day to 0700 hours Monday to Saturday and 0900 hours Sunday and public holidays (Night)	35 + influencing factor	45 + influencing factor	55 + influencing factor
Noise sensitive premises: any area other than highly sensitive area	All hours	60	75	80

^{1.} $\emph{highly sensitive area}$ means that area (if any) of noise sensitive premises comprising —

The closest sensitive receivers are located to the north and east of Lot 287. Lot 287 is zoned rural and the land surrounding the receivers is zoned rural or rural/residential. No significant commercial or industrial land uses were found within 450 metres of the receivers. However, it is noted that with the potential expansion, the excavation area will be located within 450 metres of the closest receivers (R1 to R3). As this area will be considered an industrial land use, the influencing factor therefore increases at these receivers due to the expansion.

In addition, South Western Highway is considered a secondary road given it carries more than 6,000 vehicles per day (Main Roads WA traffic 2017/18 count at site 15058, south of Bendall Road). As such, the influencing factor for sensitive receivers within 100 metres of the Highway will increase by 2 dB. It is noted this road also carries approximately 18% heavy vehicles.

The **existing and future** influencing factor applicable at each noise sensitive premises were determined as shown in *Table 2-3*. In the case of the 'highly sensitive area', the assigned noise levels apply outside the receiving premises and at a point at least 3 metres away from any substantial reflecting surfaces, but within 15 metres of the residence. However, it must be noted that assigned noise levels also apply at the boundary between the lots i.e. 'area other than highly sensitive'.

⁽a) a building, or a part of a building, on the premises that is used for a noise sensitive purpose; and

⁽b) any other part of the premises within 15 metres of that building or that part of the building.

Table 2-3 Influencing Factor Calculation

Description	Within 100 metre Radius	Within 450 metre Radius	Total					
	Existing Scenario							
Industrial Land	Industrial Land R1 to R4 – 0 % R1 to R4 – 0 %							
Commercial Land	Commercial Land R1 to R4 – 0 % R1 to R4 – 0 %							
	Transport Factor, R1 and R2							
	Total							
	Future Scenario (at full expansion)						
Industrial Land	R1 – 25 % Industrial Land R1 to R4 – 0 to 5 % R2 and R3 – 20 % R4 – 0 %							
Commercial Land	R1 to R4 – 0 %	R1 to R4 – 0 %	R1 to R4 – 0 dB					
	Transport Factor, R1 and R2							
		Total	R1 and R2 – 2 dB R3 – 4 dB R4 – 2 dB					

Given the nature and proposed hours of operations, only the daytime L_{A10} assigned noise level is considered applicable. Table 2-4 shows the assigned noise levels including the influencing factor and transport factor at each of the receiving locations.

Table 2-4 Assigned Noise Levels

	Receiver Highly	Assigned Level (dB)		
Time Period	Sensitive Area ¹	Existing	Future	
0700 to 1900 hours Monday to Saturday (Day)	R1	45 dB L _{A10}	47 dB L _{A10}	
	R2	45 dB L _{A10}	47 dB L _{A10}	
	R3	45 dB L _{A10}	49 dB L _{A10}	
	R4	45 dB L _{A10}	47 dB L _{A10}	
All hours	Lot Boundaries	60 dB L _{A10}	60 dB L _{A10}	

^{1.} *highly sensitive area* means that area (if any) of noise sensitive premises comprising —

⁽a) a building, or a part of a building, on the premises that is used for a noise sensitive purpose; and

⁽b) any other part of the premises within 15 metres of that building or that part of the building.

As the assigned noise levels are statistical levels and therefore the period over which they are determined is important. The Regulations define the Representative Assessment Period (RAP) as a period of time of not less than 15 minutes, and not exceeding 4 hours, which is determined by an inspector or authorised person to be appropriate for the assessment of a noise emission, having regard to the type and nature of the noise emission. An inspector or authorised person is a person appointed under Sections 87 & 88 of the Environmental Protection Act 1986 and include Local Government Environmental Health Officers and Officers from the Department of Environment Regulation. Acoustic consultants or other environmental consultants are not appointed as an inspector or authorised person. Therefore, whilst this assessment is based on a 4 hour RAP, which is assumed to be appropriate given the nature of the operations, this is to be used for guidance only.

2.1 Reversing Alarms on Mobile Plant

With regards to noise from reversing alarms, regulation 3(1)(h) states:

- (1) Nothing in these regulations applies to the following noise emissions
 - (h) noise emissions from
 - (i) a reversing alarm fitted to a motor vehicle, mobile plant, or mining or earthmoving equipment;

If -

- (iii) it is a requirement under another written law that such an alarm be fitted; and
- (iv) it is not practicable to fit an alarm that complies with the written law under which it is required to be fitted and emits noise that complies with these regulations;

It is considered that any reversing alarms fitted to the mobile plant and transport trucks are not necessarily exempt under the Regulations, since they are not specifically required under another written law.

The commonly used fixed noise output tonal reversing alarms also known as 'reversing beeper' emit, by their very nature, tonal and modulating noise at high levels. As such, this type of reversing alarm generally cannot comply with the Regulations even at distant receivers. Alternative alarms such as broadband alarms are commonly used to minimise the impact.

3 METHODOLOGY

Computer modelling has been used to predict noise levels at each nearby receiver. The advantage of modelling is that it is not affected by background noise sources and can provide the noise level for various weather conditions and operating scenarios.

The software used was *SoundPLAN 8.2* with the CONCAWE algorithms incorporating the ISO 171534-3 improved method selected. These algorithms have been selected as they include the influence of wind and atmospheric stability. Input data required in the model are:

- Meteorological Information;
- Topographical data;
- Ground Absorption; and
- Source sound power levels.

3.1 Meteorological Information

Meteorological information utilised is provided in *Table 3-1* and is considered to represent worst-case conditions for noise propagation. At wind speeds greater than those shown, sound propagation may be further enhanced, however background noise from the wind itself and from local vegetation is likely to be elevated and dominate the ambient noise levels.

Table 3-1 Modelling Meteorological Conditions

Parameter	Day (0700-1900)
Temperature (°C)	20
Humidity (%)	50
Wind Speed (m/s)	4
Wind Direction*	All
Pasquil Stability Factor	E

^{*} Note that the modelling package used allows for all wind directions to be modelled simultaneously.

It is generally considered that compliance with the assigned noise levels needs to be demonstrated for 98% of the time, during the day and night periods, for the month of the year in which the worst-case weather conditions prevail. In most cases, the above conditions occur for more than 2% of the time and therefore must be satisfied.

3.2 Topographical Data

Topographical data for the natural ground surface was provided by the project in the form of 1 metre contour lines and also sourced from *GoogleEarth* in the form of spot heights. It is noted the land is undulating and slopes up in an eastward direction.

The existing pit was taken to be 2.5 metres deep.

3.3 Ground Absorption

Ground absorption varies from a value of 0 to 1, with 0 being for an acoustically reflective ground (e.g. water or bitumen) and 1 for acoustically absorbent ground (e.g. grass). In this instance, a value of 0.5 (mix of sand and gravel, wet soil) has been used as an average across the study area.

3.4 Source Sound Levels

CAT 972 Front End Loader

The sound power levels used in the modelling are provided in *Table 3-2*.

Octave Band Centre Frequency (Hz) Overall **Description** dB(A) 2k 4k 31.5 1k **Impact Crusher** (Terex Finlay I-130) Supertrak (Terex Finlay 693+) Stacker (Terex Finlay 632) CAT D9 Dozer ripping CAT 980 Front End Loader

Table 3-2 Source Sound Power Levels

The overall noise levels for the fixed plant (e.g. crusher, screen and the stacker) were taken from the previous noise study conducted by others (Herring Storer Acoustics, reference 15336-1-12146) for consistency, noting these are within the range of noise levels used by Lloyd George Acoustics. Spectral information were derived from data already on file for similar equipment.

With regard to the mobile plant e.g. CAT 980 FEL and CAT D9 dozer, the source sound levels were based on data already on file and vendor information.

In addition to the above, the following is noted in regard to each source:

- The sound power levels represent L₁₀ source levels for normal operation; and
- All equipment were modelled as a point source located 2 metres above local ground/pit floor.

4 RESULTS

As there is an existing pit, excavation operations within the expansion area were assumed to start from the existing pit floor and progress in an eastward/northward direction towards receiver R1. The noise emissions from excavation operations in the future area were predicted based on the following assumptions:


- Excavation starts at an average depth of 1.5 metres pit depth from natural ground level, and progresses towards receiver R1. As such mobile plant (e.g. FEL or dozer) is considered to always operate from behind a pit face;
- The front end loader is used to excavate product and cart it to the crusher stockpile;
- The D9 dozer is used occasionally to break / rip gravel or harder soil;
- The fixed plant e.g. crusher, screen and stacker operate while excavation operations are occurring; and
- The fixed plant is located at its current location in the south-western part of the existing pit and remains there or is moved further away from the noise sensitive receivers.

The noise emissions were predicted for various stages of expansion, starting from the existing pit and as excavation operations approach receiver R1 from the west/south. The results of the noise modelling are presented in *Table 4-1* with the noise contribution from the mobile plant alone also shown. *Figures 4-1* to *4-5* also show the predicted noise levels as noise contour maps at ground level as well as the location of each receiver.

Excavation Within Excavation Excavation Excavation **Existing Pit Excavation At** Approx. 250 m Approx. 200 m Approx. 150 m Approx. 500 m **Eastern Extents** from R1 from R1 from R1 Receiver from R1 **Overall Overall Overall** Mobile Mobile Mobile Overall Mobile **Overall** Mobile R1 44 43 54 54 56 56 58 58 59 59 R2 47 42 54 54 52 54 54 55 54 53 R3 40 38 50 55 54 50 50 50 53 53 R4 25 17 28 26 34 34 36 45 45 36

Table 4-1 Predicted Noise Levels, dB LA10

It can be seen from the above that receivers R1 to R3 are potentially the most affected by excavation operations.






Length Scale 1:6000 0 30 60 120 180 m



Lloyd George Acoustics www.lgacoustics.com.au 9401 7770






Length Scale 1:6000 0 30 60 120 180 m




Lloyd George Acoustics www.lgacoustics.com.au 9401 7770




Length Scale 1:6000 0 30 60 120 180 m Lloyd George Acoustics

www.lgacoustics.com.au
9401 7770

0.01.11.0



Length Scale 1:6000 0 30 60 120 180 m Lloyd George Acoustics
www.lgacoustics.com.au
9401 7770





Length Scale 1:6000 0 30 60 120 180 m Lloyd George Acoustics

www.lgacoustics.com.au
9401 7770

5 ASSESSMENT AND RECOMMENDATIONS

The receivers potentially most affected by the expansion are R1 to R3, where the applicable assigned noise level is 47 dB L_{A10} at R1 and R2, and 49 dB L_{A10} at R3.

As excavation operations progress closer to receiver R1, the mobile plant noise contribution becomes dominant over background, and therefore tonality was assumed to be present at the receivers.

Based on the above and the modelling results, compliance with the assigned noise level can be achieved from the start of excavation operations up until approximately 450 metres from receiver R1. Noise controls are then required to mitigate noise levels at R1 to R3 as excavation operations progress towards receiver R1.

The noise controls required vary with the distance to receiver R1 as follows:


- For excavation operations within 200-450 metres of receiver R1:
 - o Provide a 4 metre high noise bund on the top edge of the pit at all times. The modelling indicates the foot of the bund can be up to 6 metres away from the pit's edge.
- For excavation operations within 150-200 metres of receiver R1:
 - o Provide a 4 metre high noise bund on the top edge of the pit at all times. The modelling indicates the foot of the bund can be up to 6 metres away from the pit's edge;
 - o Provide a 3.5m high bund to the north east of the crushing and screening plant; and
 - o The dozer is not to be operated at the same time as the loader.
- For excavation operations at the eastern extents:
 - o Provide a 5 metre high noise bund on the top edge of the pit at all times. The modelling indicates the foot of the bund can be up to 6 metres away from the pit's edge;
 - o Provide a 3.5m high bund to the north east of the crushing and screening plant; and
 - o Use the CAT 972 loader already on site as this item is 2 dB quieter than the CAT 980; and
 - The dozer is not to be operated at the same time as the loader and should not be operated for more than 24 minutes in any 4 hour period.

The predicted noise levels including the recommended mitigation, is provided in *Table 5-1* and shown graphically in *Figures 5-1 to 5-5*, as well as the recommended location and extent of the noise bunds for reference.

From *Table 5-1* it can be seen that compliance with the assigned noise level can be achieved at all receivers for the proposed operations.

Table 5-1 Predicted Noise Levels with Mitigation, dB L_{A10}


Receiver		vation . 250 m n R1	Excavation Approx. 200 m from R1		Excavation Approx. 150 m from R1		Excavation At Eastern Extents	
	Overall	Mobile	Overall	Mobile	Overall	Mobile	Overall	Mobile
R1	40	38	41	40	42	41	42	41
R2	41	36	39	37	42	40	42	35
R3	34	32	36	34	39	38	38	36
R4	25	19	30	29	32	31	32	31






Length Scale 1:6000 0 30 60 120 180 m Lloyd www.


www.lgacoustics.com.au 9401 7770









Lloyd George Acoustics www.lgacoustics.com.au 9401 7770








Lloyd George Acoustics
www.lgacoustics.com.au
9401 7770







Lloyd George Acoustics

www.lgacoustics.com.au 9401 7770

6 CONCLUSIONS

The noise emissions from the excavation operations in the future area to the east of the existing pit were assessed by means of noise modelling.

Based on the assumptions made and the modelling results, it is concluded that compliance with the applicable L_{A10} assigned noise level can be achieved at all receivers as operations approach the closest receivers, provided noise controls are put in place at various stages of operations as described in *Section 5*.

In addition, the following best practices should be implemented during the expansion to further minimise noise impacts:

- If reversing alarms are deemed necessary, all plant operating within 450 metres of receiver R1 are to be fitted with broadband reversing alarms;
- The pit should be developed from south to north, therefore slowly bringing the operations closer to receiver R1 and allowing for equipment to be located against the pit face;
- Local weather conditions should be taken into consideration in scheduling excavation operations and noise bund construction. Noise reductions of the order of 5 dB may be achieved while operating 'upwind' of receivers.
- Noise bunds to be built and maintained using the quietest practicable plant and construction methods e.g. loader working from behind the bund pushing material.

It is noted this assessment assumed that the crushing and screening plant is located in the existing pit (south-western corner) and remaining at this location following the expansion. Should it be desired to move the crushing and screening plant closer to the excavation area(s), additional noise controls will likely be required around the fixed plant, but also in relation to the haul trucks accessing site and loading activities e.g. noise bunds along travel route, truck number restrictions, and/or noise bunds around loading area.

Appendix A

Terminology

The following is an explanation of the terminology used throughout this report.

Decibel (dB)

The decibel is the unit that describes the sound pressure and sound power levels of a noise source. It is a logarithmic scale referenced to the threshold of hearing.

A-Weighting

An A-weighted noise level has been filtered in such a way as to represent the way in which the human ear perceives sound. This weighting reflects the fact that the human ear is not as sensitive to lower frequencies as it is to higher frequencies. An A-weighted sound level is described as L_A dB.

Sound Power Level (L_w)

Under normal conditions, a given sound source will radiate the same amount of energy, irrespective of its surroundings, being the sound power level. This is similar to a 1kW electric heater always radiating 1kW of heat. The sound power level of a noise source cannot be directly measured using a sound level meter but is calculated based on measured sound pressure levels at known distances. Noise modelling incorporates source sound power levels as part of the input data.

Sound Pressure Level (Lp)

The sound pressure level of a noise source is dependent upon its surroundings, being influenced by distance, ground absorption, topography, meteorological conditions etc and is what the human ear actually hears. Using the electric heater analogy above, the heat will vary depending upon where the heater is located, just as the sound pressure level will vary depending on the surroundings. Noise modelling predicts the sound pressure level from the sound power levels taking into account ground absorption, barrier effects, distance etc.

LASIOW

This is the noise level in decibels, obtained using the A frequency weighting and the S (Slow) time weighting as specified in IEC 61672-1:2002. Unless assessing modulation, all measurements use the slow time weighting characteristic.

LAFast

This is the noise level in decibels, obtained using the A frequency weighting and the F (Fast) time weighting as specified in IEC 61672-1:2002. This is used when assessing the presence of modulation only.

L_{APeak}

This is the greatest absolute instantaneous sound pressure in decibels using the A frequency weighting as specified in IEC 61672-1:2002.

LAmax

An L_{Amax} level is the maximum A-weighted noise level during a particular measurement.

L_{A1}

An L_{A1} level is the A-weighted noise level which is exceeded for one percent of the measurement period and is considered to represent the average of the maximum noise levels measured.

L_{A10}

An L_{A10} level is the A-weighted noise level which is exceeded for 10 percent of the measurement period and is considered to represent the "intrusive" noise level.

L_{Aeq}

The equivalent steady state A-weighted sound level ("equal energy") in decibels which, in a specified time period, contains the same acoustic energy as the time-varying level during the same period. It is considered to represent the "average" noise level.

L_{A90}

An L_{A90} level is the A-weighted noise level which is exceeded for 90 percent of the measurement period and is considered to represent the "background" noise level.

One-Third-Octave Band

Means a band of frequencies spanning one-third of an octave and having a centre frequency between 25 Hz and 20 000 Hz inclusive.

L_{Amax} assigned level

Means an assigned level which, measured as a L_{A Slow} value, is not to be exceeded at any time.

L_{A1} assigned level

Means an assigned level which, measured as a $L_{A\,Slow}$ value, is not to be exceeded for more than 1% of the representative assessment period.

L_{A10} assigned level

Means an assigned level which, measured as a L_{A Slow} value, is not to be exceeded for more than 10% of the representative assessment period.

Tonal Noise

A tonal noise source can be described as a source that has a distinctive noise emission in one or more frequencies. An example would be whining or droning. The quantitative definition of tonality is:

the presence in the noise emission of tonal characteristics where the difference between -

- (a) the A-weighted sound pressure level in any one-third octave band; and
- (b) the arithmetic average of the A-weighted sound pressure levels in the 2 adjacent one-third octave bands,

is greater than 3 dB when the sound pressure levels are determined as $L_{Aeq,T}$ levels where the time period T is greater than 10% of the representative assessment period, or greater than 8 dB at any time when the sound pressure levels are determined as $L_{A\,Slow}$ levels.

This is relatively common in most noise sources.

Modulating Noise

A modulating source is regular, cyclic and audible and is present for at least 10% of the measurement period. The quantitative definition of modulation is:

a variation in the emission of noise that —

- (a) is more than 3 dB L_{A Fast} or is more than 3 dB L_{A Fast} in any one-third octave band;
- (b) is present for at least 10% of the representative.

Impulsive Noise

An impulsive noise source has a short-term banging, clunking or explosive sound. The quantitative definition of impulsiveness is:

a variation in the emission of a noise where the difference between $L_{A peak}$ and $L_{A Max slow}$ is more than 15 dB when determined for a single representative event;

Major Road

Is a road with an estimated average daily traffic count of more than 15,000 vehicles.

Secondary / Minor Road

Is a road with an estimated average daily traffic count of between 6,000 and 15,000 vehicles.

Influencing Factor (IF)

$$= \frac{1}{10} \left(\% \text{ Type A}_{100} + \% \text{ Type A}_{450} \right) + \frac{1}{20} \left(\% \text{ Type B}_{100} + \% \text{ Type B}_{450} \right)$$
 where :

% Type A_{100} = the percentage of industrial land within

a100m radius of the premises receiving the noise

 $\%\, Type A_{450} =$ the percentage of industrial land within

a 450m radius of the premises receiving the noise

% Type B_{100} = the percentage of commercial and within

 $a 100 m\, radius\, of\, the\, premises\, receiving\, the\, noise$

%TypeB₄₅₀ = the percentage of commercial land within

a 450m radius of the premises receiving the noise

+ Traffic Factor (maximum of 6 dB)

= 2 for each secondary road within 100m

= 2 for each major road within 450m

= 6 for each major road within 100m

Representative Assessment Period

Means a period of time not less than 15 minutes, and not exceeding four hours, determined by an inspector or authorised person to be appropriate for the assessment of a noise emission, having regard to the type and nature of the noise emission.

Background Noise

Background noise or residual noise is the noise level from sources other than the source of concern. When measuring environmental noise, residual sound is often a problem. One reason is that regulations often require that the noise from different types of sources be dealt with separately. This separation, e.g. of traffic noise from industrial noise, is often difficult to accomplish in practice. Another reason is that the measurements are normally carried out outdoors. Wind-induced noise, directly on the microphone and indirectly on trees, buildings, etc., may also affect the result. The character of these noise sources can make it difficult or even impossible to carry out any corrections.


Ambient Noise

Means the level of noise from all sources, including background noise from near and far and the source of interest.


Specific Noise

Relates to the component of the ambient noise that is of interest. This can be referred to as the noise of concern or the noise of interest.

Chart of Noise Level Descriptors



Typical Noise Levels



DA AND EIL APPLICATION

APPENDIX 6: TRAFFIC IMPACT STATEMENT





Transport Impact Statement

MGM Bulk Pty Ltd Lot 393 Lowrie Road Gwindinup

CW1200811_300306977

29 August 2023

Prepared for:

MGM Bulk Pty Ltd

Prepared by:

Stantec Australia Pty Ltd



Revision	DATE	Description	Author	Reviewed by	Approved by
Α	03/08/2023	For Issue	SV	BS	SJL
В	29/08/2023	For Issue	SV	BS	SJL
С					

This document entitled Sand & Gravel Extraction Site- Lot 393 Lowrie Road, Gwindinup was prepared by Stantec Australia Pty Ltd ("Stantec") for the account of MGM Limestone (the "Client"). Any reliance on this document by any third party is strictly prohibited. The material in it reflects Stantec's professional judgment in light of the scope, schedule, and other limitations stated in the document and the contract between Stantec and the Client. The opinions in the document are based on conditions and information existing at the time the document was published and do not take into account any subsequent changes. In preparing the document, Stantec did not verify the information supplied to it by others. Any use that a third party makes of this document is the responsibility of such third party. A such third party agrees that Stantec shall not be responsible for costs or damages of any kind, if any, suffered by it or any other third party as a result of decisions made or actions taken based on this document.

	C.11 V.
	omesia
Prepared by	
	(signature)
Sai Vemula / Brian Sii	
	1
	Dune
Reviewed by	400
	(signature)
Scott Lambie	
	Mod
Approved by	
	(signature)
Ray Cook	



Table of Contents

1.0	INTRODUCTION	
1.1	BACKGROUND	1
1.2	SITE LOCATION	
2.0	EXISTING SITUATION	3
2.1	EXISTING LAND USES	
2.2	EXISTING ROAD NETWORK	
2.3	EXISTING RESTRICTED ACCESS VEHICLE (RAV) NETWORK	
2.4	EXISTING TRAFFIC VOLUMES	
2.5	CRASH ASSESSMENT	
2.6	INTERSECTION ASSESSMENT	
3.0	PROPOSED DEVELOPMENT	11
3.1	PROPOSED LAND USES	
3.2	ACCESS ARRANGEMENTS	
3.3	PROPOSED HAULAGE ROUTE	
3.4	HOURS OF OPERATION	
4.0	SWEPT PATH ANALYSIS	45
-	SWEPT PATH ANALYSIS	
4.1	SWEPT PATHS ON THE SITE ACCESS	15
5.0	TRIP GENERATION	16
5.1	ESTIMATED TRAFFIC GENERATION	
6.0	SIIMMARY	17

LIST OF TABLES

Table 2-1	Road Hierarchy and Characteristics	5
Table 2-2	Traffic Volumes	7
Table 2-3	Total Crashes	<u>C</u>
Table 2-4	Sight Distance Requirements	
Table 5-1	Estimated Traffic Generation	16
LIST OF FIGUR	RES	
Figure 1-1	Aerial Overview of the Site	2
Figure 2-1	Site Zoning Map	3
Figure 2-2	Road Hierarchy around the Site	5
Figure 2-3	Existing RAV Network	6
Figure 2-4	Crash Location	
Figure 2-5	Lowrie Rd-South Western Hwy Intersection	11
Figure 3-1	Proposed Development Area	12
Figure 3-2	Site Access Arrangement	
Figure 4-1	Swept Path - Site Access	
LIST OF APPE	NDICES	
APPENDIX A	WAPC CHECKLIST	A.1
APPENDIX B	PROPOSED DEVELOPMENT AREA	B.2



1.0 INTRODUCTION

1.1 BACKGROUND

Stantec has been commissioned by MGM Bulk Pty Ltd ('the Client') to undertake a Transport Impact Statement for a Sand & Gravel Extraction Site located at Lot 393 Lowrie Road within Gwindinup, Shire of Capel (the 'Site'). This report aims to assess the impact of the development on the adjacent road network and focus on access arrangements to and from the Site.

This report has been prepared following the Western Australian Planning Commission (WAPC) Transport Impact Assessment Guidelines for Developments: Volume 4 – Individual Developments (2016) and the checklist is included in **Appendix A**.



CW1200811_300306977

1.2 SITE LOCATION

The proposed development site Lot 393 (eastern portion) is located east of the intersection with Lowrie Road and Morris Road. The roads fronting the site are Lowrie Road and Morris Road as shown in **Figure 1-1.**

Figure 1-1 Aerial Overview of the Site



Source: Metromap



CW1200811_300306977

2.0 EXISTING SITUATION

2.1 EXISTING LAND USES

According to the *Shire of Capel's Local Planning Scheme No. 8*, the subject Site is zoned as a 'Rural' area as shown in **Figure** 2-1. The majority of the properties surrounding the Site are zoned as Priority agriculture and Rural areas whereas properties on North-East to the site are zoned for Sate forest and Regional open space.

Legend
Region Scheme Reserves (GBRS)
Regional open space
Regional

Figure 2-1 Site Zoning Map

Source: Shire of Capel LPS No.8



CW1200811_300306977

2.2 EXISTING ROAD NETWORK

Road types are defined in the Main Roads Functional Hierarchy as follows:

- Primary Distributors (Light blue): These roads provide for the major regional and inter-regional traffic movement and carry large volumes of fast-moving traffic. Some are strategic freight routes, and all are State roads. They are managed by Main Roads.
- > Regional Distributors (Red): These are the Roads that are not Primary Distributors but link significant destinations and are designed for efficient movement of people and goods within and beyond regional areas. They are managed by Local Government.
- District Distributor A (Green): These roads carry traffic between industrial, commercial, and residential areas and connect to Primary Distributors. These are likely to be truck routes and provide only limited access to adjoining property. They are managed by Local Government.
- District Distributor B (Dark blue): These roads perform a similar function to District Distributor A but with reduced capacity due to flow restrictions from access to and roadside parking alongside the adjoining property. These are often older roads with a traffic demand in excess of that originally intended. District Distributor A and B roads run between land-use cells and generally not through them, forming a grid that would ideally space them around 1.5 kilometres apart. They are managed by Local Government.
- Local Distributors-Rural (Orange): These roads connect to other Rural Distributors and to Rural Access Roads These are Regional Distributors, but which are designed for efficient movement of people and goods within regional areas. They are managed by the Local government.
- Access Roads (grey): These roads provide access to abutting properties with amenity, safety, and aesthetic aspects having priority over the vehicle movement function. These roads are bicycle and pedestrian friendly. They are managed by the Local government.

The Site is accessed via Lowrie Road at the north-east corner of the Site. This access to Lowrie Road is used for all the vehicle movements to and from the Site, and provides a connection to South Western Highway. The surrounding road network is further characterised in **Table 2-1** and **Figure 2-2** shows the hierarchy as per Main Roads WA Road Information Mapping System.




CW1200811_300306977

Table 2-1 Road Hierarchy and Characteristics

Road Name	Road	Hierarchy		Road Char	acteristics		
(Road ID)	Road Hierarchy	Road Jurisdiction	No. of Lanes	No. of Footpaths	Road Width (m)	Posted Speed (km/h)	
Lowrie Road (2060005)	Local Distributor	Local Government	2 (two-way undivided)	N/A	7.0	110	
Clarke Road (2060010)	Access Road	Local Government	1 (two-way undivided)	N/A	4.0	110	
South Western Highway (H009)	Primary Distributor	MRWA	2 (one lane in each direction, undivided)	N/A	12.0	110	

Source: MRWA Road Information Mapping System

Figure 2-2 Road Hierarchy around the Site



Source: MRWA Road Information Mapping System



CW1200811_300306977

2.3 EXISTING RESTRICTED ACCESS VEHICLE (RAV) NETWORK

Figure 2-3 shows the existing RAV network nearest to the Site. Currently, Lowrie Road has RAV 4 permit access that extends to the northeast edge of the Site till SLK 0.507 and RAV 3 permit access westwards connecting Lowrie Road (SLK 0.507) to Boundary Road.

Cline Rt Cli

Figure 2-3 Existing RAV Network

Source: MRWA HVS Network Map



CW1200811_300306977

2.4 EXISTING TRAFFIC VOLUMES

Existing traffic data were sourced from MRWA's Traffic Map and are summarised below in **Table 2-2.** The traffic volumes were collected relative to the location of the Site along with the hourly peak data for both of these sites during AM and PM.

Table 2-2 Traffic Volumes

Site No.	Road Name	Source	Year	Traffic Volume (% of Heavy Vehicles)	AM Hourly Peak	PM Hourly Peak
1	South Western Highway South of Bridge St (SLK 170.55) Site 15241	MRWA Traffic Map	2018/2019	7,796 (11.8%)	11AM 589 vehicles (308 N & 281 S)	3PM 683 vehicles (337 N & 346 S)
2	South Western Highway South of Knights Rd (SLK 179.23) Site 53535	MRWA Traffic Map	2021/2022	7,465 (16.2%)	11AM 591 vehicles (305 N & 286 S)	3PM 607 vehicles (278 N & 329 S)
3	Lowrie Road 100m East of Clarke Rd. SLK 1340	Shire of Capel	July 2015	237.4 (35.38%)	15.6 vehicles	24.7 vehicles
4	Lowrie Road 250m from South Western Hwy	Shire of Capel	July 2020	333 (35.4%)	33.2 vehicles	36.5 vehicles

Source: MRWA Traffic Map

The traffic count data was also obtained from the Shire of Capel for the year 2015 and 2020 at two different sites located on Lowrie Road near the subject Site.




CW1200811_300306977

2.5 CRASH ASSESSMENT

Recorded crashes on the road network surrounding the Site were extracted from the available MRWA database between 2018 and 2022. Results of the crash assessment are presented in **Table 2-3. Figure 2-4** illustrates the location and severity of these crashes.

Figure 2-4 Crash Location



Source: MRWA Crash Reporting Centre



CW1200811_300306977

Table 2-3 Total Crashes

Type of Crash (RUM Code)	Fatal	Hospital	Medical	Major Property Damage	Minor Property Damage	Total Crashes
Right Angle	-	-	-	2	-	2
Total	-	-	-	2	-	2

From the assessment conducted, two (2) crash incidents were recorded along the surrounding road network; observations are summarised as follows:

- > The two (2) recorded were all Right-Angle crashes at the intersection;
- Both crashes resulted in major property damage only;
- > These incidents occurred along South Western Highway and Lowrie Road; and
- No crash incidents were recorded along Morris Road, Clarke Road, and Brilliant Road.

A history of similar type of crashes occurring within the same road section suggests further investigation should be undertaken to identify the underlying cause. It is noted that all the crashes occurred near the intersection of SWH and Lowrie Road. However, both crashes are Major Property Damage only with no casualty. The existing Basic right turn and the Auxiliary left turn lanes with good Safe Intersection Sight Distance (SISD) significantly reduces the risk of major crashes. As such, the additional truck movements in and out of this intersection may be less likely to contribute to additional crashes.

2.6 INTERSECTION ASSESSMENT

An intersection assessment has been carried out for the Lowrie Road and South Western Highway intersection as shown in **Figure 2-5**. For a robust assessment, the design speed of truck and car of 110 km/h and 120 km/h has been adopted from the Austroads Guide to Road Design. The minimum required safe intersection sight distance (SISD) for the trucks turning onto South Western Hwy from Lowrie Road is 302m for both north and south directions (for the design speed of 110 km/h). The minimum required safe intersection sight distance (SISD) for cars turning onto South Western Hwy from Lowrie Road is 341m for both north and south directions (for the design speed of 120 km/h). After carrying out the assessment, it is noted that the available SISD from both directions is as much as 500m, thus satisfying the Austroads minimum requirements.

Austroads Guide to Road Design Part4A Section A.10 was reviewed where it is suggested that an acceleration lane may be preferable where SISD is insufficient and/or traffic volumes on the road and the number of trucks entering are relatively high. According to the MRWA Standard Restricted Access Vehicle Route Assessment Guidelines, the required sight distance for posted speed limit of 100km/h for RAV is 252m, which can be achieved at this intersection. As the sight distance available on the through road is



CW1200811_300306977

9

good, it is relatively easy for through drivers to perceive the slow movement of these vehicles and to slow for them.

According to the historical traffic volume data, the through traffic in during the peak hours along South Western Highway is between 300-350vph in one direction. This would translate to approximately 6 vehicles per minute, or 1 car per 10 seconds in any direction.

This indicates that a turning vehicle/truck would have an average gap of 10 seconds, (approximately 300m on 110km/h posted speed). This gap is more than sufficient for through drivers to perceive the slow movement of these vehicles and to slow for them if required.

Table 2-4 Sight Distance Requirements

Sight Distance Type	Vehicle Type	Design Speed (km/h)	Reaction Time (R _T)	Distance (m)
SISD	Truck	110	2.5 sec	302m (minimum)
SISD	Car	120	2.5 sec	341m (minimum)
ASD	Car	120	2.5 sec	241m (minimum)

Source: Guide to Road Design Part 4A



CW1200811_300306977



Figure 2-5 Lowrie Rd-South Western Hwy Intersection

Source: Metromap

3.0 PROPOSED DEVELOPMENT

3.1 PROPOSED LAND USES

A portion of the Site Lot 393 is currently being used for the extraction of sand and gravel located to the eastern end of Lowrie Road. The indicative extraction area of the Site is 31.4 hectares, as shown in **Figure 3-1** (also provided in **Appendix B**).



CW1200811_300306977



Figure 3-1 Proposed Development Area

Source: MBS Environmental

3.2 ACCESS ARRANGEMENTS

Although the Site (Lot 393) can be accessed via Morris Road, the extractive operations will only utilise the access onto Lowrie Road at the North East corner of the site. This access is currently being used by both Lot 393 and the adjacent Lot 287 as illustrated in **Figure 3-2**.



CW1200811_300306977

12



Figure 3-2 Site Access Arrangement

Source: Metromap

3.3 PROPOSED HAULAGE ROUTE

Trucks leaving the Site drive in both directions on Lowrie Road, South Western Highway is only accessible with a RAV 4 permit (east) or RAV 3 permit (west). All hauling activities will be conducted by several truck configurations such as 6 wheelers, semi's, rigid trucks, dog trailers and semi-trailers up to 27.5m.



CW1200811_300306977

13

3.4 HOURS OF OPERATION

The proposed development site will operate between 7:00 am to 6:00 pm Monday to Friday and 7:00 am to 1:00 pm on Saturday. Days of operation will be from Monday to Saturday with an expected maximum movement of up to 150 truck trips per day (weekdays).



CW1200811_300306977

4.0 SWEPT PATH ANALYSIS

Swept path checks were conducted to assess the manoeuvrability of transport trucks along the haulage route of the proposed development. Swept path checks were conducted using the 27.5 RAV truck as design vehicles to emulate the trucks moving in and out of the proposed development.

4.1 SWEPT PATHS ON THE SITE ACCESS

Figure 4-1 Swept Path - Site Access



Figure 4-1 above shows the indicative swept path at the Site's access point, approximately 500m West of the intersection of Lowrie Road and South Western Highway. The crossover from Lowrie road to the site track is sealed and caters for road train truck configuration. Swept path analysis on the aerial image suggests that the existing access is adequate to accommodate one way movement only. A layby area has been provided approximately 65m south of the intersection, allowing for exiting vehicles to give way to entering vehicles if required.



CW1200811_300306977

15

5.0 TRIP GENERATION

5.1 ESTIMATED TRAFFIC GENERATION

For this assessment, a generated trip is defined by the ingress and egress movement of vehicles relative to the Site. If a vehicle is to enter and exit the Site on the same day, the vehicle is considered to generate 2 trips per day.

The maximum daily truck movements to and from the Site are proposed to be, 75 loaded trucks per day. Therefore, the Site is expected to generate up to 150 truck trips per day, which could be translated to approximately 14 truck trips/hour on average. **Table 5-1** provides a tabular summary of the estimated trips for the proposed development.

Table 5-1 Estimated Traffic Generation

Estimated Site-generated Trips	No. of Vehicles (11 hours of operation per day)	
	Daily	Hourly
Truck Trips	150	14 (7 IN & 7 OUT)

Note that the values above were based on maximum extraction. The actual number of trips generated by the development will vary based on time of day and extraction requirements through the life of the Site.

Based on the estimated site-generated trips, 14 hourly trips = approximately 1 truck per 5 minutes.

- Traffic management, such as the use of intercom, could be put in place to manage the inbound and outbound movements to minimise potential conflict at the access.
- > Due to Low background traffic on Lowrie Road, additional truck traffic from the Site is unlikely to generate any significant delays to the existing traffic using the road.
- Existing intersection turning facilities (auxiliary lanes) minimise the delay for through traffic on South Western Highway even with the increased entering volumes. Some queueing may occur on Lowrie Road leg, but the delay is unlikely to significantly impact the overall operation of the intersection.



CW1200811_300306977

6.0 SUMMARY

This Transport Impact Statement outlines the transport aspects of the proposed development focusing on traffic operations and access. Included are discussions regarding traffic generation and potential issues.

This statement has been prepared following the WAPC Transport Assessment Guidelines for Developments: Volume 4 – Individual Developments (2016).

The following conclusions are made for the proposed development:


- The proposed development is a Sand & Gravel extraction site located at the eastern end of Lowrie Road within Gwindinup, Shire of Capel;
- ➤ The proposed truck movements in and out of the Site are expected to be up to 150 daily truck movements in and out of the Site which translate to approximately 14 truck trips per hour on average.
- > Two crashes over five years were recorded at the intersection of Lowrie Road and South Western Highway and both crashes are Major Property Damage only. The existing Basic right turn and the Auxiliary left turn lanes with good Safe Intersection Sight Distance (SISD) significantly reduces the risk of major crashes. Therefore, the additional truck movements in and out of this intersection are less likely to contribute to additional crashes.
- Swept path analysis of 27.5m trucks have been conducted for the assessment. The analysis suggests that 27.5m trucks could be accommodated to access the site from northeast corner of Lowrie road.

Overall, the traffic assessment has been conducted for the worst-case scenario for the Sand & Gravel extraction site- Lot 393 Lowrie Road Gwindinup. On normal days, the truck volumes are likely to be much lower than assessed and is unlikely to have a substantial long-term impact on traffic operations and the overall safety of the road network around it.



CW1200811_300306977

17



APPENDIX A WAPC CHECKLIST


ltem	Status	Comments/Proposals
Proposed Development		
Proposed Land Use	Section 3	
Existing Land Uses	Section 2	
Context with Surrounds	Section 2	
Vehicular Access and Parking		
Access Arrangements	Section 3	
Public, Private, and Disabled Parking Set Down / Pick-up	N/A	
Service Vehicles (non-residential)		
Access Arrangements	Section 3	
On/Off-site Loading Facilities	N/A	
Service Vehicles (residential)		
Rubbish Collection and Emergency Vehicle Access	N/A	
Hours of Operation (non-residential only)	Section 3	
Traffic Volumes		
Daily or Peak Traffic Volumes	Section 2	
Type of Vehicles (e.g., cars, trucks)	Section 2	
Traffic Management on Frontage Streets	N/A	
Public Transport Access		
Nearest Bus/Train Routes	N/A	
Nearest Bus Stops/Train Stations	N/A	
Pedestrian/Cycle Links to Bus Stops/Train Station	N/A	
Pedestrian Access/Facilities		
Existing Pedestrian Facilities Within The Development (If Any)	N/A	
Proposed Pedestrian Facilities Within Development	N/A	
Existing Pedestrian Facilities On Surrounding Roads	N/A	
Proposals To Improve Pedestrian Access	N/A	
Cycle Access/Facilities		
Existing Cycle Facilities Within The Development (If Any)	N/A	
Proposed Cycle Facilities Within The Development	N/A	
Existing Cycle Facilities On Surrounding Roads	N/A	
Proposals To Improve Cycle Access	N/A	
Site-specific Issues	N/A	
Safety Issues		
Identify Issues	N/A	
Remedial Measures	N/A	



APPENDIX B PROPOSED DEVELOPMENT AREA



CW1200811_300306977 B.2





DA AND EIL APPLICATION

APPENDIX 7: SURVEY VERIFICATION



Ian Cocker

From: Admin <admin@bcesurveying.com.au>
Sent: Thursday, 7 April 2011 10:09 AM

To: Ian Cocker

Subject: Site Survey Lot 287 Sth Western Highway Gwindinup (E3205)

Attachments: E3205 Final DF_LTYPE.shx; E3205 Final DF.dwg

Dear Ian

Please confirm receipt of the attached file via return email.

Regards,

<u>Don Forrest</u> Supervising Surveyor BCE Surveying Pty Ltd

Ph: 9791 7411 / 0417 182 863


Fax: 9791 9315

PLEASE READ THE FOLLOWING NOTICE CAREFULLY:

If you have received this email in error please advise the sender immediately and erase all copies of this message and attachments as it is confidential and may also be subject to legal privilege. If you are not the intended recipient, please be advised that any use, dissemination, distribution or copying of this message or data is prohibited. Whilst care has been taken, it is recommended that you scan any attachments for viruses.

The attached files are supplied subject to the following condition: That this statement always remains with the data as provided in the event when it is passed onto a third party. That the data is not altered in any way without the prior approval of *BCE Surveying Pty Ltd*. That the following information is noted and accepted: (1) Where a coordinate system is used, the data may have been truncated. (2) Where boundary information is supplied it is current as of the date of this file and is subject to variation and should be read in conjunction with Department Land Information Registered Diagrams & Plans. (3) *BCE Surveying Pty Ltd* accept no liability for any loss or damage howsoever arising from future changes that may be applied to this data, or from use of the data for purposes for which it was not intended. (4) *BCE Surveying Pty Ltd* acknowledges that the client has copyright over the product however, this is restricted to the use for which the data was prepared. (5) *BCE Surveying Pty Ltd* is acknowledged as the author of the data. Any further limitations of use that may be contained within the product itself must be accepted by the use. Where the data is presented in hard copy format, then the statements contained in conditions 3 & 4 shall be included. The responsibility of *BCE Surveying Pty Ltd* is removed if these conditions of use are not observed.

Please consider the environment before printing this e-mail notice



DA AND EIL APPLICATION

APPENDIX 8: STORMWATER MANAGEMENT PLAN



STORMWATER MANAGEMENT PLAN

LOT 393 LOWRIE ROAD AND LOT 287 SOUTH WESTERN HIGHWAY, **GWINDINUP** (REV 7)

PREPARED FOR:


MARIO MICHELE GIACCI

FEBRUARY 2024

PREPARED BY:

Martinick Bosch Sell Pty Ltd
4 Cook Street
West Perth WA 6005
Ph: (08) 9226 3166
Email: info@mbsenvironmental.com.au Web: <u>www.mbsenvironmental.com.au</u>





environmental and geoscience consultants

LOT 393 LOWRIE ROAD AND LOT 287 SOUTH WESTERN HIGHWAY STORMWATER MANAGEMENT PLAN

Distribution List:

Company	Contact name	Copies	Date
MGM Bulk Pty Ltd	Craig Carbone — Director	Electronic	27 February 2024

Document Control for Job Number: MGML393

Document Status	Prepared By	Authorised By	Date
Draft Report	Michael Dufty	Kirsi Kauhanen	14 January 2024
Final Report	Michael Dufty	Kirsi Kauhanen	27 February 2024

Disclaimer, Confidentiality and Copyright Statement

This report is copyright. Ownership of the copyright remains with Martinick Bosch Sell Pty Ltd (MBS Environmental) and Mario Michele Giacci.

This report has been prepared for **Mario Michele Giacci** on the basis of instructions and information provided by **Mario Michele Giacci** and therefore may be subject to qualifications which are not expressed.

No person other than those authorised in the distribution list may use or rely on this report without confirmation in writing from MBS Environmental and **Mario Michele Giacci**. MBS Environmental has no liability to any other person who acts or relies upon any information contained in this report without confirmation.

This report has been checked and released for transmittal to Mario Michele Giacci.

These Technical Reports:

- Enjoy copyright protection and the copyright vests in Martinick Bosch Sell Pty Ltd (MBS Environmental) and Mario Michele Giacci unless otherwise agreed in writing.
- May not be reproduced or transmitted in any form or by any means whatsoever to any person without the written permission of the Copyright holder.



TABLE OF CONTENTS

1.	Introduction	1
1.1 1.2	BACKGROUND AND SCOPE	
2.	HYDROLOGY AND CATCHMENTS	3
2.1 2.2 2.3 2.4	CATCHMENTS RAINFALL AND CLIMATERUNOFF COEFFICIENT AND CATCHMENT YIELDPEAK FLOW.	5 5
3.	STORMWATER MANAGEMENT	7
3.1 3.2 3.3 3.3.1 3.3.2 3.4	OPERATIONAL CONTEXT DIVERSION BANKS RETENTION PONDS AND CATCH DRAINS Retention Pond Specification. Catch Drain Specifications CONTOUR BANKS	
4.	MONITORING AND MAINTENANCE	16
5.	ROLES AND RESPONSIBILITIES	17
6.	REFERENCES	18
	TABLES	
Table 1:	Rainfall Intensity Frequency Duration Data for Lot 393 and Lot 287	5
Table 2:	Calculated 1% AEP Peak Flows	6
Table 3:	Runoff Capacity Required for Retention Ponds	10
Table 4:	Roles and Responsibilities	17
	Figures	
Figure 1:	Location and Regional Drainage	4
Figure 2:	Stormwater Management Measures	9
Figure 3:	Retention Pond Design Cross-section	11
Figure 4:	Major Retention Pond Lot 287	13
Figure 5:	Catch Drain Design Cross-section — V Drain	14
Figure 6:	Catch Drain Design Cross-section — Additional Stripping	15
	APPENDICES	
Appendix 1:	Hydrological Calculations — Lot 393 Lowrie Road	
Appendix 2:	Hydrological Calculations — Lot 287 Southwestern Highway	



1. Introduction

1.1 BACKGROUND AND SCOPE

Mario Michele Giacci is the owner of Lot 393 Lowrie Road (Lot 393) and Lot 287 South Western Highway (Lot 287) (the properties) in Gwindinup, located within the Shire of Capel (Figure 1). Mr Giacci holds Development Approvals (DA) and Extractive Industry Licences (EIL) from the Shire of Capel for extraction of sand and gravel on the properties. The most recent DA/EIL application for Lot 287 provides for the extension of extraction further to the east.

Shire of Capel Local Planning Policy LPP6.2 Extractive Industries specifies that DA and EIL applications include a Stormwater Management Plan. Previous DA condition (e) for Lot 393 (from 2022) also states following:

e) Prior to Commencement a detailed Engineering design plan of the stormwater disposal system shall be submitted for approval of the Shire of Capel, and thereafter implemented in accordance with the approved plan to the satisfaction of the Shire of Capel.

This Stormwater Management Plan (SMP) has been prepared to address the above requirements. It has been developed with reference to the Department of Water and Environmental Regulation (DWER) submission to the 2019 DA/EIL applications, which recommend:

- Cut-off bunds will be constructed along boundaries to the Extractive Industry (EI) area to prevent any external runoff from entering active EI areas.
- All stormwater runoff from active EI areas shall be contained onsite initially, through detention ponds and settling pits, to achieve effective removal of sediment and turbidity.
- All runoff from active EI areas shall be contained onsite initially, through the detention pond (as described) to achieve effective removal of sediment and turbidity.
- Stormwater management structures shall be designed to manage at minimum the calculated runoff, with detention ponds / sediment traps designed and built to an adequate standard and capacity, prior to extraction beginning.
- Any El licence include a condition whereby following the occurrence of a rainfall event greater than the 10-year / 2-hour Average Recurrence Interval, the proponent shall inspect the site and within 48 hours report to the Shire, with details of impacts and remediation actions (if required).
- Stormwater detention ponds include an overflow spillway, or acceptable alternative, to manage discharge of excess water in events up to and including the 100-year Average Recurrence Interval / 1% annual exceedance probability.
- A 'Stormwater Management Plan' be prepared, including details of the proposed measures taken to manage and contain calculated runoff within each stage of the proposed extractive activity.

This SMP (Rev7) supersedes all previous revisions of the plan. It includes amendments made following a review of stormwater leaving the site on Lot 393 in 2022 during high rainfall events. Key amendments include changing assumptions regarding soil profile and runoff coefficients (see Section 2.3) and pit depth (see Section 3), and increasing the size of the retention ponds (see Section 3.3). Indicative proposed locations for ponds and drains have been amended to match installation in areas that have been completed. At the time of preparation of this SMP, Stages 1 to 11 of Lot 287 and Stages 1 and 2, and most of 4 and 5 of Lot 393 have had extraction activities completed and rehabilitation works commenced.

1.2 OBJECTIVE

The objective of this SMP is to reduce the potential of impacts from extractive activities on downstream waters, specifically sediment and turbidity impacts caused by stormwater runoff from disturbed areas.



STORMWATER MANAGEMENT PLAN

This will be achieved by the construction of stormwater management structures to contain initial runoff from extraction areas from rainfall events up to 10% Annual Exceedance Probability (AEP) and 2 hours duration. AEP is the currently preferred terminology for rainfall event probability, as used in the current edition of Australian Rainfall and Runoff (Ball et al. 2019). A 10% AEP event is equivalent to a 10-year Average Recurrence Interval specified in the DWER comments (see Section 1.1).



2. HYDROLOGY AND CATCHMENTS

2.1 CATCHMENTS

The project site is situated at the eastern edge of the catchment of Gynudup Brook, a tributary of the Capel River that discharges into the Indian Ocean at Geographe Bay. There are no watercourses at the site due to the well-draining soil and lack of upstream catchment area (the site is within 500 m of the upstream watershed). Almost the entire extraction area is within the Gynudup brook catchment, which drains west. A small area of proposed extraction (approximately 1.3 ha) at the eastern limit of the extraction area on Lot 287 is within the Preston River Catchment and drains east toward the Preston River. The location of the project site and relevant catchments are shown in Figure 1. Most of the Lot 287 extraction area is within the upstream catchment of Lot 393.

The extraction areas within the Gynudup Brook catchment slope to the northwest, while extraction areas in the Preston River catchment slope northeast and east (Figure 2). Surface flow is only likely to occur during intense rainfall events. Any surface flow leaving the extraction areas of Lot 287 does so across the western boundary into Lot 393, with the exception of the 1.3 ha in the Preston River catchment.

Any surface flow leaving Lot 393 does so across the western boundary adjacent to Morris Road. On the northern half of Lot 393, Morris Road has shallow open drains that direct runoff under the road and into the adjacent property through 300-mm culverts (Figure 2). This property contains the completed Gwindinup North mineral sand mine. The reconstructed landform includes a drainage/sumpland that flows southwest through minor water courses and drains to join Gynudup Brook. On the southern half of the boundary, Morris Road is an unformed dirt road and natural surface flow across the road to the west is possible as no roadside drainage is in place.


On Lot 287, any water leaving the extraction area that is located within the Preston River Catchment will drain toward the eastern property boundary, which adjoins the South Western Highway Road reserve — approximately 300 m from the extraction area. Any natural runoff from the eastern portion of Lot 287 (within Preston River catchment) also drains this way. Any flow leaving the property will be intercepted by the highway's drainage infrastructure, where it would mix with road and railway runoff that flows toward the Preston River, a further 200 m to the east.

The Gynudup Brook catchment downstream of the project site is almost entirely cleared agricultural land. Land use is primarily beef and dairy grazing. The hydrology of the catchment has been extensively modified as a result of agriculture and includes many artificial drains constructed to alleviate water logging. The Elgin Main Drain, located 12 km downstream of the project area, diverts all flow in Gynudup Brook at that point.

Nutrient concentrations in Gynudup Brook are elevated due to poor soils and agricultural land use. It is categorised as a 'recovery waterway' in the Revitalising Geographe Waterways initiative as nutrient concentrations do not meet water quality targets (DWER/DPIRD 2018).

The Preston River catchment is 1,136 km² with headwaters 80 km inland in the Darling Range and flows to Leschenault Estuary at Vittoria Bay near Bunbury. The hydrology is significantly altered via river straightening near the Bunbury township and a water supply dam (Glen Mervyn Dam). The Lower Preston catchment is about two thirds cleared. The catchment contains multiple sources of nutrient pollution including urban areas, beef and dairy grazing, abattoirs, Dardanup wastewater treatment plant, and septic tanks (DWER/DPIRD 2024).





2.2 RAINFALL AND CLIMATE

The properties experience warm summers and cold winters with a winter dominant rainfall pattern (BoM 2016a). Mean annual rainfall recorded by the Bureau of Meteorology (BoM) at Donnybrook (9 km southeast of Lot 393) is 970.4 mm (BoM 2024).

Rainfall Intensity Frequency Duration (IFD) data for the project site from the BoM is shown in Table 1. This data is from the 2016 revision of design rainfalls by BoM (BoM 2016b).

Table 1: Rainfall Intensity Frequency Duration Data for Lot 393 and Lot 287

Duration		Annual Exceedance Probability				
Duration	50%	20%	10%	5%	2%	1%
1-h	19.9	25.8	30.0	34.5	40.8	46.0
2-h	25.4	32.8	38.3	44.0	52.2	58.9
3-h	29.3	37.9	44.3	51.0	60.6	68.6
6-h	37.5	48.7	57.2	66.1	78.8	89.4
12-h	47.7	62.1	73.0	84.5	101.0	115.0
24-h	59.6	77.2	90.3	104.0	124.0	141.0
48-h	73.2	93.0	107.0	122.0	144.0	161.0
72-h	82.5	103.0	118.0	132.0	153.0	170.0
96-h	90.5	112.0	126.0	140.0	161.0	177.0
120-h	98.1	120.0	134.0	148.0	168.0	183.0
144-h	106.0	128.0	142.0	156.0	175.0	190.0

Source: Bureau of Meteorology (BoM 2016b)

2.3 RUNOFF COEFFICIENT AND CATCHMENT YIELD

Over the various revisions of this SMP, guidance regarding runoff estimation methods has changed and therefore the runoff estimates have varied. This SMP Rev7 follows guidance provided in the revised Water Quality Protection Note No. 15 Basic Raw Materials Extraction (DWER 2019). This specifies that for calculation of runoff from the 10% AEP 2-hour rainfall event, a minimum runoff coefficient of 0.1 should be adopted for sand pit floors and 0.8 for gravel pits.

The soil profile in the extraction areas at both Lots 287 and 393 is sand over gravel, with material of higher clay content underneath. Majority of the sand and gravel will be removed by the planned excavation, with some sandy topsoil and overburden returned as part of rehabilitation. Based on this and supported by observations of high runoff from excavated areas in August 2022, the gravel pit coefficient has now been adopted for revised pond designs for the active and completed pit areas.

All calculations are provided in Appendix 1 and Appendix 2.

2.4 PEAK FLOW

Peak flows were estimated for a 1% AEP event for spillway design and drain capacity using the empirical rational method for the cleared catchment and using the Regional Flood Frequency Estimation (RFFE) model of the current edition of Australian Rainfall and Runoff (Ball et al. 2019) for rehabilitated or natural catchments. For the empirical method, a runoff coefficient of 0.54 was adopted based on a rolling catchment with bare ground in line with methods



in Carey et al. (2015). The time of concentration was calculated based on Horton's n of 0.275 (bare ground) (Carey et al. 2015).

Calculated flows are given in Table 2. All calculations are provided in Appendix 1 and Appendix 2.

Table 2: Calculated 1% AEP Peak Flows

Catchment	Area (ha)	1% AEP flow (m ³ /s)	Method
Upstream Catchment	31.9	0.25	RFFE
Lot 287 EIL Stages 1–19 (west)	32.9	4.5	Empirical Rational
Lot 287 Stage 20 (northeast)	1.8	0.3	Empirical Rational
Lot 287 Stage 21 (southeast)	0.5	0.1	Empirical Rational
Lot 393 Stages 1 and 2 combined.	3.2	0.53	Empirical Rational
Lot 393 Stage 3 and Lot 287 Stage 8 combined	2.9	0.53	Empirical Rational
Lot 393 Individual Stages (4 – 18)	2 (maximum)	0.41	Empirical Rational
Lot 393 Complete Excavation (bare ground)	31.4	4.20	Empirical Rational
Lot 393 Complete Excavation (rehabilitated)	31.4	0.26	RFFE



3. STORMWATER MANAGEMENT

3.1 OPERATIONAL CONTEXT

As described in the DA/EIL applications, extraction in Lot 393 is being carried out in 18 stages of approximately 2 ha each, commencing at the southern (upstream) end of the site and gradually moving north. Stages 1 and 2, and most of stages 4 and 5 have had extraction activities completed and rehabilitation works are underway. Operations are currently active in stages 6 to 9, including crushing and screening plant, material stockpiles, access track and turnaround area. Rehabilitation of these stages has commenced where possible, particularly along eastern batter slopes. Stage 3, at the common boundary of the properties, was cleared together with Stage 8 of Lot 287 and remains partly open to facilitate access to both properties. Going forward, extraction will proceed stage by stage, with a new stage commencing as an open stage is rehabilitated (landform reinstated, topsoil returned). Each stage will be excavated to full depth before commencement of the next stage of extraction.

Extraction in Lot 287 is being carried out in 21 stages, with each stage a maximum 2 ha in size, commencing at the western end of the property. At the time of writing of this plan, stages 1 to 11 have been excavated and are undergoing rehabilitation. Stages 12 to 21 are an extension to the previously approved pit and subject to a current DA/EIL application. Extraction is proposed to proceed stage by stage, with a new stage commencing as an open stage is rehabilitated (landform reinstated, topsoil returned).

3.2 DIVERSION BANKS

To divert 'clean' runoff from upstream catchments around the active extraction area, diversion banks will be constructed along sections of the eastern boundary of the Lot 393 extraction area and the southern boundary of the Lot 287 extraction area, with indicative alignments shown in Figure 2. Stage 3 of Lot 393 and Stage 8 of Lot 287 were developed together to connect the extraction area between the two properties and therefore no diversion banks are necessary along this section of property boundary. An additional diversion bank will be constructed along the northeast boundary of Lot 287 to prevent runoff from exiting the northern boundary (in line with pre-existing drainage management), instead diverting it to the eastern boundary (Figure 2).

Banks are to be constructed to the following specifications:

- Only clean material that is free of roots, stumps, or debris to be used.
- Minimum crest width 0.5 m.
- Maximum bank grade 2:1 (horizontal to vertical).
- Minimum height 0.5 m.
- Aligned to ensure positive drainage.
- Runoff discharges downstream of active stage.

As the purpose of the diversion banks is to divert clean water from active extraction areas, the diversion banks will be removed when rehabilitation earthworks on the adjacent stage are completed. A maximum of two stages (250 m) in Lot 393 are expected to require diversion banks in place at any time. Diversion banks are not required on the south, west, or north sides of the Lot 393 extraction area as on those sides the natural topography of the site will result in no substantial surface flow into the extraction area. The diversion bund on the northeast boundary of Lot 287 will be kept permanently as it will support the pre-existing drainage arrangements along this boundary.

Maximum flood flow for the entire upstream catchment of the excavation area for a 1 % AEP flood event is $0.25 \, \text{m}^3/\text{s}$. This corresponds to a flow depth of $0.16 \, \text{m}$ at the diversion bund, providing $0.34 \, \text{m}$ freeboard. Since the flow diversion banks are split along the eastern boundary, they will not intercept runoff from the entire upstream catchment and peak flows experienced at the banks will be less than half the whole catchment flow. Flow calculations are provided in Appendix 1 and Appendix 2.



3.3 RETENTION PONDS AND CATCH DRAINS

On Lot 287, a major retention pond has been constructed in the northwest part of the extraction area (mainly stages 4 and 6), where extraction has already been completed. This pond has capacity to provide retention for runoff from the other west draining stages on Lot 287. Two smaller ponds are required in the future at the downstream edges of stages 20 and 21, as these stages drain eastwards away from the major retention pond. These two stages have separate catchments from the rest of the extraction area on Lot 287 and do not receive runoff from any other stages. Some minor runoff from the western edges of Lot 287 will enter stage 3 of Lot 393 and so, in this case, the pond catchments do not precisely match the stage areas. Further information on retention pond specifications is provided in Appendix 2 and Section 3.3.1.

As extraction on Lot 393 commenced at the upstream (southern end) of the site, the approach to stormwater management is different to Lot 287. As presented in the previous revisions of the SMP, the initial calculations based on extraction to the maximum approved depth indicated that the resulting pit landform on Lot 393 would have sufficient water storage capacity to provide the required runoff retention. Additional retention was only expected to be required temporarily in the active stages that had not yet reached the final depth. However, extraction to August 2022 indicated that sand and gravel resource is not consistently present to the full approved depth of the pit, resulting in a shallower final pit depth that has insufficient capacity for runoff retention. Therefore, the stormwater management measures have been revised to increase runoff retention.


A large retention pond will be used to capture runoff from most of stages 1 to 9 (excluding stage 3) totalling approximately 15 ha. This pond is currently in stage 9, however the location may be adjusted as part of rehabilitation once the active operational areas move further north. This pond could be removed completely in the future if sufficient containment is installed downstream. Details of the retention volume and spillway size for this catchment are provided in Appendix 1 and Section 3.3.1.

For the remaining stages 10 to 18 on Lot 393, small ponds will be constructed gradually for each stage as the stage is commenced. Approximately 2-m depth containment ponds will need to be retained at each stage or alternatively, these ponds can be removed if downstream ponds are constructed to a larger size able to contain the runoff from upstream stages. The construction of small ponds for each stage could be avoided all together by constructing a large retention pond in the northwest (downstream) corner of the extraction area prior to proceeding with further stages. This option has been tentatively shown in Figure 2 in addition to the option of smaller ponds for each stage.

Catch drains will be constructed on the downstream boundaries of each stage to direct runoff to the corresponding retention pond (Figure 2). Stripping of topsoil and the removal of overburden at the time of clearing (and stockpiling this material on the downstream side, as described in the EIL application) will be sufficient to direct any runoff reaching the boundary of a stage into the retention pond.

Figure 2 shows the locations of stormwater management measures.





3.3.1 Retention Pond Specification

Retention ponds are to be constructed with sufficient capacity to retain the 10% AEP 2-hour duration runoff volume from the upstream cleared area, assuming a runoff coefficient of 80%. Table 3 presents the required capacity for each retention pond. Details of calculations are provided in Appendix 1. The storage requirements can be met by constructing a 600 m³ capacity pond for each stage except Lot 287 Stages 20 and 21 (which require 260 m³ and 140 m³) and the major retention pond for Lot 287, which requires 10,400 m³. As the retention ponds are to be created by excavation of the natural surface, there is no embankment subject to failure due to overtopping and no requirement to maintain freeboard.

Lot 393 Stages 1 to 9 (excluding 3)are now directed to a retention pond in stage 9. This has an estimated capacity of 6,000 m³ to a full level of 61.5 m Australian Height Datum (mAHD). This is sufficient capacity for the upstream catchment of the pond, comprising most of Stages 1 to 9 (15 ha), which has a required containment volume of 4,596 m³. If retained, as this pond is constructed above-ground it will need freeboard to be maintained to avoid overtopping and potential wall failure. A spillway will be required to achieve this and should be constructed in natural ground to the east of the embankment at least 0.5 m below the minimum crest level of the embankment. The embankment should be constructed from selected material placed and compacted in controlled layers.

Table 3:	Runoff Capacity	Required for	Retention	Ponds

Lot	Stage	Area (ha)	10% AEP 2 hour Runoff Volume (m³)
	1#	1.5	459.6
	2#	1.7	520.9
	3*	2.9	888.6
	4#	1.7	520.9
	5#	2.0	612.8
	6#	1.8	551.5
	7#	2.0	612.8
	8#	1.8	551.5
	9#	2.0	612.8
L at 202	10	1.8	551.5
Lot 393	11	1.9	582.2
	12	1.8	551.5
	13	1.9	582.2
	14	1.8	551.5
	15	1.9	582.2
	16	1.0	306.4
	17	1.0	306.4
	18	2.0	612.8
	Total to Stage 9#	15.0	4,596
	Total 1 to18	31.5	9,958
	1 to 19*	32.5	9,970
L at 207	20	0.8	257
Lot 287	21	0.5	139
	Total 1 to21	33.8	10,367

^{*} Stage 3 Lot 393 and stage 8 Lot 287 adjusted as some runoff flows between them.



[#] Stages 1 to 9 excluding Stage 3 directed to combined retention pond as of 2023.

Ponds other than the existing Lot 287 pond and Lot 393 Stage 9 pond are to be constructed to the following specification:

- Pond to be excavated below the natural surface.
- The downstream side of the pond to be constructed along the natural contour for a distance of at least 4 m to provide a level spreader discharge spillway in event of overtopping.
- Side slopes to be no steeper than 2:1 (horizontal to vertical).

Recommended pond depth is 2 m below surface, which will result in the pond dimensions shown in Figure 2, but deeper or shallower ponds are acceptable provided the specifications for containment volume and spillway are met. The designs shown in Figure 2 achieve the specification for ponds that are 2 m deep, with a spillway of 20-m length, and floor length of 18 m (20 m for stage 3).

As removal of product during excavation will result in a lowering of the surface level surrounding the retention ponds in the eastern stages of Lot 393, the ponds will need to either be excavated initially to a greater depth to allow for this, or deepened once excavation of the adjoining stage to the west commences. Alternatively, as described in Section 3.3, these small ponds can be removed or not constructed at all, if other sufficiently large containment is available downstream within the extraction area.

An effective level spreader spillway for the retention ponds is provided by the construction of the downstream edge on contour for a minimum length of 4 m. The 1% AEP flood flow is 0.53 m³/s for the largest catchment (Lot 393 Stage 3). Calculated flow depth for the minimum level spillway length of 4 m at this flow is 0.061 m. As the ponds are excavated, there is no possibility of embankment failure due to spillway erosion (see Appendix 1).

A schematic cross section of a retention pond meeting the specification is shown in Figure 3.




Figure 3: Retention Pond Design Cross-section

The main retention pond on Lot 287 was constructed during 2023 (Figure 4). This was constructed by a combination of excavation and building up of a downstream wall and provides retention volume for Stages 1 to 19 of Lot 287. The pond has a storage volume to full level (69 mAHD) of approximately 10,000 m³ with 1 m freeboard. This is sufficient to contain the design runoff for a 10% AEP 2-hour rainfall event, which is 9,970 kL (Table 3). This volume has been calculated based on DWER guidance for bare ground pit floors (Appendix 2). Actual runoff is expected to be much lower considering rehabilitation works will be completed progressively as extraction activity progresses. Furthermore, extraction activities have already been completed for Stages 1 to 11. The pond spillway is a channel



STORMWATER MANAGEMENT PLAN

cut into natural ground to the south of the dam wall, maintaining separation between overflows and the dam wall to avoid risk of wall failure during overflow. This spillway needs to pass a 1% AEP flood peak flow of 4.5 m 3 /s with a maximum flow depth of 0.5 m.

The access track from Lowrie Road to Lots 393 and 287 currently runs immediately downstream (west) of the major retention pond. The access track includes drains and a culvert, which will act to concentrate any overflow from the pond. In order to manage and diffuse these flows, outflow from the culvert is directed to the retention pond in Lot 393 Stage 3, which, via a drain and spreader bunds, will discharge across the undisturbed pasture of Lot 393. The drain and spreader bunds will be moved as extraction on Lot 393 progresses to ensure discharge is not directed into active stages. Discharge will eventually move to completed areas once contour bunds are installed and vegetation reestablished.






Figure 4: Major Retention Pond Lot 287



3.3.2 Catch Drain Specifications

Catch drains are to be constructed to the following specifications on each stage in Lot 393:

- Drains to follow the downstream external boundary of the stage (slope 3% to 4%, up to 20 m inside the boundary once final excavation is completed, as shown in Figure 2).
- Drains are to be constructed by excavation with side slopes no steeper than 2:1 (horizontal to vertical).
- Drains to have a constant fall from south to north.
- Drains to discharge into retention ponds.
- Drains to have capacity to transfer the 1% AEP peak flow from the adjacent stage with 150 mm freeboard.

The 1% AEP peak flow for the largest stage (stage 3: 0.53 m³/s) (Appendix 1). Either of the two options below for drain dimensions will satisfy the capacity requirements for all stages.

- V drain 500 mm depth below the natural ground surface with 2:1 (horizontal to vertical) side slopes (Figure 5).
- Additional stripping with removal of a minimum 350 mm overburden for at least 4 m to the east, with 2:1 (horizontal to vertical) side slope on the west side (Figure 6).




Figure 5: Catch Drain Design Cross-section — V Drain






Figure 6: Catch Drain Design Cross-section — Additional Stripping

3.4 CONTOUR BANKS

To further manage runoff, increase infiltration, and reduce sediment movement post extraction, contour banks are to be constructed along the final landform contour at 100-m intervals. These are to be constructed during post mining rehabilitation works for each stage after completion of extraction.

Contour banks are to be constructed to the following specifications:

- Only clean material that is free of roots, stumps, or debris to be used.
- Minimum crest width 0.5 m.
- Maximum bank grade 2:1 (horizontal to vertical).
- Minimum height 0.5 m.
- Aligned on the contour of the final landform.
- Joined to the final pit batters at each end.

Rehabilitation works for each stage will also include ripping along the contour to remove soil compaction and improve runoff infiltration and root penetration. Topsoil will be respread following ripping and vegetation established as described in the rehabilitation and decommissioning programs and the native vegetation rehabilitation plans for the properties.



4. MONITORING AND MAINTENANCE

All full inspection of stormwater management structures will be undertaken ahead of the commencement of seasonal autumn/winter rains and ahead of forecasted major out-of-season rainfall (e.g. summer rainfall due to cyclone activity). The purpose of these inspections is to check that everything is operational and to undertake maintenance as need be.

Catch drains and retention ponds will be inspected weekly during operations and within 24 hours after any runoff-producing rainfall events. Any slumps, bank damage, or loss of freeboard that would interfere with performance will be repaired to specification. Any fill material or sediment blocking the drain will be removed.

Following the occurrence of a rainfall event greater than the 10% AEP 2-hour duration (38.3 mm) or in the event of sediment laden runoff leaving the properties, a report will be made within 48 hours to the Shire of Capel detailing impacts and remediation actions (if any necessary).



5. ROLES AND RESPONSIBILITIES

Roles and responsibilities with respect to stormwater management are outline in Table 4.

Table 4: Roles and Responsibilities

Role	Responsibilities
EIL Licensee	 Responsible for overall implementation of this plan. Will provide information for site personnel on stormwater management objectives and measures to be undertaken on site. Responsible for reporting to Shire of Capel.
All personnel	 Will be familiar with stormwater management objectives. Will implement stormwater management measures as outlined in this plan. Responsible for reporting stormwater management issues to EIL Licensee.



6. REFERENCES

Ball J, Babister M, Nathan R, Weeks W, Weinmann E, Retallick M, Testoni I, (Editors). 2019. *Australian Rainfall and Runoff: A Guide to Flood Estimation*. Commonwealth of Australia. Accessed January 2024. https://arr.ga.gov.au/

Bureau of Meteorology (BoM). 2016a. *Climate classification maps*. Accessed January 2024. http://www.bom.gov.au/jsp/ncc/climate_averages/climate-classifications/index.jsp

Bureau of Meteorology (BoM). 2016b. *Design Rainfall Data System (2016)*. Accessed January 2024. http://www.bom.gov.au/water/designRainfalls/revised-ifd/

Bureau of Meteorology (BOM). 2024. *Climate Statistics for Australian Locations*. Donnybrook Meteorological Station 9534. Accessed January 2024.

http://www.bom.gov.au/climate/averages/tables/cw_009534.shtml

Carey, B.W., Stone, B., Norman, P.L., and Shilton, P. 2015. *Soil Conservation Guidelines for Queensland*. Department of Science, Information Technology and Innovation, Brisbane. Accessed January 2024. https://nla.gov.au/nla.obj-2742578827/view

Department of Water and Environmental Regulation / Department of Primary Industries and Regional Development (DWER/DPIRD). 2018. *Gynudup Brook*. Revitalising Geographe Waterways. Accessed January 2024. https://rgw.dwer.wa.gov.au/geographe-waterways/gynudup-brook/.

Department of Water and Environmental Regulation (DWER). 2019. *Water Quality Protection Note No. 15 Basic Raw Material Extraction*. July 2019 (Plain English version, February 2021). Accessed January 2024. https://www.wa.gov.au/system/files/2022-06/WQPN-15-Basic-raw-materials-extraction.pdf

Department of Water and Environmental Regulation / Department of Primary Industries and Regional Development (DWER/DPIRD). 2024. *Lower Preston Catchment*. Healthy Estuaries WA. Accessed January 2024. https://estuaries.dwer.wa.gov.au/catchment/leschenault/lower-preston/



STORMWATER MANAGEMENT PLAN


APPENDICES



STORMWATER MANAGEMENT PLAN

APPENDIX 1: HYDROLOGICAL CALCULATIONS — LOT 393 LOWRIE ROAD





A1.2 Peak Flow Estimates for Vegetated Catchments (RFFE Method)

Peak Flow Estimate for Extraction Area (Stages 1 to 17) Lot 393 Lowrie Road

Results from ARR RFFE Model

https://rffe.arr-software.org/

Regional Flood Frequency Estimation Model for the 4th Edition of Australian Rainfall and Runoff

Input Data

Datetime: 2019-03-27 15:18 Region name: SW WA Region code: 5

Site name: 393 Lowrie St 1-18

Latitude at catchment outlet (degree) = -33.5143 Longitude at catchment outlet (degree) = 115.731 Latitude at catchment centroid (degree) = -33.5193 Longitude at catchment centroid (degree) = 115.733

Distance of the nearest gauged catchment in the database (km) = 3.82

Catchment area (sq km) = 0.314


Design rainfall intensity, 1 in 2 AEP and 6 hr duration (mm/h): 6.248338 Design rainfall intensity, 1 in 50 AEP and 6 hr duration (mm/h): 13.147148

Shape factor of the ungauged catchment: 1.05

Catchment Location



Results



*The catchment is outside the recommended catchment size of 0.5 to 1,000 km². Results have lower accuracy and may not be directly applicable in practice.

AEP (%)	Discharge		Upper Confidence
	(m ³ /s)	Limit (5%) (m ³ /s)	Limit (95%) (m ³ /s)
50	0.04	0.01	0.16
20	0.07	0.02	0.28
10	0.11	0.02	0.42
5	0.14	0.04	0.62
2	0.2	0.04	1.01
1	0.26	0.05	1.43

Peak Flow Estimate for Upstream Catchment of Lot 393 Lowrie Road

Results from ARR RFFE Model

https://rffe.arr-software.org/

Regional Flood Frequency Estimation Model for the 4th Edition of Australian Rainfall and Runoff

Input Data

Datetime: 2021-02-11 18:55 Region name: SW WA Region code: 5

Site name: Gwindinup Upstream Diversion
Latitude at catchment outlet (degree) = -33.5203
Longitude at catchment outlet (degree) = 115.7345
Latitude at catchment centroid (degree) = -33.5221
Longitude at catchment centroid (degree) = 115.7378

Distance of the nearest gauged catchment in the database (km) = 4.5


Catchment area (sq km) = 0.319

Design rainfall intensity, 1 in 2 AEP and 6 hr duration (mm/h): 6.248338 Design rainfall intensity, 1 in 50 AEP and 6 hr duration (mm/h): 13.147148

Shape factor of the ungauged catchment: 0.65



Results



AEP (%)	Discharge		Upper Confidence
	(m ³ /s)	Limit (5%) (m ³ /s)	Limit (95%) (m ³ /s)
50	0.04	0.01	0.16
20	0.07	0.02	0.28
10	0.11	0.03	0.42
5	0.15	0.04	0.62
2	0.2	0.04	1
1	0.25	0.05	1.42

A1.2 Peak Flow Estimate for Bare Catchments (Empirical Rational Method)

Calculation methods from Soil Conservation Guidelines for Queensland, Ch4 Empirical Version of Rational Method

The Rational Method design equation is:

QY=0.278*Cy*ltc,_Y*A

C10 based on catchment characteristics

Slope	5.7% (Rolling - 2 to 10%)
Permeability	High
Condition	3 (Bare)
C ₁₀	0.3

Rational Method Frequency Factors (C_Y /C₁₀):

ARI (years)	2	5	10	20	50	100
Frequency Factor	0.6	0.8	1	1.2	1.5	1.8

Calculations and Results
Complete Excavation Area (bare ground)

Horton n	0.0275	(bare surface)
Total Distance	1019	
Overland	390	
Drain	700	
t overland		minutes
t channel (1m/s)	11.7	minutes
t _c	26.8	minutes
t _c	0.45	hr
A	0.314	km ²
C ₁₀	0.300	

(Rainfall intensity based on ARR 2016)

Average Recurrence Interval (years)		100
Annual Exceedance Probability		1%
Coefficient	C _Y	0.54
Time of Conc rainfall intensity	Itc	89.33
Peak Discharge (Rational)	$Q_v (m^3/s)$	4.2

Stage 9 Large Pond (as constructed)

To a second		۱
Horton n	0.0275	(bare surface)
Total Distance	570	
Overland	570	
Drain	0	
t overland	17.2	minutes
t channel (1m/s)	0.0	minutes
t_c	17.2	minutes
t _c	0.29	hr
A	0.150	km ²
C ₁₀	0.300	

(Rainfall intensity based on ARR 2016)

Average Recurrence Interval (years)		100
Annual Exceedance Probabilit	1%	
Coefficient	C _Y	0.54
Time of Conc rainfall intensity	Itc	105.00
Peak Discharge (Rational)	$Q_Y (m^3/s)$	2.4

Stage 1 & 2 and 3 (bare ground)

Horton n	0.0275	bare surface	
		bare surface	
Total Distance	268		
Overland	268		
Drain	0		
t overland	13.3		
t channel (1m/s)	0.0		
t _c	13.3	minutes	
t _c	0.25	hr	
A	0.032	km ²	
C ₁₀	0.300		
(Rainfall intensity based on ARR 2016)			

(rounded to 15min)

Average Recurrence Interval (years)		10	100
Annual Exceedance Probability		10%	1%
Coefficient	C _Y	0.30	0.54
Time of Conc rainfall intensity	Itc	72.00	110.80
Peak Discharge	$Q_Y (m^3/s)$	0.19	0.53

Individual Stages (4 to 18)

Horton n	0.0275	bare surface	
Total Distance	179		
Overland	179		
Drain	0		
t overland	11.7		
t channel (1m/s)	0.0		
t _c	11.7	minutes	
t _c	0.25	hr	
A	0.020	km ²	
C ₁₀	0.300		
(Rainfall intensity based on ARR 2016)			

(rounded to 15min)

Average Recurrence Interval (y	10	100	
Annual Exceedance Probability		10%	1%
Coefficient	C _Y	0.30	0.54
Time of Conc rainfall intensity	Itc	90.00	138.00
Peak Discharge	$Q_{\rm Y}$ (m ³ /s)	0.15	0.41

L287 Complete Excavation Area (bare ground)

Horton n	0.0275	(bare surface)
Total Distance	500	
Overland	500	
Drain	0	
t overland	16.4	minutes
t channel (1m/s)	0.0	minutes
t _c	16.4	minutes
t _c	0.27	hr
A	0.184	km ²
C ₁₀	0.300	
/Datafall takensthell	I ADD 201	/\

(Rainfall intensity based on ARR 2016)

Average Recurrence Interval (100	
Annual Exceedance Probabilit	1%	
Coefficient	C _Y	0.54
Time of Conc rainfall intensity	Itc	110.80
Peak Discharge (Rational)	$Q_V (m^3/s)$	3.1

A1.3 Runoff Capacity Required for Retention Ponds

Runoff volume calculation for 10% AEP 2 hour duration event from bare ground for retention pond capacity.

Runoff based on WQPN 15 (DWER 2019) coefficient for gravel pits

Ī	P (mm)	38.3	10% AEP, 2 hour rainfall (mm
ſ	Runoff Coefficient	0.80	
ſ	Runoff (mm)	30.6	

Runoff Volume for Catchments

Stage	Area (ha)	Runoff	Runoff Volume
J	` ,	(mm)	(m ³)
1	1.5	30.6	459.6
2	1.7	30.6	520.9
3*	2.9	30.6	888.6
4	1.7	30.6	520.9
5	2.0	30.6	612.8
6	1.8	30.6	551.5
7	2.0	30.6	612.8
8	1.8	30.6	551.5
9	2.0	30.6	612.8
10	1.8	30.6	551.5
11	1.9	30.6	582.2
12	1.8	30.6	551.5
13	1.9	30.6	582.2
14	1.8	30.6	551.5
15	1.9	30.6	582.2
16	1.0	30.6	306.4
17	1.0	30.6	306.4
18	2.0	30.6	612.8
Total 1 to18	32.5	30.6	9958.0
Stage 9 Large Pond**	15.0	30.6	4596.0

^{*3} includes some runoff from L287 Stage 8
** includes most of stages 1 to 9, excluding 3

A1.4 Hydraulic Flow Depth Calculations

Flood Levels for Peak Flows were estimated using Manning's Equation for an irregular channel. Calculations were done with the HY-8 hydraulic analysis package version 7.6 (US Federal Highway Administration, 2019).

Diversion Banks

Channel bank 2:1 downstream, 20:1 upstream. Slope 3.00% Slope 3.00% 0.03 m/m Mannings n of 0.035 was used for the channel (natural channel, irregular, rough).

Channel Cross Section Definition

No.		Dist	Elevation	Mannings n
	1	0	1	0.02
	2	2	0	0.02
	3	22	1	0.02

Hy-8 Output

AEP	Flow (m ³ /s)	Elevation (m)	depth(m)	velocity (m/s)	shear (pa)
1%	0.25	0.16	0.16	0.948	49.881

Temporary Retention Pond Spillway

4m wide level spillway on natural terrain

Slope 5.00% Mannings n of 0.02 was used (earth,uniform clean). 5.00% 0.05 m/m

Channel Cross Section Definition

No.	Dist	Elevation	Mannings n	
1	0	0.3	0.02	
2	10	0	0.02	
3	14	0	0.02	
4	24	0.3	0.02	

Hy-8 Output

AEP	Flow (m ³ /s)	Elevation (m)	depth(m)	velocity (m/s)	shear (pa)
1%	0.53	0.06	0.06	1.431	30.037

Catch Drain (V drain)

Channel bank 2:1 downstream and upstream. 5.00% Slope 5.00% Mannings n of 0.02 was used (earth,uniform clean).

0.05 m/m

Hy-8 Output

AEP	Flow (m ³ /s)	Elevation (m)	depth(m)	velocity (m/s)	shear (pa)
1%	0.53	0.33	0.33	2.422	97.264

Catch Drain (Additional Excavation)

Channel bank 2:1 downstream, 20:1 upstream. 3.00% Slope 3.00% Mannings n of 0.02 was used (earth,uniform clean). 0.03 m/m

Channel Cross Section Definition

0110111101 01000 00	Charmer Greek Geottern Bermittern					
No.		Dist	Elevation	Mannings n		
	1	0	1	0.02		
	2	2	0	0.02		
	3	20	1	0.02		

Hy-8 Output

AEP	Flow (m ³ /s)	Elevation (m)	depth(m)	velocity (m/s)	shear (pa)
1%	0.53	0.18	0.18	1.702	51.897

Final Excavation Spillway

45m wide level spillway on natural terrain

5.00% 0.05 m/m

Slope 5.00% Mannings n of 0.02 was used (earth,uniform clean).

Channel Cross Section Definition

No.	Dist	Elevation	Mannings n
1	0	49	0.02
2	8.5	48	0.02
3	53.5	48	0.02
4	78	49	0.02

Hy-8 Output

rry o Output					
Flow	Flow (m ³ /s)	Elevation (m)	depth(m)	velocity (m/s)	shear (pa)
1% AEP, Lot 393 only	4.20	48.06	0.06	1.622	27.63
1% AFP, Lot 393 and Lot 287	8 70	48 09	0.09	2 15	42 67

Stage 9 Large Pond Spillway

Trapezoidal drain on natural terrain

Slope 3.00% Mannings n of 0.02 was used (earth,uniform clean). 3.00% 0.03 m/m

Channel Type:	Trapezoidal
Bottom Width:	2
Side Slope (H:V):	2.0:1

Hy-8 Output


Flow	Flow (m ³ /s)	Elevation (m)	depth(m)	velocity (m/s)	shear (pa)
1% AEP, Stage 9 large pond	4.20	48.06	0.40	3.815	116

STORMWATER MANAGEMENT PLAN

APPENDIX 2: HYDROLOGICAL CALCULATIONS — LOT 287 SOUTHWESTERN HIGHWAY



A2.1 Project Site Location and Catchments



A2.2 Peak Flow Estimate for Bare Catchments (Empirical Rational Method)

Methods

Calculation methods from Soil Conservation Guidelines for Queensland, Ch4 Empirical Version of Rational Method The Rational Method design equation is:

 $QY{=}0.278^{*}Cy^{*}Itc_{,Y}{^{*}}A$

C10 based on catchment characteristics

O TO BUCCU OTT GUICETTION CONGRE	0.0.0.00
Slope	5.7% (Rolling - 2 to 10%)
Permeability	High
Condition	3 (Bare)
C ₁₀	0.3

Rational Method Frequency Factors (C_Y /C₁₀):

ARI (years)	2	5	10	20	50	100
Frequency Factor	0.6	0.8	1	1.2	1.5	1.8

Calculations and Results L287 Excavation Area (bare ground)

	Main Pit	Stage 21	Stage 22
Horton n	0.0275	0.0275	0.0275
Total Distance (m)	980	300	100
Overland (m)	980	300	100
Drain (m)	0	0	0
t overland (min)	20.6	13.9	9.6
t channel (min)	0.0	0.0	0.0
t _c (min)	20.6	13.9	9.6
t_c (hr)	0.34	0.23	0.16
A (km ²)	0.326	0.018	0.005
C ₁₀	0.300	0.300	0.300

(Rainfall intensity based on ARR 2016)

Average Recurrence Interval (years)		100	100	100
Annual Exceedance Probabilit	у	1%	1%	1%
Coefficient	C _Y	0.54	0.54	0.54
Time of Conc rainfall intensity	Itc	91.60	110.80	138.00
Peak Discharge (Rational)	$Q_Y (m^3/s)$	4.5	0.3	0.1

A2.3 Runoff Capacity Required for Retention Ponds in L287

Runoff volume calculation for 10% AEP 2 hour duration event from bare ground for retention pond capacity.

Runoff based on WQPN 15 (DWER 2019) coefficient for gravel pits

P (mm)	38.3	10% AEP, 2 hour rainfall (mm)
Runoff Coefficient	0.80	
Runoff (mm)	30.6	

Runoff Volume

Stage	Area (ha)	Runoff	Runoff Volume
		(mm)	(m ³)
Stages 1 to 19 (draining west to main pond)	32.5	30.6	9,970
Stage 20 (NE Pond)	0.8	30.6	257
Stage 21 (SE Pond)	0.5	30.6	139
Total	33.8	30.6	10,367

A2.4 Hydraulic Flow Depth Calculations

Flood Levels for Peak Flows were estimated using Manning's Equation for an irregular channel. Calculations were done with the HY-8 hydraulic analysis package version 7.6 (US Federal Highway Administration, 2019).

Permanent Retention Pond Spillway

Trapezoidal drain on natural terrain

Slope 3.00 Mannings n of 0.02 was used (earth,uniform clean). 3.00% 0.03 m/m

Channel Type:	Trapezoidal
Bottom Width:	2
Side Slope (H:V):	2.0:1

Hy-8 Output

Flow	Flow (m ³ /s)	Elevation (m)	depth(m)	velocity (m/s)	shear (pa)
1% AEP, Lot 287	4.50	69.51	0.51	3.44	150.35

APPENDIX 9: DUST MANAGEMENT PLAN



LOT 287 SOUTH WESTERN HWY, GWINDINUP DUST MANAGEMENT PLAN

PREPARED FOR:

MARIO MICHELE GIACCI

MARCH 2024

PREPARED BY:

Martinick Bosch Sell Pty Ltd 4 Cook Street

Ph: (08) 9226 3166

Email: <u>info@mbsenvironmental.com.au</u>
Web: <u>www.mbsenvironmental.com.au</u>





environmental and geoscience consultants

LOT 287 SOUTH WESTERN HIGHWAY, GWINDINUP DUST MANAGEMENT PLAN

Distribution List:

Company	Contact name	Copies	Date
MGM Bulk Pty Ltd	Craig Carbone Sales/Business Development	Electronic	8 March 2024

Document Control for Job Number: MGM287EXT

Document Status	Prepared By	Authorised By	Date
Draft Report	Nathan Dunn, Sharon Rose	Kirsi Kauhanen	23 August 2023
Final Report	Sharon Rose	Kirsi Kauhanen	14 September 2023
Final Report	Sharon Rose	Kirsi Kauhanen	8 March 2024

Disclaimer, Confidentiality and Copyright Statement

This report is copyright. Ownership of the copyright remains with Martinick Bosch Sell Pty Ltd (MBS Environmental) and **Mario Michele Giacci**.

This report has been prepared for **Mario Michele Giacci** on the basis of instructions and information provided by **Mario Michele Giacci** and therefore may be subject to qualifications which are not expressed.

No person other than those authorised in the distribution list may use or rely on this report without confirmation in writing from MBS Environmental. MBS Environmental has no liability to any other person who acts or relies upon any information contained in this report without confirmation.

This report has been checked and released for transmittal to Mario Michele Giacci.

These Technical Reports:

- Enjoy copyright protection and the copyright vests in MBS Environmental and Mario Michele Giacci unless otherwise agreed in writing.
- May not be reproduced or transmitted in any form or by any means whatsoever to any person without the written permission of the Copyright holder.



TABLE OF CONTENTS

1.	Introduction	1
1.1 1.2 1.3	PurposeScopeObjective	1
2.	EXISTING ENVIRONMENT	4
2.1 2.2 2.3 2.4 2.5	CLIMATE LAND USE LANDFORM AND SOILS VEGETATION SENSITIVE RECEPTORS	
3.	POTENTIAL SOURCES OF DUST	8
4.	SITE RISK ASSESSMENT	10
5.	DUST MANAGEMENT ACTIONS	11
5.1 5.2 5.3	Dust Prevention Dust Monitoring and Mitigation Dust Complaints	11
6.	Roles and Responsibilities	12
7.	References	13
	TABLES	
Table 1:	Sensitive Receptors within 500 m of Extractive Operations	<i>6</i>
Table 2:	Roles and Responsibilities	12
	FIGURES	
Figure 1:	Location	2
Figure 2:	Existing Contour and Features	3
Figure 3:	Climate Statistics (1900–2023) for BoM Station 9534	4
Figure 4:	Sensitive Receptors	7
Figure 5:	Works and Excavation Plan	9
	APPENDICES	

Appendix 1: Wind Roses

Appendix 2: Risk Assessment

Appendix 3: Dust Complaint Form



1. Introduction

1.1 Purpose

Mario Michele Giacci (the applicant) has an existing Development Approval (DA) and Extractive Industry Licence (EIL) for the extraction of sand and gravel on Lot 287 South Western Highway, Gwindinup (the property) within the Shire of Capel (Figure 1). The applicant is proposing to expand extraction operations on Lot 287 by an additional 15.31 ha in an easterly direction, which requires an updated Dust Management Plan (DMP).

This DMP was prepared in accordance with the Department of Environment and Conservation's (DEC — now Department of Water and Environmental Regulation) "A guideline for managing the impacts of dust and associated contaminants from land development sites, contaminated sites remediation and other related activities" (DEC 2011). This DMP should be read in conjunction with the DA and EIL report.

1.2 SCOPE


The scope of this DMP includes the following:


- Description of the existing environment and identification of sensitive receptors.
- Identification of potential sources of dust associated with the operations.
- Identification of roles and responsibilities.
- A site risk assessment for dust.
- Description of appropriate dust prevention, monitoring, and mitigation measures.
- A dust complaints process.

1.3 OBJECTIVE

The objective of this DMP is to minimise dust emissions generated by sand and gravel extraction operations on Lot 287.







2. EXISTING ENVIRONMENT

2.1 CLIMATE

The climate of the project area is Mediterranean, with cool wet winters and hot dry summers. Bureau of Meteorology (BoM) long-term average climate data for the closest meteorological station (Donnybrook, 9 km southeast of the property) is shown in Figure 3. The average annual rainfall is 970.4 mm, mean minimum temperatures between 5 and 15°C and mean maximum temperatures between 16 and 31°C (BoM 2023).

Long-term wind roses for Donnybrook (BoM 2023) indicate prevailing winds comprise morning easterlies and afternoon westerlies (Appendix 1).




Figure 3: Climate Statistics (1900–2023) for BoM Station 9534

2.2 LAND USE

Lot 287 is located on South Western Highway within the Shire of Capel, approximately 3.5 km south of Boyanup and approximately 26 km southeast of Bunbury (Figure 1). The property covers a total area of 60.01 ha and is zoned Rural under the Shire of Capel Local Planning Scheme (LPS) No.8 and the Greater Bunbury Region Scheme (WA Gov 2014). LPS No.8 maps the property within three Special Control Areas (SCA): SCA4 — Transport Corridors, SCA6 — Strategic Minerals and Basic Raw Materials, and SCA8 — Regional Ecological Linkages (Shire of Capel 2023).

A 'Highway Protection Line' straddles the property along its eastern highway road frontage and delineates an area (100 m distance from either side of the centre line of the road), which is defined as the 'Highway Protection Area'. The purpose of the 'Highway Protection Area' is to protect the function, amenity, and visual character of the Highway. The proposed extraction area is well outside the 'Highway Protection Area'.

The property contains no buildings. In addition to the active extraction area on the western side of the property, Lot 287 contains a blue gum plantation with pockets of remnant native vegetation (Figure 2).



2.3 LANDFORM AND SOILS

The highest point on Lot 287 is situated approximately halfway along the southern property boundary and has an elevation of 111 m Australian Height Datum (mAHD) (Figure 2). From this point, the land to the west and north slopes and undulates downward at gradients between approximately 1:10 and 1:20. Near the northern boundary there are steep areas of approximately 1:6. To the east of the proposed extraction area lies the steepest gradients on the property, which slope towards the South Western Highway at gradients up to 1:6 within the proposed extraction area and 1:4 further east, beyond the proposed EIL boundary line. Within the proposed extraction area, the highest point is 109 mAHD in the south and the lowest point is 78 mAHD in the northeast (Figure 2).

Three soil and landform mapping systems are mapped within and surrounding the proposed extraction area (DPIRD-064):

- Whicher Scarp System: Low scarp and raised platform, on the northern edge of the Donnybrook Sunkland.
 Sandy gravel and pale deep sands, loamy gravel, and non-saline wet soils. Jarrah-marri forest and woodland.
- Goodwood Valleys System: Valleys, of the Donnybrook Sunkland. Sandy gravel, loamy gravel, and deep sand. Jarrah-marri forest and woodland.
- Blackwood Plateau System: Lateritic plateau in the Donnybrook Sunkland. Sandy gravel, loamy gravel, and deep sand. Jarrah-marri forest.

The proposed expansion to the extraction area is mostly located within the Goodwood Valleys System. Extraction on the property so far has shown that there is a layer of sand, of varying depth, that overlies the gravel.

Lot 287 is located away from wetlands and waterways on well-draining soils. The Australian Soil Resource Information System maps the property as 'Extremely Low Probability/Low Confidence' for the risk of acid sulfate soil (CSIRO 2014).

2.4 VEGETATION

Lot 287 contains a mosaic of remnant native vegetation, blue gum plantation, extraction operation, and some cleared land. There is approximately 19 ha of native vegetation, split into several patches. Reconnaissance flora and vegetation survey (Marsh 2019) identified three native vegetation types and an introduced vegetation type in the proposed extraction area:

- VT1: Tall woodland of Eucalyptus marginata and Corymbia calophylla over low woodland of Banksia grandis over tall sparse shrubland of Kunzea glabrescens over low sparse shrubland of Xanthorrhoea preissii.
- VT2: Tall woodland of Eucalyptus marginata and Corymbia calophylla over tall sparse shrubland of Kunzea glabrescens over low sparse shrubland of Xanthorrhoea preissii and Xanthorrhoea gracilis.
- VT3: Tall woodland of Eucalyptus marginata and Corymbia calophylla over low sparse shrubland of Xanthorrhoea preissii and Hibbertia hypericoides.
- D: Disturbed: Blue gum plantations, tracks, and clearings.

The native vegetation communities vary in condition from Degraded to Very Good – Good (using condition scale by Keighery 1994) and show signs of multiple historical disturbances including selective logging, fire, weeds, and *Phytophthora cinnamomi* (dieback). Currently there is disturbance in the form of cleared tracks and small bare areas. The blue gum plantation areas have been completely cleared of native vegetation in the past.

No Threatened or Priority Ecological Communities or Threatened or Priority flora species have been recorded at Lot 287. Several weed species have been recorded but no Declared Pest species or weeds of national significance (Marsh 2019).



2.5 Sensitive Receptors


The land surrounding Lot 287 is zoned either 'Rural', 'State Forest', 'Regional Open Space', or 'Primary Regional Road' (Shire of Capel 2023). They include land uses of sand and gravel extraction, remnant bushland, state forest, and residential dwellings (Figure 4).

The main sensitive receptors in the area are the residential dwellings on other rural properties. The closest receptor is a residential dwelling to the north on Lot 26, located 157 m from the proposed EIL area. Dwellings within 500 m of the extraction area are summarised in Table 1 and shown in Figure 4. It is noted that there is a sand and gravel extraction site on Lot 393 located immediately west of the property.

Table 1: Sensitive Receptors within 500 m of Extractive Operations

Property Details	Distance and Direction from Operations	Type of Receptor
Lot 26 (Plan 143766)	157 m north	Residential dwelling, outbuildings, and a dam
Lot 100 (Plan 44666)	272 m northeast	Residential dwelling and outbuildings
Lot 9 (Plan 130054)	310 m north	Residential dwelling and outbuildings
Lot 7 (Plan 130054)	362 m north	Residential dwelling and outbuildings
Lot 24 (Plan 143273)	467 m northeast	Residential dwelling and outbuildings
Lot 3 (Plan 5336)	477 m east	Residential dwelling and outbuildings






3. POTENTIAL SOURCES OF DUST

The proposed project layout is shown in Figure 5. Potential sources of dust associated with the sand and gravel extraction operations include following:

- Vegetation clearing, topsoil stripping, and stockpiling.
- Sand and gravel extraction, crushing, stockpiling, and loading activities.
- Wind-borne dust from exposed surfaces, including cleared land, topsoil and resource stockpiles, and tracks.
- Vehicle movements on internal unpaved roads.
- Loading of haulage trucks.
- Poorly contained truck loads.
- Rehabilitation works, including final contouring, ripping, and spreading of topsoil and other materials.





4. SITE RISK ASSESSMENT

Dust potentially generated as part of the extraction operations is expected to be free of contaminants and pollutants. The adverse effects of dust generation from the site would typically be 'nuisance dust'.

A risk assessment was prepared based on the DEC "A guideline for managing the impacts of dust and associated contaminants from land development sites, contaminated sites remediation and other related activities" (DEC 2011). The risk assessment for the proposed extractive operations is provided in Appendix 2.

It calculates the risk of dust impacts and the need for management controls based on the nature of the site and the proposed operations as well as the proximity of sensitive receptors and prevailing winds. The risk assessment assumes that vegetation clearing will be gradual and proceed in stages and that revegetation will follow gradually in stages as well. Prevailing summer winds are morning easterlies and afternoon westerlies, and these have been taken into consideration in the risk assessment.

A site classification score of 396 was calculated for the on-site works, placing this development in a Classification 2 (Low Risk) category (between 200 and 399 points). Based on the Low Risk classification, the following are required (DEC 2011):

- Contingency plan detailing activities to be undertaken should dust impacts occur.
- Monitoring requirements.

These are both addressed in Section 5.

The main sensitive receptor is the closest residential dwelling located 157 m to the north of the extraction area. The residence is well screened by vegetation and is not downwind of the site under prevailing summer winds. The other nearby residences are located further away (272 m, 310 m, 362 m, 467m, and 477 m) from the extractive operations and are also screened by vegetation. Therefore, dust impacts to these residences are not likely to be significant with dust management actions in place (see Section 5).



5. DUST MANAGEMENT ACTIONS

5.1 DUST PREVENTION

The Site operator will implement the following measures to prevent dust generation from site activities:

- Vegetation clearing and topsoil removal will only be undertaken on days of conducive wind strength and conditions to ensure windblown dust is minimised.
- Vegetation clearing and ground disturbance will be gradual in nature and proceed in stages (Figure 5).
- Rehabilitation will also be gradual in nature and proceed in stages, closely following the completion of sand extraction.
- Topsoil stockpiles will be no greater than 2 m in height and other stockpiles will not exceed 4 m in height.
- A vehicle speed limit of 20 km/h will be implemented across the site.
- A water cart with a capacity greater than 10,000 L will be available when required and will undertake
 preventative watering of access tracks, working areas, and stockpiles during dry periods.
- Trucks leaving the site will be required to have their load covered and tailgates and draw-bars clear of dust producing material prior to exiting the property. Appropriate signage will be erected at the site exit advising truck drivers to cover loads and clean their vehicle as required prior to entering public roads.

5.2 DUST MONITORING AND MITIGATION

The Site operator will implement the following measures to monitor and mitigate dust generation from site activities:

- Visual monitoring of dust generation from the operations will be undertaken on an ongoing basis.
- Should excessively dust generation be observed onsite and there is a risk of dust being blown off site, additional watering of dust sources with the water cart will be organised. Alternative dust controls, such as chemical dust suppressants or dust fencing, may also be considered for more persistent sources of dust.
- When weather conditions negate the effectiveness of dust prevention and mitigation measures and dust continues to be blown off site, the dust generating activities will cease until conditions improve and compliance with this DMP can be achieved.

5.3 DUST COMPLAINTS

The dust complaints process is as follows:

- A sign will be erected at the entrance to the extraction site advising the public on the appropriate contact in the event of a complaint.
- In the event of receiving a complaint, the EIL licensee will complete a Dust Complaint Form (Appendix 3), investigate, and resolve the complaint within 4 hours.
- A copy of the completed Dust Complaint Form will be forwarded to the Shire of Capel for their records.
- If required, a review of the DMP will be undertaken to refine dust prevention, monitoring, and mitigation measures.



6. ROLES AND RESPONSIBILITIES

Roles and responsibilities with respect to dust management are outlined in Table 2.

Table 2: Roles and Responsibilities

Role	Responsibilities	
EIL Licensee	 Will have overall responsibility for the dust management of the operations. Will provide information for site operators and truck drivers on dust management objectives, and dust management measures to be undertaken on site (prevention, monitoring, and mitigation). Will be responsible for resolving any persistent dust management issues. Will be responsible for administering the dust complaints process. 	
All personnel	 Will be familiar with potential sources of dust associated with own role and how to minimise dust generation. Will implement the dust prevention, monitoring and mitigation measures as described in this plan and as advised by the EIL Licensee. Will be responsible for reporting any persistent dust management issues to the EIL Licensee. 	



7. REFERENCES

Bureau of Meteorology (BOM). 2023. Climate Statistics for Australian Locations. Bunbury Meteorological Station 9534. http://www.bom.gov.au/climate/averages/tables/cw_009534.shtml (accessed August 2023).

Commonwealth Scientific and Industrial Research Organisation (CSIRO). 2014. Australian Soil Resource Information System. https://www.asris.csiro.au/index.html (accessed August 2023).

Department of Environment and Conservation (DEC). 2011. A guideline for managing the impacts of dust and associated contaminants from land development sites, contaminated sites remediation and other related activities. https://www.der.wa.gov.au/images/documents/your-environment/air/publications/Guideline_for_managing_impac ts of dust.pdf (accessed August 2023).

Department of Primary Industries and Regional Development (DPIRD). 2022. *Soil Landscape Mapping - Systems* (DPIRD-064). https://catalogue.data.wa.gov.au/dataset/soil-landscape-mapping-systems (accessed August 2023).

Government of Western Australia (WA Gov). 2014. *Greater Bunbury Region Scheme*. https://www.legislation.wa.gov.au/legislation/statutes.nsf/main_mrtitle_12899_homepage.html (accessed August 2023).

Keighery, B.J. 1994. Bushland Plant Survey: A Guide to Plant Community Survey for the Community. Wildflower Society of WA (Inc). Nedlands, Western Australia.

Marsh, D. 2019. Desktop Study and Reconnaissance Flora and Vegetation Survey. Unpublished report for Mario Michele Giacci, Lot 287 South West Hwy, Gwindinup, WA. By Botanical Consulting, January 2019.

Shire of Capel. 2023. *Local Planning Scheme No. 8.* Gazetted on 17 July 2023. https://www.capel.wa.gov.au/local-planning-schemes.aspx (accessed August 2023).



APPENDICES



DUST MANAGEMENT PLAN

APPENDIX 1: WIND ROSES



Rose of Wind direction versus Wind speed in km/h (01 Jan 1957 to 10 Aug 2023)


Custom times selected, refer to attached note for details

DONNYBROOK

Site No: 009534 • Opened Jan 1900 • Still Open • Latitude: -33.5719° • Longitude: 115.8247° • Elevation 63m

An asterisk (*) indicates that calm is less than 0.5%.

Other important info about this analysis is available in the accompanying notes.





Rose of Wind direction versus Wind speed in km/h (01 Jan 1957 to 10 Aug 2023)


Custom times selected, refer to attached note for details

DONNYBROOK

Site No: 009534 • Opened Jan 1900 • Still Open • Latitude: -33.5719° • Longitude: 115.8247° • Elevation 63m

An asterisk (*) indicates that calm is less than 0.5%.

Other important info about this analysis is available in the accompanying notes.



3 pm 20359 Total Observations

Calm 5%



DUST MANAGEMENT PLAN

APPENDIX 2: RISK ASSESSMENT



Site Risk Assessment/Classification for Activities Generating Uncontaminated Dust

Part A: Nature of site

Item		Score Options		Allocated Score	
Nuisance potential of soil, when disturbed.	Very low1	Low2	Medium4	High6	4
2. Topography and protection provided by undisturbed vegetation.	Sheltered and screened1	Medium screening6	Little screening12	Exposed and wind prone18	6
3. Area of site disturbed by the works.	Less than 1 ha1	Between 1-5 ha(3)	Between 5-10 ha6	More than 10 ha9	3
4. Type of work being done.	Roads or shallow trenches1	Roads, drains, and medium depth sewers3	Roads, drains, sewers, and partial earthworks6	Bulk earthworks and deep trenches9	9
			•	TOTAL score for Part A	22

Part B: Proximity of site to other land uses

Item	Score Options		Allocated Score		
Distance of other land uses from site.	More than 1 km1	Between 1 km and 500 m6	Between 100 m and 500 m12	Less than 100 m18	12
2. Effect of prevailing wind direction (at time of construction) on other land uses.	Not affected1	Isolated land uses affected by one wind direction	Dense land uses affected by one wind direction9	Dense/sensitive land uses highly affected by prevailing winds12	6
				TOTAL score for Part B	18

Site Classification Score (A x B) = 396



DUST MANAGEMENT PLAN

APPENDIX 3: DUST COMPLAINT FORM



DUST COMPLAINT FORM

Property:	Lot 287 South Western Hwy, Gwindinup
Complaint date:	
Complaint time:	
Received by:	
Complainant's Details	
Name:	
Telephone:	
Affected address:	
Complaint Details (attach re	eport if insufficient space)
Action Taken (attach report	if insufficient space)
Actions recorded by:	
Date:	
Copy to Shire of Capel:	(tick)

11100	Marie	E GIACCI
IVIARI()	IVII(:HFI	F (TIACCI

DA AND EIL APPLICATION

APPENDIX 10: WEED AND DIEBACK MANAGEMENT PLAN



WEED AND DIEBACK MANAGEMENT PLAN LOT 287 SOUTH WESTERN HWY, GWINDINUP

PREPARED FOR:

MARIO MICHELE GIACCI

MARCH 2024

PREPARED BY:

Martinick Bosch Sell Pty Ltd
4 Cook Street
West Perth WA 6005
Ph: (08) 9226 3166
Email: info@mbsenvironmental.com.au

Web: <u>www.mbsenvironmental.com.au</u>





LOT 287 SOUTH WESTERN HWY, GWINDINUP WEED AND DIEBACK MANAGEMENT PLAN

Distribution List:

Company	Contact name	Copies	Date
MGM Bulk	Craig Carbone — Sales/Business Development	Electronic	8 March 2024

Document Control for Job Number: MGM287EXT

Document Status	Prepared By	Authorised By	Date
Draft Report	Sharon Rose	Kirsi Kauhanen	15 September 2023
Final Report	Sharon Rose	Kirsi Kauhanen	8 March 2024

Disclaimer, Confidentiality and Copyright Statement

This report is copyright. Ownership of the copyright remains with Martinick Bosch Sell Pty Ltd (MBS Environmental) and Mario Michele Giacci.

This report has been prepared for **Mario Michele Giacci** on the basis of instructions and information provided by **Mario Michele Giacci** and therefore may be subject to qualifications which are not expressed.

No person other than those authorised in the distribution list may use or rely on this report without confirmation in writing from MBS Environmental and **Mario Michele Giacci**. MBS Environmental has no liability to any other person who acts or relies upon any information contained in this report without confirmation.

This report has been checked and released for transmittal to Mario Michele Giacci.

These Technical Reports:

- Enjoy copyright protection and the copyright vests in MBS Environmental and **Mario Michele Giacci** unless otherwise agreed in writing.
- May not be reproduced or transmitted in any form or by any means whatsoever to any person without the written permission of the Copyright holder.



TABLE OF CONTENTS

1.	Introduction	1
1.1 1.2	PurposeScope and Objective	
2.	EXISTING ENVIRONMENT	4
2.2 2.3 2.4 2.5 2.6	LANDFORM AND SOILS VEGETATION LAND USE CURRENT WEED STATUS CURRENT DIEBACK STATUS	7 7 7
3.	WEED MANAGEMENT	9
3.1 3.2 3.2.2	WEED PREVENTION MONITORING Weed Control Monitoring	10
4.	DIEBACK MANAGEMENT	11
5.	Roles and Responsibilities	12
6.	REFERENCES	13
	TABLES	
Table 1:	Roles and Responsibilities	12
	Figures	
Figure 1:	Project Location	2
Figure 2:	Works and Excavation Plan	3
Figure 3:	Climate Statistics (1900–2023) for BoM Station 9534	4
Figure 4:	Landform and Soils	6
	APPENDICES	

Appendix 1: Phytophthora Dieback Assessment Report



1. Introduction

1.1 Purpose

Mario Michele Giacci (the applicant) is proposing to expand existing sand and gravel extraction operations on Lot 287 (Plan 100056) South Western Hwy in Gwindinup (the property), Western Australia (Figure 1, Figure 2). This Weed and Dieback Management Plan (WDMP) has been prepared for the proposed operations as supporting documentation to accompany a Development Application (DA) and Extractive Industry Licence (EIL) application to the Shire of Capel (the Shire).

This WDMP is prepared in accordance with the *Biosecurity and Agriculture Management Act 2007* (BAM Act), the *Australian Weeds Strategy 2017–2027* developed by the Invasive Plants and Animals Committee (2017), and the Dieback Working Group's (DWG 2021) *Best Practice Guidelines for Management of Phytophthora Dieback in Raw Material Industries* (the Guidelines). Consideration has also been given to the *Phytophthora Dieback Management Manual* (the Manual) produced by the Department of Biodiversity, Conservation and Attractions (DBCA 2020) and the *Dieback Hygiene Guidelines* by South Coast Natural Resource Management (South Coast NRM 2013).


1.2 SCOPE AND OBJECTIVE


This WDMP has been developed to provide details of the existing environment and guidance around best management practices for weeds and *Phytophthora cinnamomi* (dieback) with the objective to minimise the risk of introduction and spread of weeds and dieback during the extraction operations.

The scope of this WDMP includes following:

- Describe the existing environment.
- Provide guidance to minimise spread of weeds and dieback within, to, and from Lot 287.







2. EXISTING ENVIRONMENT

2.1 CLIMATE

The climate of the Project area is Mediterranean, with cool wet winters and hot dry summers. Bureau of Meteorology (BoM) long-term average climate data for the closest meteorological station (Donnybrook, 9 km southeast of the property) is shown in Figure 3. The average annual rainfall is 970.4 mm, mean minimum temperatures between 5 and 15°C and mean maximum temperatures between 16 and 31°C (BoM 2023).




Figure 3: Climate Statistics (1900-2023) for BoM Station 9534

2.2 LANDFORM AND SOILS

The highest point on Lot 287 is situated approximately halfway along the southern property boundary and has an elevation of 111 m Australian Height Datum (mAHD) (Figure 4). From this point, the land to the west and north slopes and undulates downward at gradients between approximately 1:10 and 1:20. Near the northern boundary there are steeper areas of approximately 1:6. To the east of the proposed extraction area lies the steepest gradients on the property, which slope towards the South Western Highway at gradients up to 1:6 within the proposed extraction area and up to 1:4 further east, beyond the proposed extraction area. Within the proposed extraction area, the highest point is 109 mAHD in the south and the lowest point is 78 mAHD in the northeast (Figure 4).

Three soil and landform mapping systems are mapped within and surrounding the proposed extraction area (DPIRD-064):


- Whicher Scarp System: Low scarp and raised platform, on the northern edge of the Donnybrook Sunkland.
 Sandy gravel and pale deep sands, loamy gravel, and non-saline wet soils. Jarrah-marri forest and woodland.
- Goodwood Valleys System: Valleys, of the Donnybrook Sunkland. Sandy gravel, loamy gravel, and deep sand. Jarrah-marri forest and woodland.
- Blackwood Plateau System: Lateritic plateau in the Donnybrook Sunkland. Sandy gravel, loamy gravel, and deep sand. Jarrah-marri forest.

WEED AND DIEBACK MANAGEMENT PLAN

The proposed expansion to the extraction area is mostly located within the Goodwood Valleys System. Extraction on the property so far has shown that there is a layer of sand, of varying depth, that overlies the gravel.

Lot 287 is located away from wetlands and waterways on well-draining soils. The Australian Soil Resource Information System maps the property as 'Extremely Low Probability/Low Confidence' for the risk of acid sulfate soil (CSIRO 2014).





2.3 VEGETATION

Lot 287 contains a mosaic of remnant native vegetation, blue gum (*Eucalyptus saligna*) plantation, extraction operation, and some cleared land. There is approximately 19 ha of native vegetation, split into several patches. Reconnaissance flora and vegetation survey (Marsh 2019) identified three native vegetation types and an introduced vegetation type in the proposed extraction area:

- VT1: Tall woodland of *Eucalyptus marginata* and *Corymbia calophylla* over low woodland of *Banksia grandis* over tall sparse shrubland of *Kunzea glabrescens* over low sparse shrubland of *Xanthorrhoea preissii*.
- VT2: Tall woodland of *Eucalyptus marginata* and *Corymbia calophylla* over tall sparse shrubland of *Kunzea glabrescens* over low sparse shrubland of *Xanthorrhoea preissii* and *Xanthorrhoea gracilis*.
- VT3: Tall woodland of *Eucalyptus marginata* and *Corymbia calophylla* over low sparse shrubland of *Xanthorrhoea preissii* and *Hibbertia hypericoides*.
- D: Disturbed: Blue gum plantations, tracks, and clearings.

The native vegetation communities vary in condition from Degraded to Very Good – Good (using condition scale by Keighery 1994) and show signs of multiple historical disturbances including selective logging, fire, weeds, and dieback. Currently there is disturbance in the form of cleared tracks and small bare areas. The blue gum plantation areas have been completely cleared of native vegetation in the past.

No Threatened or Priority Ecological Communities or Threatened or Priority flora species have been recorded at Lot 287. Several common weed species have been recorded but no Declared Pest species or weeds of national significance (Marsh 2019).

2.4 LAND USE

Lot 287 is zoned 'Rural' under the Shire of Capel Local Planning Scheme No.8 (2023) and falls within three Special Control Areas (SCA): SCA4 - Transport Corridors, SCA6 - Strategic Minerals and Basic Raw Materials, and SCA8 - Regional Ecological Linkages.

The property contains no buildings. In addition to the active extraction area on the western side of the property, Lot 287 contains a blue gum plantation with pockets of remnant native vegetation (Figure 2). Blue gums within the previously approved extraction area have been harvested, with the remainder of the current application area to be harvested prior to extraction.

The eastern edge of Lot 287 is reserved for 'Primary Regional Road' (Shire of Capel 2023). A 'Highway Protection Line' straddles the property along its eastern highway road frontage and delineates an area (100 m distance from either side of the centre line of the road), which is defined as the 'Highway Protection Area'. The purpose of the 'Highway Protection Area' is to protect the function, amenity, and visual character of the Highway. The proposed extraction area is well outside the 'Highway Protection Area'.

2.5 CURRENT WEED STATUS

Seven introduced (weed) species were identified from the 62 plant taxa recorded on the property (Marsh 2019) and are listed below:

- Blowfly Grass (*Briza maxima*).
- Cape Bluebell (Wahlenbergia capensis).
- Flinders Range Wattle (Acacia iteaphylla).
- Silvery Hairgrass (Aira cupaniana).
- Smooth Cats-ear (*Hypochaeris glabra*).
- Ursinia (Ursinia anthemoides).
- Velvet Pink (Petrorhagia dubia).

None of the identified weeds are listed as Weeds of National Significance or Declared Pests under the BAM Act.



Other weed species (e.g. ink weed *Phytolacca octandra*) have been opportunistically observed in the blue gum plantation and other disturbed areas of the property. Blue gums are an introduced species and will be harvested before extraction occurs. Any subsequent blue gum regrowth will be controlled as part of the site weed management program.

2.6 CURRENT DIEBACK STATUS

Dieback is present in locations around the globe that have a Mediterranean climate, including the southwest of Western Australia. There are over 140 species of *Phytophthora* worldwide, but the most commonly found and damaging species in the southwest is *Phytophthora cinnamomi*.

Dieback Public Map (Project Dieback 2024) indicates that all the native vegetation on Lot 287 and the adjacent properties is dieback infested with moderate confidence, based on an assessment in 2008. Bark Environmental conducted site-specific dieback surveys at Lot 287 in May and September of 2019 (Appendix 1). It was determined that the majority of the remaining native vegetation, 15 ha is dieback infested with only around 1 ha uninfested (Bark Environmental 2020). The remainder of the native vegetation, blue gum plantation areas, and cleared areas are mapped as excluded because the presence of dieback was undeterminable due to the lack of indicator species (Appendix 1). The presence of dieback in these areas cannot be ruled out and, because of this, they will be treated as potentially dieback infested for site management purposes.

Dieback is spread through infected soil. The infected soil can be spread by fauna movement, surface water runoff, soil movement on sloping surfaces, and spores; however, the biggest spreader of dieback is human activity and movement. Infected soil can contaminate vehicles, footwear, and equipment that then moves to an uninfected area, introducing the pathogen. Additionally, the transport of infected soil as import or export material from a site can contribute to dieback spread. Various rural activities in the local area and recreational use of the reserves carry a risk of introducing and spreading dieback.



3. WEED MANAGEMENT

Weeds can be spread or introduced to an area via a number of circumstances, such as wind-borne seed, vehicle movements, rain runoff, fauna activity, movement of soil, dust, and introduction of materials, such as soil and mulch, from external sources. The applicant recognises the importance of effective management of weeds during extractive operations and subsequent revegetation. As the site already contains a range of common weed species and part of the property will be rehabilitated to pasture, weed management during the extractive operations will mainly aim to prevent the introduction of declared weed species, minimise spread of the more common weeds, and instigate the monitoring and control of weeds during rehabilitation.

3.1 WEED PREVENTION

The site operator will implement the following measures as part of the extractive operations to reduce weed spread and prevent, as far as practicable, the introduction of new weed species at Lot 287 and the export of weeds from the property:

- All vehicles, plant, and equipment entering or exiting the property will be clean and free of weeds.
- Topsoil will be removed from the extraction area and stockpiled (gradually in stages).
- Following removal of topsoil, the movement of vehicles and machinery will be limited to the areas free of topsoil to limit the spread of weeds.
- Exported quarry products will be free of weeds.
- Materials imported to site will be free of weeds.
- Weed control will be conducted in operational areas (e.g. trafficable areas and material stockpiles) to ensure these areas remain weed free.
- Weed control of topsoil stockpiles will be undertaken to minimise seed set.
- During rehabilitation activities, weed control will be undertaken as necessary to minimise weed spread and to prevent weeds from compromising the end land use.
- Weed presence and control will be monitored (Section 3.2).

Weed control will be tailored to cater for the specific needs of the weed species being managed and may involve chemical and/or manual control. In addition to broad spectrum herbicides, weed specific herbicides will be used where appropriate to target broadleaf, grass, geophyte, and woody weeds.

The requirements for rehabilitation and associated weed control are detailed in a separate rehabilitation plan. At this stage, it is anticipated that both pasture and native vegetation will be returned as part of rehabilitation. It is expected that rehabilitation weed control will, as a minimum, include control prior to planting/seeding once topsoil has been re-spread. This is typically undertaken in late autumn/early winter depending on commencement of seasonal rains. This will enable any weeds germinating from the soil seed bank to be targeted. Ongoing weed control following planting/seeding will also occur as need be to allow for the pasture and native species to become established.



3.2 MONITORING

3.2.1 Weed Status Monitoring

The weed status of Lot 287 will be monitored biannually to determine whether introduction or spread of weeds is occurring and to identify required weed control. Monitoring should occur four to six weeks after the first significant autumn/early winter rains and in mid to late spring; however, opportunistic passive monitoring will also occur as a part of general operations and weed control will be organised if the need is identified.

3.2.2 Weed Control Monitoring

Areas requiring weed control will be checked within two weeks before the commencement of weed control (either as part of biannual monitoring or separately) and then six to eight weeks after weed control has been conducted to gauge effectiveness and determine if follow up control is required.



4. DIEBACK MANAGEMENT

Based on Section 2.6, the occurrence of dieback on Lot 287 is confirmed (Bark Environmental 2020). For the purposes of dieback management, the proposed extraction area and blue gum harvest areas will be considered as dieback infested. Vegetation outside the proposed extraction area mapped as dieback-free (Bark Environmental 2020) will become a no-access zone.

Dieback will be managed in accordance with the best practice guidelines and manuals (Section 1.1), and will include the following measures:

- All earth-moving machinery will be cleaned of soil and vegetation prior to entering and leaving site.
- Soil will only be moved in dry conditions.
- No dieback-affected material will be brought to site.
- Machinery and other vehicles will remain within the extraction area to minimise the risk of spreading disease.
- Drainage will be contained within the extraction area, with designated overflow pathways that minimise
 potential for disease spread. Direct surface water runoff from the extraction area to the surrounds will be
 avoided.
- Personnel will be informed that the site may be infested with dieback and that dieback can spread on vehicles, machinery, equipment, footwear, and tools, and instructed on clean down requirements.
- Topsoil will be stockpiled and respread as close to its source area as possible.
- Potential customers will be advised that the material exported from site cannot be considered dieback free.
- Entry to and exit from the site will be limited to designated locations.
- Trucks exporting sand from the site will be required to have their load properly covered.
- Ensure that, as far as can be known, any soil, mulch, fill, or other material brought on site is sourced responsibly and free of dieback.
- Topsoil will be removed and stockpiled from the extraction area (gradually in stages), and the subsequent movement of vehicles and machinery will be limited to the areas free of topsoil.
- Vegetation clearing and topsoil removal and stockpiling will only be undertaken in dry conditions.
- Existing and new personnel will be informed of dieback prevention measures and be required to meet them.
- Unauthorised access to the extraction site will be managed through fencing and lockable gates.
- Signage regarding unauthorised entry and 'clean on entry' requirements will be placed at the gates.
- Trafficable areas and material stockpiles areas will be maintained well drained.



5. ROLES AND RESPONSIBILITIES

Roles and responsibilities with respect to weed and dieback management are outline in Table 1.

Table 1: Roles and Responsibilities

Role	Responsibilities
EIL Licensee	 Responsible for overall implementation of this plan. Will provide information for site personnel and truck drivers on weed and dieback management objectives and measures to be undertaken on site. Responsible for organising monitoring and control of weeds.
	 Responsible for site access security and appropriate signage.
All personnel	 Will be familiar with weed and dieback management objectives. Will implement measures to prevent spread and introduction of weeds and dieback as outlined in this plan. Responsible for reporting any weed or dieback management issues to EIL Licensee.



6. REFERENCES

Bark Environmental. 2020. *Phytophthora Dieback Assessment Report Lot 287 Gwindinup*. Unpublished report for Mario Michele Giacci, February 2020.

Bureau of Meteorology (BOM). 2023. *Climate Statistics for Australian Locations*. Donnybrook Meteorological Station 9534. http://www.bom.gov.au/climate/averages/tables/cw-009534.shtml (accessed August 2023).

Commonwealth Scientific and Industrial Research Organisation (CSIRO). 2014. *Australian Soil Resource Information System*. https://www.asris.csiro.au/index.html (accessed August 2023).

Department of Biodiversity, Conservation and Attractions (DBCA). 2020. *Phytophthora Dieback Management Manual*. https://www.dpaw.wa.gov.au/images/documents/conservation-management/pests-diseases/disease-riskareas/DBCA%20PDMM%20v1.2%20October%202020.pdf (accessed August 2023).

Department of Primary Industries and Regional Development (DPIRD). 2021. Soil Landscape Mapping - Systems (DPIRD-064). https://catalogue.data.wa.gov.au/dataset/soil-landscape-mapping-systems (accessed August 2023).

Dieback Working Group (DWG). 2021. *Management of Phytophthora Dieback in the Basic Raw Material Industries*. https://www.dwg.org.au/publications-links/publications/download-info/basic-raw-materials-best-practice-guidelines/ (accessed August 2023).

Government of Western Australia. 2022. *Biosecurity and Agriculture Management Act 2007*. https://www.legislation.wa.gov.au/legislation/statutes.nsf/main_mrtitle_2736_homepage.html (accessed August 2023).

Invasive Plants and Animals Committee. 2017. *Australian Weeds Strategy 2017-2027*. https://www.agriculture.gov.au/biosecurity-trade/pests-diseases-weeds/pest-animals-and-weeds (accessed August 2023).

Marsh, D. 2019. Desktop Study and Reconnaissance Flora and Vegetation Survey Lot 287 South West Hwy, Gwindinup, WA. Unpublished report by Botanical Consulting for Mario Michele Giacci, January 2019.

Project Dieback. 2024. Dieback Public Map. https://dieback.net.au/dieback-public-map/ (accessed January 2024).

Shire of Capel. 2023. *Shire of Capel Local Planning Scheme No. 8.* https://www.capel.wa.gov.au/services/planning/strategy/ (accessed July 2023)

South Coast Natural Resource Management (South Coast NRM). 2013. *Phytophthora Dieback - Dieback hygiene Guidelines*. https://dieback.net.au/wp-content/uploads/2019/03/dieback hygiene 2 email version2013.pdf (accessed August 2023).



APPENDICES



WEED AND DIEBACK MANAGEMENT PLAN

APPENDIX 1: PHYTOPHTHORA DIEBACK ASSESSMENT REPORT





Phytophthora Dieback Assessment Report Lot 287 Gwindinup

Method of assessment	Comprehensive / Basic raw materials (BRM) pit assessment	
Dates of field work	May and September 2019	
Interpretation	BARK Environmental	
Map Expiry	September 2020 – It can be rechecked up to 3 years after initial assessment (up to 2022), then a Comprehensive Assessment is required.	
Map Validity for disturbance activities	This Dieback Occurrence Map (Figure 1) is valid for 12 months (September 2020). It can be rechecked annually for up to 3 years (September 2022), before any further soil disturbance activities occur.	
	After September 2022, a complete <i>Phytophthora</i> assessment should be undertaken to ensure accurate mapping of disease.	
Report Version	2.2020	

BARK ENVIRONMENTAL

Enquiries: <u>barkenv@gmail.com</u>
W: www.barkenviro.com

T: 0400 208 582



Contents

1	Intr	oduction	5
	1.1	Background	5
	1.1	Site description and historical disturbance	5
2	Met	hods	7
	2.1	Interpretation	7
	2.2	Demarcation	7
	2.3	Soil and tissue sampling	7
	2.4	Mapping	7
	2.5	Vegetation Condition Rating	8
3	Res	sults	8
	3.1	Assessment category distribution	8
	3.2	Disease expression	9
	3.3	Disease impact	9
	3.4	Sample results	10
	3.5	Vegetation Condition	10
4	Cor	nclusion	11
5	Red	commendations	12
6	Ref	erences	12

Figures

Figure 1. Phytophthora Dieback Occurrence: Lot 287 Gwindinup

Appendices

A: Site Photographs Lot 287 – October 2019

B: Sample Data Sheet

INTRODUCTION

1.1 Background

A Phytophthora Dieback Assessment is required as part of the environmental approvals process for the proposed expansion of a basic raw materials area within Lot 287 (Plan 100056) situated approximately 5km south of Boyanup.

Phytophthora Dieback is a devastating plant disease caused by a soil-borne water mould that threatens biodiversity in the south west region where up to approximately 40% of the known native plant species are susceptible. The pathogen is now widespread.

Phytophthoras spread is accelerated by physically moving infested soil and plant material across landscapes, particularly under warm, moist conditions. It also spreads autonomously through infected root to root contact and in water. Therefore, human activities that can transport *Phytophthora* infected material present the most significant risk to vectoring the disease such as on uncleaned vehicles, tools and footwear, when clearing vegetation and vehicle movements.

Mitigating the spread and impact of *Phytophthora* Dieback in natural areas is difficult. Raising awareness of the issue among stakeholders and mapping its spatial distribution are the first steps to developing an effective Dieback Management Plan. This report describes the results with recommendations from undertaking a Phytophthora Dieback Occurrence Assessment over Lot 287 over 2 days in May and September 2019. It includes a *Phytophthora Dieback Occurrence Map* (Figure 1) with management recommendations. Figure 1 is valid for 1 year and can be rechecked in the field annually for up to 3 years to ensure the boundaries are accurate as the disease can spread over time. A comprehensive assessment is recommended as standard practice by the Department of Biodiversity Conservation and Attractions (DBCA) when occurrence maps are over 3 years old.

1.1 Site description and historical disturbance

Lot 287 is a rectangular fenced area bounded by the South Western Highway to the east, remnant vegetation to the north and south and cleared land with sand extraction occurring in the west. The total assessment area size is 46.1 ha and the majority has been planted with blue-gums. Approximately 19ha comprises fragmented native vegetation in clumps separated by blue-gum plantations. Exploration pits are scattered throughout and some previous gravel exploration and extraction has occurred in the eastern parts (see Plate 1). The entire area has been subjected to historic clearing (see Plate 2), firewood collection (Plate 3) and various degrees of human disturbance over decades.

The average annual rainfall in this locality exceeds 900mm, that confirms the study area falls within the vulnerable zone where *Phytophthora* disease can develop and cause impacts to native vegetation (Bureau of Meteorology, 2019).

Site vegetation is comprised of three vegetation complexes, namely the Rosa, Whicher Scarp and Kingia vegetation complexes as described in the 'Vegetation Complexes of South West Forest Region of WA (DBCA-047)' dataset. Each of these complexes contain some plants susceptible to *Phytophthora* disease. Deep sandy soils were observed during assessment enabling good drainage, however surface laterite is also present particularly on the eastern slopes that appears to form micro collection of surface water run-off that may support

Phytophthora development, if it is introduced. There was no significant recent fire damage observed to existing vegetation in the area that could limit Phytophthora interpretation.

Plate 1. Old gravel exploration pits are scattered throughout Lot 287.



Plate 2. Much of the assessment area has been subjected to historic clearing and disturbance, that has reduced the understorey density and abundance of expected plant species.



Plate 3. Firewood collection.



2 METHODS

2.1 Interpretation

Field interpretation was based on the Comprehensive and Basic Raw Materials (BRM) pit assessment methodology used by the DBCA and described in their manual "Forest and Ecosystem Management Division 2015, Phytophthora Dieback Interpreter's manual for lands managed by the department, DPaW, Perth, Western Australia."

2.2 Demarcation

BARK was advised that no taping was necessary at this stage and given the remnant blocks can be clearly identified by plantation boundaries, no taping was done. Instead, boundaries were recorded and mapped using GPS data obtained in the field. The standards for taping are given below for general information only.

Infested areas are demarcated using 25 mm fluoro pink tape tied to trees at chest height with the knots facing into the infestation. Excluded and Uninterpretable areas are demarcated using 25 mm striped black/pink tape tied to trees with the knots facing towards the respective category. When vegetated boundaries adjoin cleared completely degraded areas, taping may not be applied as they can easily be observed in the field, on aerial imagery and established with captured GPS data.

2.3 Soil and tissue sampling

Soil and tissue samples associated with dead or dying plants are collected per DPaW 2015 methodology to confirm the presence or absence of *Phytophthoras*. Sample locations are tagged in the field and point data is recorded with GPS receivers before despatching samples to a laboratory for testing. Sample results are only used as supporting evidence. <u>Please note</u>: It cannot be concluded that an entire site or an entire stockpile of basic raw material is dieback-free from a single or a small number of samples where *Phytophthora* was not detected. On occasions sample results may give false negative results, so field observations are critical to making effective interpretation decisions.

2.4 Mapping

Field observations, boundaries, waypoints and survey data are recorded on hand-held GPS and downloaded into a Geographic Information System (GIS) to produce *Phytophthora* maps.



2.5 Vegetation Condition Rating

Site vegetation was rated using the scale described below.

Table 1. Vegetation Condition Rating Scale (Keighery, 1996).

Datina	Description
Rating	Description
Pristine (1)	Pristine or nearly so, no obvious signs of disturbance.
Excellent (2)	Vegetation structure intact, disturbance affecting individual species and
	weeds are non-aggressive species.
Very Good (3)	Vegetation structure altered, obvious signs of disturbance. For example,
	disturbance to vegetation structure caused by repeated fires, the
	presence of some more aggressive weeds, dieback, logging and grazing.
Good (4)	Vegetation structure significantly altered by very obvious signs of multiple
	disturbances. Retains basic vegetation structure or ability to regenerate
	it. For example, disturbance to vegetation structure caused by very
	frequent fires, the presence of some very aggressive weeds at high
	density, partial clearing, dieback and grazing.
Degraded (5)	Basic vegetation structure severely impacted by disturbance. Scope for
	regeneration but not to a state approaching good condition without
	intensive management. For example, disturbance to vegetation structure
	caused by frequent fires, the presence of very aggressive weeds, partial
	clearing, dieback and grazing.
Completely Degraded (6)	The structure of the vegetation is no longer intact and the area is
	completely or almost completely without native species. These areas are
	often described as 'parkland cleared' with the flora comprising weed or
	crop species with isolated native trees or shrubs.

3 RESULTS

3.1 Assessment category distribution

Three Dieback categories have been applied to within Lot 287 (Table 2) as follows:

- Uninfested Free from plant disease symptoms caused by Phytophthora spp.
 This includes 2 separate areas of remnant vegetation located towards the northwest and southwest boundaries of Lot 287.
- Infested Areas where disease symptoms are consistent with the presence of *Phytophthora spp*.

There are 3 separate infested remnant vegetation areas within Lot 287.

• Excluded – Areas of high disturbance unlikely to recover to enable interpretation.

This category was applied to all blue-gum plantation and previously disturbed completely degraded cleared areas and tracks. It includes Degraded and Completely Degraded areas.



Table 2: Dieback Occurrence Categories, Lot 287

Category	Area (ha)
Infested	17
Uninfested	1
Excluded	28.1
Total Area Assessed	46.1

3.2 Disease expression

Phytophthora disease expression within Lot 287 was "average" at the time of assessment. Within the infested areas, there is a marked reduction in biomass with species such as Banksia grandis expected to be present and abundant but that was not the case. Xanthorrhoea gracilis and X. preissii were observed to be the most reliable dead and dying indicator species. This was supported by sample results. There is some chronology of susceptible plant deaths present, particularly between upslope infestations and downslope areas where the disease has been present for longer. However, with reduced biomass and the presence of lateritic outcrops may be limiting root-root contact and even distribution of surface water, so the disease appears as scattered deaths, namely among Xanthorrhoea spp.

3.3 Disease impact

Site observations identified that *Phytophthora* disease is present and has caused a moderate to high impact to the native vegetation community structure and species composition within Lot 287 over time. However, the adverse effects from previous human disturbance activities such as clearing to establish plantations, track development, gravel extraction and timber harvesting have all contributed to this. There is no evidence in the public domain of any previous biosecurity-hygiene being applied for the aforementioned historic activities within Lot 287.

The predicted impact of *Phytophthora cinnamomi* at this site is moderate to high given the site contains a vulnerable plant community. In high rainfall years with warm-moist conditions, the disease in this area is likely to become more active and obvious with an increasing number of fresh plant deaths present resulting from *Phytophthora* infection. This observation has been made by the author within proximate vegetated areas in greater Bunbury.

3.4 Sample results

Four soil and plant tissue samples were collected on 12.05.2019 within Lot 287 and the laboratory results are summarised in table 3 with full details in appendix B. The sampling strategy applied was to target a range of indicator plants at different points along the contour across the site. Samples 1 and 2 were collected in upslope areas from not recent deaths. Sample 2 was collected from a potentially drought and insect affected dead *Banksia*. Samples 3 and 4 were collected from fresher plant deaths showing typical chlorosis symptoms on leaf structures.

Table 3. Sample Results Summary

Sample Name (date)	Plant Sampled	Result (POSITIVE, NEGATIVE)
S1	Xanthorrhoea preissii	NEGATIVE
S2	Banksia grandis	NEGATIVE
S3	X. gracilis	POSITIVE
S4	X. preissii	POSITIVE

3.5 Vegetation Condition

Industry Dieback assessment methodology and Keighery 1996 Vegetation Condition Scale Ratings were considered. Degraded areas and Completely Degraded areas were allocated the Excluded category. A good example of what Good-Very Good remnant vegetation condition would look like, if present within Lot 287 is situated outside of the Lot to the immediate north (see Appendix 1). In this area the density and diversity of plants vulnerable to Phytophthora is greater than within Lot 287.

This assessment included walking transects 25m wide throughout the entire study area that revealed a relatively consistent pattern of scattered *Xanthorrhoea spp.* deaths that were associated with long-term *Phytophthora* disease and two samples (3 and 4) results support this conclusion.

In the authors opinion, currently the majority of the remnant vegetation remaining at this site is made up of a mosaic of Degraded-Good condition areas and all remaining disturbed areas and plantations are Degraded and Completely Degraded.

4 CONCLUSION

Lot 287 has been exposed to a history of disturbance activities. Two small isolated blocks of remnant vegetation are Uninfested and in Very Good condition in the western part. However, their combined small area (1ha) will be difficult to manage in respect to Phytophthora Dieback given the surrounding site conditions. In the authors opinion if either of the aforementioned areas is to be retained as "Protectable Area", the Uninfested area on the vegetated south west corner of Lot 287 is in the best condition and landscape position to be retained. By Department of Biodiversity Conservation and Attractions (DBCA) protocols for determining protectable areas, and based on information available to BARK at the time of assessment — none of the Uninfested areas warrant protection. The landholder may choose to retain these areas for example if Rare flora is present or as part of any vegetation clearing offset proposal.

Dieback infested areas are present and extensive within Lot 287 (17 ha). All remaining areas including the plantations within Lot 287 have been Excluded due to their Completely Degraded Vegetation condition ratings and no Dieback controls are necessary within them (28.1 ha).

The attached Figure 1 shows the spatial distribution of Phytophthora assessment categories and sample point locations. It is valid for 1 year and should be rechecked in the field annually for up to 3 years prior to undertaking soil disturbance activities. After 3 years (2022) a comprehensive *Phytophthora* assessment will be required to inform the Dieback Management Plan to guide activities at this site.

Overall, Dieback Management within Lot 287 should aim to not spread the disease outside of the operational footprint into any adjacent "protectable" vegetation or into offsite areas.

Standard *Phytophthora* management tactics are recommended below to assist with developing a Dieback Management Plan.

5 RECOMMENDATIONS

Dieback Management within Lot 287 should aim to not spread the disease outside of the operational footprint into any adjacent "protectable" vegetation retained or into offsite areas.

- 1. **Train the workforce** about *Phytophthora* Dieback, its impact and management. Green Card training is recommended.
- 2. **Inform personnel** within contracts and inductions that they are entering a site largely Infested with *Phytophthora* Dieback and that precautions need to be taken to ensure that it is not spread from the site or into any retained "Protectable" native vegetation.
- 3. Clearly demarcate any Uninfested area/s to be retained to ensure there are no quarantine breaches.
- 4. **Schedule disturbance activities** ideally in dry-soil conditions to minimise the effort needed to clean-down effectively.
- 5. **Surface water management** Runoff is an efficient means for the spread of Phytophthora Dieback and increases in soil moisture can increase the impact of the pathogen on surrounding native vegetation. Thus, contain runoff from stockpiles so it does not enter sensitive areas.
- 6. Clean-on-exit to avoid depositing Phytophthora infected material along carting routes, vehicles should be cleaned-down free of clods of dirt on the undercarriage and wheel arches prior to exiting the site. Scheduling work to cart materials in dry-soil conditions and informing operators to avoid driving through wet soil areas will reduce the clean-down effort.
- 7. **Separate Uninfested topsoil from Infested topsoil** for insitu use on the area it was sourced from.
- 8. **Rehabilitation** if planting, use resistant plant species from accredited nurseries to increase success of revegetation.
- 9. **Customer notification** advise potential customers that the material is likely to be infested with *Phytophthora* Dieback.
- 10. Maintain secure access to prevent uncontrolled access.
- 11. **Consider having a split phase operation** to isolate loading from excavation, thus reducing the need to clean-down/washdown loading trucks.
- 12. Signage ensure Dieback signage is installed at any Clean-Down access points.

6 REFERENCES

Department of Conservation and Land Management (2001) Phytophthora cinnamomi and disease caused by it. Volume I Management Guidelines

DPaW (2015) Forest and Ecosystem Management Division 2015. Phytophthora Dieback Interpreter's manual for lands managed by the department, DPaW, Perth, WA.


DWG (no date). Management of Phytophthora Dieback in Extractive Industries.

DWG (2000). Managing Phytophthora Dieback - Guidelines for Local Government.

Havel, J.J. (1975) Site Vegetation Mapping in the Northern Jarrah Forest (Darling Range). 2. Location and Mapping of Site-Vegetation Types.

Keighery, B. J. 1994. Bushland Plant Survey: A guide to plant community survey for the community. Wildflower Society of WA Inc.







Assessment Area

Dieback Occurrence

— Lot 287

Excluded

Sample Locations

Infested Uninfested

Negative

A Positive (P. cinnamomi)

Area (ha)
0.986
15.0038
30.0943
46.0841

Interpretation Completed: September 2019

Map Expiry: September 2020



Project Location

Phytophthora Dieback Occurrence Lot 287 Gwindinup


Datum: GDA 1994 Projection: MGA Zone 50

Scale: 1:3,500

Date: 23/10/2019 Prepared: K. Jennings

Figure 1

Figure Record: B2019_Gwindinup.Dieback.Assessment_Fig1_RevA



Site Photographs Lot 287 (November 2019)

Appendix B

ONTACT DETAILS of ame BARK Environme hone No.0400 208 583	ental		GDA (1) GDA 94	D.E. Rec	Type (Ple C. (C) oup (R) ate (P)	Alcoa (A) FPC Other	Date receive	SE ONLY d 17-5	S 1 1 2 1
VHS Identification Number (VHS USE ONLY)	Sample Date	Sample label (Give location, eg. Forest Block or Shire, etc. and sample number)	Plant species sampled	Site Impact (2)	Zone 50 or 51	Map Reference (3)	Land Tenure (4)	RESULT s/s root (5)	RESULT bait (5)
VHS 39496	12.5.19	S1 - Lot 287 SW Hwy	X. preissii	L	50	E 382937 N 6290522	Р		NEG
VHS 39497	12.5.19	S2 - Lot 287 SW Hwy	B. grandis	M	50	E 382789 N 6290748	P		NEG
VHS 39498	12.5.19	S3 - Lot 287 SW Hwy	X. gracilis	L	50	E 383296 N 6290665	P		CIN
VHS 39499	12.5.19	S4 - Lot 287 SW Hwy	X. preissii	L	50	E 383371 N 6290311	Р		CIN
Site impact - Low, Moder An MGA map reference of Land Tenure - State Ford Result codes used - CIN PM = P. megasperma, P. lease Note: a). NEG results of	rate, or High with prefixes est (SF), Na I = Phytoph N = P. nicol cannot be us	rences are supplied in the GDA 94 so (as in the Dieback Interpreter's Mass must be supplied for all samples. Intional Park (NP), Reserve (R), West thora cinnamomi, MUL = P. multivortianae, CON = P. constricts, NEG = sed to represent a total absence of Physiults & invoice to barkenv@c	nual). trail (W), Private (P), Grav a, CRY = P. crypfogea, Pl negative, SUB = subcultu rtophthora in the sampled a	el Pit (GP) = P. inund red for furth rea. b). Info	, or other, (P. arenaria, ELO = P. elon	gata, THE = P		

Sample Data Sheet

APPENDIX 11: REHABILITATION AND DECOMMISSIONING PROGRAMME



Lot 287 South Western Highway, Gwindinup

REHABILITATION AND DECOMMISSIONING **PROGRAMME**

PREPARED FOR:

MARIO MICHELE GIACCI

MARCH 2024

PREPARED BY:

Martinick Bosch Sell Pty Ltd
4 Cook Street
West Perth WA 6005
Ph: (08) 9226 3166
Email: info@mbsenvironmental.com.au

Web: <u>www.mbsenvironmental.com.au</u>





LOT 287 SOUTH WESTERN HIGHWAY, GWINDINUP REHABILITATION AND DECOMMISSIONING PROGRAMME

Distribution List:

Company	Contact name	Copies	Date
MGM Bulk	Craig Carbone Sales and Business Development	Electronic	11 March 2024

Document Control for Job Number: MGM287EXT

Document Status	Prepared By	Authorised By	Date
Draft Report	Kirsi Kauhanen	Kristy Sell	28 April 2021
Final Report	Kirsi Kauhanen	Kristy Sell	30 April 2021
Final Rev1 Report	Kirsi Kauhanen	Kristy Sell	20 April 2022
Draft Rev 2	Emily Cranstoun	Kirsi Kauhanen	9 March 2024
Final Rev 2	Emily Cranstoun, Sharon Rose	Kirsi Kauhanen	11 March 2024

Disclaimer, Confidentiality and Copyright Statement

This report is copyright. Ownership of the copyright remains with Martinick Bosch Sell Pty Ltd (MBS Environmental).

This report has been prepared for **Mario Michele Giacci** on the basis of instructions and information provided by **Mario Michele Giacci** and therefore may be subject to qualifications which are not expressed.

No other person other than those authorised in the distribution list may use or rely on this report without confirmation in writing from MBS Environmental and **Mario Michele Giacci**. MBS Environmental has no liability to any other person who acts or relies upon any information contained in this report without confirmation.

This report has been checked and released for transmittal to Mario Michele Giacci.

These Technical Reports:

- Enjoy copyright protection and the copyright vests in Martinick Bosch Sell Pty Ltd (MBS Environmental) and Mario Michele Giacci unless otherwise agreed in writing.
- May not be reproduced or transmitted in any form or by any means whatsoever to any person without the written permission of the Copyright holder.



TABLE OF CONTENTS

1.	INTRODUCTION	1
2.	Objectives	2
3.	Background	7
3.1	SITE LOCATION	7
3.2	ZONING AND LAND USE	7
3.3	Extraction works	7
4.	ENVIRONMENTAL CONTEXT	10
4.1	LANDFORM AND SOIL	10
4.2	CONTOURS AND SITE STABILITY	10
4.3	Hydrology	12
4.3.1	Groundwater	12
4.3.2	Surface Water	
4.4	Vegetation	
4.4.1	Bioregional Context	
4.4.2	Vegetation Complexes	
4.4.3	Vegetation Associations	
4.4.4	Site Specific	
4.5	DIEBACK AND OTHER PATHOGENS	
4.6	Fauna	
4.6.1	Fauna Habitats	
4.6.2	Significant Fauna	
4.6.3	Herbivores	
4.7	CLIMATE	
4.7.1	Existing Climate	
4.7.2	Regional Climate Change	
5.	REHABILITATION RISK ASSESSMENT	21
6.	IMPLEMENTATION STRATEGY	22
6.1	REHABILITATION ZONES	22
6.2	APPROACH AND STAGING	22
6.2.1	Within Extraction Area	22
6.2.2	Outside Extraction Area	22
7.	ADVANCED PLANNING AND MANAGEMENT	24
7.1	BLUE GUM REMOVAL	24
7.2	VEGETATION RETENTION AND CLEARING	24
7.3	TOPSOIL MANAGEMENT AND EARTHWORKS	24
7.4	EROSION AND SEDIMENT CONTROL	25
7.5	MULCH SUPPLY	25
7.6	SPECIES SELECTION AND PLANT ALLOCATION	25
7.7	PROVENANCE SEED COLLECTION AND SUPPLY	25
7.8	SEEDLING PROPAGATION	26
7.9	DIEBACK MANAGEMENT	26
7.10	Access	26
7.11	FIRE MANAGEMENT	26
7.12	SIGNAGE	26
7.13	FENCING	27
8.	REVEGETATION IMPLEMENTATION METHODOLOGY	28



8.1	DECOMMISSIONING	28
8.2	Earthworks	28
8.3	Topsoil Respread	28
8.3.1	Zone 1: Extraction Area to Pasture	28
8.3.2	Zone 2: Extraction Area to Native Vegetation	28
8.3.3	Zone 3: Plantation to Native Vegetation	
8.3.4	Zone 4: Native Vegetation Improvement	
8.4	EROSION MANAGEMENT	
8.5	DEEP RIPPING AND SCARIFICATION	29
8.5.1	Zone 1: Extraction Area to Pasture	29
8.5.2	Zone 2: Extraction Area to Native Vegetation	
8.5.3	Zone 3: Plantation to Native Vegetation	
8.5.4	Zone 4: Native Vegetation Improvement	
8.6	HABITAT LOGS	
8.7	Mulching	29
8.8	WEED MANAGEMENT	29
8.8.1	Zone 1: Extraction Area to Pasture	
8.8.2	Zone 2: Extraction Area to Native Vegetation	30
8.8.3	Zone 3: Plantation to Native Vegetation	
8.8.4	Zone 4: Native Vegetation Improvement	
8.8.5	General	
8.9	Direct Seeding	31
8.9.1	Zone 1: Extraction Area to Pasture	31
8.9.2	Zone 2: Extraction Area to Native Vegetation	31
8.9.3	Zone 3: Plantation to Native Vegetation	31
8.9.4	Zone 4: Native Vegetation Improvement	
8.10	SEEDLING PLANTING	32
8.11	SCHEDULE OF WORKS	32
9.	POST INSTALLATION MANAGEMENT	34
9.1	Monitoring	34
9.1.1	Zone 1: Extraction Area to Pasture	34
9.1.2	Zone 2: Extraction Area to Native Vegetation	34
9.1.3	Zone 3: Plantation to Native Vegetation	35
9.1.4	Zone 4: Native Vegetation Improvement	35
9.2	Maintenance	35
9.3	COMPLETION CRITERIA	
9.3.1	Zone 1: Extraction Area to Pasture	36
9.3.2	Zone 2: Extraction Area to Native Vegetation	36
9.3.3	Zone 3: Plantation to Native Vegetation	37
9.3.4	Zone 4: Native Vegetation Improvement	38
10.	RECORD KEEPING, AUDITING, AND REPORTING	39
10.1	RECORD KEEPING	39
10.2	REPORTING AND AUDITING	39
11.	References	40
	Tables	
Table 1:	Groundwater Levels on Lot 287	12
Table 1:	Groundwater Levels on Lot 393	
Table 3:	Vegetation Complexes	13



Table 4:	Fauna Habitat Types on Lot 287	19
Table 5:	Indicative Rehabilitation Schedule of Works	33
Table 6:	Monitoring Data Requirements for Native Revegetation	35
Table 7:	Completion Criteria - Zone 1	36
Table 8:	Completion Criteria - Zone 2	36
Table 9:	Completion Criteria - Zone 3	37
	FIGURES	
Figure 1:	Location	3
Figure 2:	Existing Contours and Features	4
Figure 3:	Works and Excavation Plan	5
Figure 4:	Finished Development Plan	6
Figure 5:	Land Use	9
Figure 6:	Landform and Soils	11
Figure 7:	Vegetation Complexes and Associations	15
Figure 8:	Vegetation Types	16
Figure 9:	Vegetation Condition	17
Figure 10:	Dieback Status	18
Figure 11:	Climate Statistics (1900–2023) for Donnybrook (BoM Station 9534)	20
Figure 12:	Rehabilitation Zones	23

APPENDICES

Appendix 1: Risk Assessment and Management

Appendix 2: Indicative Species List



1. Introduction

Mario Michele Giacci, the owner of Lot 287 (Plan 100056), is proposing to expand the existing sand and gravel extraction operations on the property, located in Gwindinup within the Shire of Capel (Figure 1). This Rehabilitation and Decommissioning Programme has been prepared to address requirements of the Shire of Capel and is submitted as an appendix of the application for a Development Approval (DA) and an Extractive Industry Licence (EIL).

The proposed extraction area (Figure 2, Figure 3) includes a previously approved western part of the pit covering 17.27 ha that is in the process of being rehabilitated, and an extension area of 15.31 ha. The proposed extraction area totals 32.58 ha. The proposed extension area involves clearing of 9.70 ha of native vegetation whereas the rest of the extraction area was historically cleared for rural purposes, most recently containing blue gums. Gradual post-extraction rehabilitation is proposed to establish 3.14 ha of native vegetation within the extraction area and convert further 15.57 ha of blue gums on the property to native vegetation. Also, 9.31 ha of existing remnant native vegetation on Lot 287 is proposed to be retained and improved. It is noted that the proposed vegetation clearing and rehabilitation areas may change as part of the Department of Water and Environmental Regulation (DWER) Clearing Permit application process.

This Rehabilitation and Decommissioning Programme has been prepared to address requirements of the Shire of Capel Extractive Industry Local Law 2016 and Local Planning Policy 6.2, and it should be read in conjunction with the DA/EIL application report and related plans. This 2024 Rehabilitation and Decommissioning Programme replaces all previous versions submitted to Shire of Capel. This document covers both pasture rehabilitation and native revegetation, however the details on native revegetation are indicative at this stage - these details will be further refined as part of the DWER Clearing Permit application process.





2. OBJECTIVES


The objectives of rehabilitation and decommissioning on Lot 287 are following:


- Establish stable and safe landform post-extraction.
- Remove temporary infrastructure, rubbish and debris.
- Establish a mixture of pasture and native vegetation (Figure 4) that will maintain the rural character of the property but also mitigate for the impacts of native vegetation clearing.











3. BACKGROUND

3.1 SITE LOCATION

Lot 287 (Plan 100056) South Western Highway, Gwindinup (the property) is located within the Shire of Capel, approximately 4.5 km south of Boyanup (Figure 1). The property covers total area of 60.01 ha. Access to the site is gained off Lowrie Road via an easement on adjacent Lot 393, which is also owned by the applicant.

3.2 Zoning and Land use

Lot 287 is zoned 'Rural' under the Shire of Capel Local Planning Scheme (LPS) No.8 and intercepts three Special Control Areas (SCA):

- SCA4 Transport Corridors.
- SCA6 Strategic Minerals and Basic Raw Materials.
- SCA8 Regional Ecological Linkages.

SCA4 is associated with the South Western Highway and covers approximately 40 m wide strip along the eastern property boundary. SCA4 is well outside the extraction area. SCA6 is associated with mineral sand deposit further to the west and Lot 287 intersects the buffer zone to the deposit. SCA8 is associated with ecological linkages running along the Preston River and the Whicher Scarp (see Molloy *et al.* 2009). Lot 287 is not on the axis line but in close vicinity to it and contributes to the local connectivity.

The property has been historically largely cleared of native vegetation (Landgate 2024). Blue gums were planted across most of the property and these have been gradually harvested ahead of the extractive operations. Some patches and isolated individuals of native vegetation remain, as described in Section 4.4.4.

The land surrounding Lot 287 is zoned either 'Rural', 'State Forest', 'Regional Open Space', or 'Primary Regional Road' (Shire of Capel 2023). They include land uses of basic raw material extraction, livestock grazing, remnant bushland, state forest, and residential dwellings. The adjacent private properties contain a mixture of pastures and native vegetation. There is an extractive site on adjacent Lot 393 to the west of Lot 287 and a finished mineral sands mine further west of this. There are three reserves adjacent to the property (Figure 5):

- Reserve 2307 (Lot 477) "Landscape Protection" (to the north).
- Reserve 25500 (Lot 31) "Landscape Protection" (to the north).
- Reserve 18237 (Lot 478) "Landscape Protection" (to the south).

3.3 EXTRACTION WORKS

The proposed extraction area (also referred to as the site) covers 32.58 ha, including the previously approved pit (17.27 ha) and an extension of the pit to the east (15.31 ha) (Figure 2). The proposed extraction operations are summarised as follows:

- Remove vegetation, including remaining native vegetation.
- Remove topsoil, litter, and any present overburden, and stockpile these.
- Extract sand and gravel material in stages in accordance with the Works and Excavation Plan (Figure 3).
- Crush and screen gravel with a mobile crusher.
- Transport sand and gravel off site.
- Form final batters to maximum 1:6 (vertical:horizontal) (pit floor approximately 1:10) in accordance with the Final Development Plan (Figure 4).




REHABILITATION AND DECOMMISSIONING PROGRAMME

• Rip pit floor, replace topsoil and any other overburden, and revegetate with mixture of pasture and native vegetation (Figure 4).

Once excavation of sand and gravel has been completed, the stage will be rehabilitated to pasture or native vegetation as excavation moves forward. Native revegetation works outside the extraction area will also progress gradually in stages to be defined later. At this stage total revegetation to pasture within the extraction area will be 29.46 ha, with 18.71 ha of native revegetation on the property, and 9.31 ha of native vegetation retained and improved.





4. ENVIRONMENTAL CONTEXT

4.1 LANDFORM AND SOIL

Three soil and landform mapping systems are present within and surrounding the proposed extraction area (Department of Primary Industries and Regional Development (DPIRD) 2022; DPIRD-064) (Figure 6):

- Whicher Scarp System: Low scarp and raised platform, on the northern edge of the Donnybrook Sunkland. Sandy gravel and pale deep sands, loamy gravel, and non-saline wet soils. Jarrah-marri forest and woodland.
- Goodwood Valleys System: Valleys, of the Donnybrook Sunkland. Sandy gravel, loamy gravel, and deep sand. Jarrah-marri forest and woodland.
- Blackwood Plateau System: Lateritic plateau in the Donnybrook Sunkland. Sandy gravel, loamy gravel, and deep sand. Jarrah-marri forest.

The majority of the proposed expansion to the extraction area and all of the proposed native revegetation area are located within the Goodwood Valleys System. Extraction on the property so far has shown that there is a layer of sand, of varying depth (mostly 0.3 m to 1.5 m thick), that overlies the gravel. The gravel layer is typically 1 m to 1.5 m thick but extends deeper in some areas. Material with increasing clay content is present under the gravel.

Lot 287 is located away from wetlands and waterways on well-draining soils, making the risk of acid sulfate soils (ASS) low.

4.2 CONTOURS AND SITE STABILITY


The highest point on Lot 287 is situated approximately halfway along the southern property boundary and has an elevation of 111 m Australian Height Datum (AHD) (Figure 6). From this point, the land to the west and north slopes and undulates downward at gradients between approximately 1:10 and 1:20 slopes. Near the northern boundary there are steep areas of approximately a 1:6 slope. To the east of the proposed extraction area lies the steepest gradients on the property, which slope towards the South Western Highway at gradients up to 1:6 within the proposed extraction area and up to 1:4 further east, beyond the proposed EIL area. Natural landform within the proposed extraction area on Lot 287 ranges from 109 mAHD in the south to 67 mAHD in the northwest. The eastern part of the property down to approximately 52 to 55 mAHD along the South Western Highway.

Batters within the extraction area will be formed to a maximum slope of 1:6 (vertical to horizontal). As shown in Figure 4, the maximum 1:6 batters are expected to be present along parts of the southern and eastern boundaries of the extraction area. Post-extraction gradients in the majority of the pit will be gently sloping (1:10), which is similar to pre-extraction landform. The establishment of pasture and native vegetation will stabilise these slopes for the long term.

Landform and soil profile outside the extraction area will remain as it. As the existing blue gum plantation has achieved stabilisation of the slopes, including the steepest natural 1:4 slopes, it is expected that native revegetation following removal of the blue gums will also stabilise the slopes over time.

Measures to minimise the risk of erosion and reduced soil stability are incorporated into the extraction and rehabilitation works. These are described in Section 7 and Section 8.





4.3 HYDROLOGY

4.3.1 Groundwater

Two piezometers were installed on Lot 287 in September 2012, and their locations are shown in Figure 2. Readings taken on 20 September 2012 are shown in Table 1. The results show that groundwater is approximately 7.8 m from the surface. Groundwater level data is also available from two piezometers on adjacent Lot 393 from October to December 2016 (Table 2). This data supports the results from Lot 287 and further also indicates that depth to groundwater increases as moving up the hill. The extractive operations on the site since 2013 have not intersected the groundwater table.

The lowest point of excavation on Lot 287 is the stormwater retention pond (at 65 mAHD) in the northwestern part of the property (Figure 4). This pond will remain approximately 2 m above maximum groundwater levels. Landform in the rest of the extraction area will be higher than the pond and depth to maximum groundwater will be more than 2 m.

Piezometer	Ground Level (AHD)	Groundwater Depth From Natural Ground Level	Groundwater Level (AHD)
А	68.20m	7.85m	60.35m
В	70.90m	7.84m	63.06m

Table 1: Groundwater Levels on Lot 287

Table 2: Groundwater Levels on Lot 393

Piezometer	Ground Level (AHD)	Groundwater Depth from Natural Ground Level	Groundwater Level (AHD)	Sampling Date
		More than 8.8 m as bore dry	Bore dry at 85.50 m	18 Oct 2016
1 (southeast)	94.30 m	More than 8.8 m as bore dry	Bore dry at 85.50 m	2 Nov 2016
		More than 8.8 m as bore dry	Bore dry at 85.50 m	14 Dec 2016
		5.25 m	40.55 m	18 Oct 2016
2 (northwest)	45.80 m	5.35 m	40.45 m	2 Nov 2016
		5.74 m	40.06 m	14 Dec 2016

4.3.2 Surface Water

The extraction area is mostly situated at the eastern edge of the catchment of Gynudup Brook, a tributary of the Capel River, which discharges into the Indian Ocean at Geographe Bay. A small area (approximately 2.3 ha) at the eastern limit of the extraction area is within the Preston River catchment and drains east toward the Preston River, approximately 800 m away. The eastern parts of the property outside the extraction area also drain east towards Preston River.

There are no watercourses on Lot 287 due to the well-draining soil and lack of upstream catchment area. Surface flow is only likely to occur during intense or prolonged rainfall events. Any surface flow leaving the extraction areas



of Lot 287 does so across the western boundary into Lot 393 Lowrie Road, with the exception of the 2.3 ha in the Preston River catchment. Lot 393 is also owned by the applicant and is being used for extraction of gravel and sand in conjunction with operations on Lot 287 under a separate EIL. Management of stormwater runoff for these two sites has been combined and is described further in a separate Stormwater Management Plan (MBS Environmental 2024b).

4.4 **VEGETATION**

4.4.1 Bioregional Context

The project area is located within the Jarrah Forest Bioregion classified by the Interim Biogeographic Regionalisation for Australia (IBRA) and described as a duricrusted plateau of Yilgarn Craton characterised by Jarrah-Marri forest on laterite gravels and, in the eastern part, by Marri-wandoo woodlands on clayey soils (Thackway and Cresswell 1995).

The Jarrah Forest Bioregion is divided into two subregions, Jarrah Forest 1 (JF1 – Northern Jarrah Forest) and Jarrah Forest 2 (JF2 – Southern Jarrah Forest), of which the proposed extraction area is located within JF2 subregion. This subregion is comprised of eluvial and alluvial deposits that support *Agonis* shrublands. In areas of Mesozoic sediments, Jarrah forests occur in a mosaic with a variety of species-rich shrublands (CALM 2003). The primary land use associated with this subregion includes grazing (improved pastures) and dry land agriculture, forestry, (both native and plantations), irrigated horticulture, mining, rural residential, easements, and conservation (CALM 2003).

4.4.2 Vegetation Complexes

Three broadscale vegetation complexes have been mapped across Lot 287 (Table 3, Figure 7) (DBCA 2018; DBCA-047).

Complex	Subregion of the South West Forests	Broad landform	Description
Kingia	Blackwood Plateau and Plain	Uplands	Open forest of <i>Eucalyptus marginata</i> subsp. <i>Marginata</i> - <i>Corymbia calophylla</i> - <i>Allocasuarina fraseriana</i> - <i>Banksia grandis</i> - <i>Xylomelum occidentale</i> on lateritic uplands in perhumid and humid zones.
Rosa	Blackwood Plateau and Plain	Valleys	Woodland to open forest of <i>Corymbia calophylla - Eucalyptus marginata</i> subsp. <i>Marginata - Xylomelum occidentale</i> on slopes and tall shrubland of <i>Agonis linearifolia</i> in valley floors in the humid zone.
Whicher Scarp (290)	Whicher Scarp	Uplands	Open forest of Eucalyptus marginata subsp. Marginata - Corymbia calophylla on escarpment with some Corymbia haematoxylon, Banksia attenuata, and Xylomelum occidentale in the humid zone.

Table 3: Vegetation Complexes

4.4.3 Vegetation Associations

Three native vegetation associations have been mapped across Lot 287 including associations 1017, 1181, and 1182 (Figure 7) (DPIRD 2019; DPIRD-006). Vegetation association 1017 is broadly described as 'Medium open



woodland; jarrah and marri, with low woodland; banksia', association 1181 as Medium woodland, jarrah, and *Eucalyptus haematoxylon* (Whicher Range), and association 1182 is described as Jarrah, marri, and wandoo.

4.4.4 Site Specific

Lot 287 contains a mosaic of remnant native vegetation, blue gum plantation, extraction operation, and some cleared land. There is approximately 19 ha of native vegetation remaining within Lot 287. A Reconnaissance Survey was undertaken of Lot 287 in November 2018 by Daniel Marsh Botanical Consulting (2019).

4.4.4.1 Flora Assemblage

A total of 55 native vascular plant taxa representative of 47 plant genera and 29 plant families were recorded within Lot 287 (Daniel Marsh Botanical Consulting 2019). The majority of the taxa recorded were representative of the Myrtaceae (7 taxa), Proteaceae (5 taxa) and Hemerocallidaceae (4 taxa) families.

An additional seven species recorded within Lot 287 were introduced species. None of these introduced taxa are listed as a Declared Pest under the *Biosecurity and Agriculture Management Act 2007* (BAM Act; WA Gov 2023).

4.4.4.2 Vegetation Types

The vegetation survey (Daniel Marsh Botanical Consulting 2019) identified three native vegetation types and an introduced vegetation type in the proposed extraction area (Figure 8):

- VT1: Tall woodland of *Eucalyptus marginata* and *Corymbia calophylla* over low woodland of *Banksia grandis* over tall sparse shrubland of *Kunzea glabrescens* over low sparse shrubland of *Xanthorrhoea preissii*.
- VT2: Tall woodland of *Eucalyptus marginata* and *Corymbia calophylla* over tall sparse shrubland of *Kunzea glabrescens* over low sparse shrubland of *Xanthorrhoea preissii* and *Xanthorrhoea gracilis*.
- VT3: Tall woodland of *Eucalyptus marginata* and *Corymbia calophylla* over low sparse shrubland of *Xanthorrhoea preissii* and *Hibbertia hypericoides*.
- D: Disturbed: Blue gum plantations, tracks, and clearings.

No Threatened or Priority Ecological Communities or Threatened or Priority flora species have been recorded at Lot 287.

4.4.4.3 Vegetation Condition


The native vegetation communities vary in condition from Degraded to Very Good – Good (using condition scale by Keighery 1994) (Figure 9) and show signs of multiple historical disturbances including selective logging, fire, weeds, and *Phytophthora cinnamomi* (dieback) (Daniel Marsh Botanical Consulting 2019). Currently there is disturbance in the form of cleared tracks and small bare areas among native vegetation. The blue gum plantation and previously approved extraction areas have been completely cleared of native vegetation in the past.


4.5 DIEBACK AND OTHER PATHOGENS


The majority of the native vegetation on Lot 287 is dieback infested (15 ha) with just under 1 ha uninfested (Bark Environmental 2020). The remainder of the native vegetation, the blue gum plantation areas and cleared areas are mapped as 'excluded' due to the lack of indicator species to determine the occurrence of dieback; however, the presence of dieback in these areas cannot be ruled out. Mapping of the dieback status of Site 287 is presented in Figure 10. The areas of bushland surrounding Lot 287 are considered dieback infested with moderate confidence based on publicly available dieback mapping (Project Dieback 2024).

A Weed and Dieback Management Plan (MBS 2024c) has been prepared for the proposed extractive operations and these measures will apply to rehabilitation and decommissioning as well.












Figure 10: Dieback Status



4.6 FAUNA

4.6.1 Fauna Habitats

Zoologist Greg Harewood was engaged to conduct a fauna assessment for Lot 287 (Harewood 2019). This assessment identified four fauna habitat types that are summarised in Table 4.

Table 4: Fauna Habitat Types on Lot 287

Unit	Fauna Habitat Description	Total Area
VT1	Tall woodland of jarrah (<i>Eucalyptus marginata</i>) and marri (<i>Corymbia calophylla</i>) over low woodlands of <i>Banksia grandis</i> over tall sparse shrubland of <i>Kunzea glabrescens</i> over low sparse shrubland of <i>Xanthorrhoea preissii</i> .	0.79 ha (1.7%)
VT2	Tall woodland of jarrah (<i>E. marginata</i>) and marri (<i>C. calophylla</i>) over tall sparse shrubland of <i>Kunzea glabrescens</i> over low sparse shrubland of <i>Xanthorrhoea preissii</i> and <i>Xanthorrhoea gracilis</i> .	0.84 ha (1.4%)
VT3	Tall woodland of jarrah (<i>E. marginata</i>) and marri (<i>C. calophylla</i>) over tall sparse shrubland of <i>Kunzea glabrescens</i> over low sparse shrubland of <i>Xanthorrhoea preissii</i> and <i>Hibbertia hypericoides</i> .	17.39 ha (28.6%)
D	Disturbed: Blue gum plantations, tracks and clearings	40.98 ha (68.3%)

4.6.2 Significant Fauna

During the fauna assessment (Harewood 2019), the following conservation significant fauna species were recorded within the proposed clearing area:

- Forest Red-tailed Black Cockatoo (Calyptorhynchus banksii naso) Vulnerable under the Biodiversity Conservation Act 2016 (BC Act) and Environment Protection and Biodiversity Conservation Act 1999 (EPBC Act).
- Baudin's Cockatoo (Calyptorhynchus baudinii) Endangered under the BC Act and EPBC Act.
- Western Ringtail Possum (Pseudocheirus occidentalis) Critically Endangered under the BC Act and EPBC Act.

Other significant fauna species may utilise Lot 287 based on habitat available although no evidence of them was recorded during the assessment. For further information, please see Harewood (2019).

4.6.3 Herbivores

Herbivores, including both native species (e.g. kangaroos) and introduced species, particularly rabbits, have the potential to severely compromise rehabilitation success by grazing on native seedlings and germinants. Both kangaroos and rabbits are known to occur on Lot 287 and the surrounding areas. Being a 'Rural' zoned area, there is also potential for the presence of cows, sheep, and other grazing livestock on surrounding properties. To limit grazing impacts on rehabilitation, fencing and other grazing controls will be utilised where appropriate.

4.7 CLIMATE

4.7.1 Existing Climate

The climate of the project area is Mediterranean, with cool wet winters and hot dry summers. Bureau of Meteorology (BoM) Long-term average climate data for the closest meteorological station (Donnybrook, 9 km southeast of the



property) is shown below in Figure 11. The average annual rainfall is 970.4 mm, mean minimum temperatures between 5 and 15°C and mean maximum temperatures between 16 and 31°C (BoM 2024).




Figure 11: Climate Statistics (1900–2023) for Donnybrook (BoM Station 9534)

4.7.2 Regional Climate Change

Climate change modelling undertaken by Commonwealth Scientific and Industrial Research Organisation (CSIRO) and BoM, places Lot 287 within the South-Western Flatlands West (SWFW) cluster (WA Gov 2021). Key findings for this cluster regarding climate change to date and predictions for future change (high confidence) included following:

- Mean temperatures have increased by about 1.1 °C since 1910, with the rate of warming higher since 1960.
- Mean, maximum and minimum temperatures are projected to continue to rise.
- The temperature and frequency of very hot days is expected to increase, and heatwaves will get longer and more intense.
- The number of days with frost risk will decrease.
- The South West has experienced a marked drying trend since 1970, particularly in autumn and early winter.
- Further decreases in annual, winter and spring rainfall are projected with high confidence. By 2030 under all emission scenarios, winter rainfall is projected to decrease by up to 15 per cent. However, the intensity of heavy rainfall events will likely increase.
- Under all emission scenarios, the time spent in drought is projected to increase.
- Drier and hotter conditions will lead to decreases in soil moisture and runoff because of increased water loss from plants and soils (evapotranspiration).
- There is high confidence that climate change will result in a harsher fire weather climate in the future.
- Mean sea level will continue to rise, as will height of extreme sea level events. The oceans are also becoming warmer and more acidic in the future.



5. REHABILITATION RISK ASSESSMENT

A risk assessment has been undertaken for factors that may adversely impact upon rehabilitation success, particularly native revegetation. The risk assessment can be found in Appendix 1. The determination of risks is based on the risk rating system outlined in the Environmental Management Plan Guidelines (DoE 2014).

A number of activities were assessed as having 'high' risk prior to mitigation, which indicated an undesirable level of risk to achieving rehabilitation objectives. Following mitigation and management measures proposed within this programme, all risks were downgraded to either 'Medium' or 'Low'.

The rehabilitation risks that were considered are listed below:

- Weeds.
- Dieback.
- Erosion.
- Fire.
- Grazing.
- Poor soil moisture.
- Insufficient mulch.
- Availability of local seeds/cuttings.
- Seed/Seedling quality.
- Unauthorised access.
- Climate change.

The management of these risks has been incorporated into the proposed rehabilitation methodology (see Section 7 and Section 8).



6. IMPLEMENTATION STRATEGY

6.1 REHABILITATION ZONES

Four main rehabilitation zones are proposed for Lot 287:

- Zone 1: Extraction area to pasture, total of 29.46 ha.
- Zone 2: Extraction area to native vegetation, total of 3.14 ha.
- Zone 3: Plantation to native vegetation (outside extraction area), total of 15.57 ha.
- Zone 4: Native vegetation improvement (outside extraction area), total of 9.31 ha.

6.2 Approach and Staging


6.2.1 Within Extraction Area

Rehabilitation works within the extraction area (Zone 1 and Zone 2) will be gradual and follow the extraction stages (Figure 3). The timing of completion of each stage will depend on market demand for the resource and therefore cannot be predicted accurately in advance. Extraction of Stages 1 to 11 (previously approved area) has now been completed and rehabilitation of these areas is underway. In the extension area, extraction will commence in Stage 12 and continue through to Stage 21.

6.2.2 Outside Extraction Area

The rehabilitation works outside the extraction area (Zone 3 and Zone 4) will also be undertaken gradually but are not dependent on the pace of extraction. The works on Zone 3 and Zone can commence as soon as the proposed extraction has been approved (local government and other approvals) and progress on an annual basis. The approach and staging of rehabilitation works in Zone 3 and Zone 4 will further defined as part of environmental approvals processed.





7. ADVANCED PLANNING AND MANAGEMENT

7.1 Blue Gum Removal

The remaining blue gums within the proposed extraction area will be harvested prior to extraction (Zone 1 and Zone 2). The stumps and excess litter will be removed by pushing into windrows and burning. Burnt vegetative matter will be spread over the native revegetation areas, which will provide accessible carbon for seedlings.

The blue gums outside of the extraction area (Zone 3) are proposed to be cleared gradually (staging to be confirmed), to maximise the following benefits:

- Maintain site erosion control and slope stability.
- Maintain visual screening of the extractive operations from the neighbouring properties and the South Western Highway.
- Opportunities for site specific learnings from previous rehabilitation works.

Within the previously approved extraction area on Lot 287 and Lot 393, blue gum removal has involved removal of all stumps. All stumps will continue to be removed within the proposed extraction area. In the native revegetation areas outside the extraction area, particularly the steeper eastern slopes, it may be beneficial to retain at least some blue gum stumps to maximise slope stability. Retaining stumps has drawbacks (e.g. access issues) that may adversely influence the success of revegetation, and therefore it is proposed that trials will be undertaken at the start of the revegetation works to determine the most beneficial approach to stumps.

7.2 VEGETATION RETENTION AND CLEARING

Clearing of native vegetation within the extraction area (Zone 1 and Zone 2) will be subject to conditions set in a Clearing Permit (yet to be determined). At this stage, the clearing is expected to occur as follows:

- Clearing areas will be marked in the field to avoid over-clearing.
- Clearing will be undertaken gradually, one stage at a time ahead of extraction.
- Experienced fauna handler will be present during clearing to inspect the vegetation to be cleared and relocate fauna as necessary.
- Clearing of will be undertaken with a bulldozer.
- Some of the cleared vegetation (e.g. selected trunks, branches, brush) will be stockpiled for use in rehabilitation.
- Suitable cleared vegetation will be mulched for use in rehabilitation. If stockpiling of mulch is required, it shall be kept free of weeds.
- Some plants to be cleared may be transplanted into the native revegetation areas.

7.3 TOPSOIL MANAGEMENT AND EARTHWORKS

The following earthworks and soil management will be undertaken within the extraction areas (Zone 1 and Zone 2):

- Removal of topsoil (approximately 100 mm thick) and remaining litter will proceed in stages ahead of extraction. The topsoil/litter mix will be removed using appropriate machinery and will be stored in windrows to a maximum height of 4 m.
 - Topsoil from native vegetation areas will be stockpiled separately from topsoil from other areas.



- Observations will be made of the weed load of topsoil prior to its removal and during the stockpiling period. Heavily weed infested topsoil will be suitable for respread only in the pasture rehabilitation areas.
- Sand and gravel extraction will proceed in accordance with the DA/EIL report.
- Dust generation from topsoil and other stockpiles (wind erosion) will be minimised as necessary with a water truck (spraying water).
- As each stage of extraction is completed, the permanent landform contours will be established in accordance
 with the latest approved Finished Development Plan. Batter slopes will be maximum 1:6 with the remainder
 of the pit with gentle gradients of approximately 1:10. The final contours shall be achieved and confirmed by
 way of digital survey.
- Ripping will be undertaken along contour lines to promote root penetration and runoff infiltration.
- To further manage runoff, increase infiltration and reduce sediment movement post mining, contour banks will be constructed along the final landform contour at 100 m intervals.
- The stockpiled topsoil/litter mix will be replaced across the rehabilitation area.

In the areas outside the extraction area (Zone 3 and Zone 4), the natural landform and soil profile will be retained.

7.4 Erosion and Sediment Control

Rip lines and contour banks will 'baffle' runoff within the extraction area, providing infiltration and minimising erosion. Catchment runoff from the pit area will flow to the attenuation basins, where sediment will settle out and some infiltration will occur. Further details on runoff management and sediment control as part of the extractive operations is provided in the Stormwater Management Plan (MBS 2024b). Water trucks will be used as necessary to control wind generated dust and minimise dust impacts on surrounding bushland and residents (see Dust Management Plan for further details, MBS 2024a).

7.5 Mulch Supply

As described in Section 7.2, some of the native vegetation to be cleared will be mulched. Should there be insufficient quantities of site mulch for use in the rehabilitation works, mulch will be imported to site. Imported mulch must either have originated from a dieback free area of similar vegetation type or composted for a period of three to six months to neutralise pathogens and weeds. Mulch is to be between 10 - 50 mm in diameter.

7.6 Species Selection and Plant Allocation

The species selected for native revegetation on Lot 287 will be based on species recorded on Lot 287 and species known on occur in similar habitats in the local area. Species selection will focus on easy to propagate species and dieback resistant species that will provide the highest likelihood of success in achieving completion criteria. An indicative species list is provided as Appendix 2. Plant allocation within the site will be based on soil suitability, hydrological properties, and landscape features.

7.7 Provenance Seed Collection and Supply

Provenance seed and cutting collection is scheduled generally over the spring and summer periods (but can vary for different species), occurring over a number of years, as the seeds of different species mature at different times and depending on the progress of staged extraction and rehabilitation.



Seed and cuttings shall be collected from onsite and within 50 km of the site, where possible. In situations where provenance seed and cuttings cannot be sourced, material will be sourced from other local areas, or alternative species with provenance seed may be considered.

Prior to clearing of native vegetation on site, seed and plant material will be collected to supplement the rehabilitation process. Transplanting of species such as *Xanthorrhoea* sp. will be undertaken where possible.

7.8 SEEDLING PROPAGATION

All seedlings shall be sourced from NIASA certified nurseries, with preference to local nurseries, where possible. Tubestock will be grown from provenance seed, where possible and will either be grown in forestry tubes or deep cells (50 mm square by 120 mm deep) to ensure appropriate root development.

All containers must be sterilised prior to any soil material being placed in them to avoid the introduction or spread of soil borne pathogens. Only suitably mature tube stock with well developed roots, 10 to 15 cm high foliage that has been hardened off and is of a generally good health condition, is accepted.

Seedling orders are typically due around October/November the year preceding the planting works. However, some harder to source species and larger quantities of seedlings will require longer lead times.

7.9 DIEBACK MANAGEMENT

Dieback management measures applicable to the extractive operations are detailed in the Weed and Dieback Management Plan (MBS 2024c) that is part of the DA/EIL application package, and these measures apply to rehabilitation and decommissioning as well. As the property has been confirmed to be largely dieback infected, the native revegetation works will focus on establishing flora species that are dieback resistant. Dieback susceptible species will be included in the species mixture as well but the likelihood of survival of these species is expected to be lower. The implications of dieback for re-establishing native vegetation will be also be addressed as part of the Clearing Permit approval process.

7.10 Access

Access to Lot 287 will be maintained off Lowrie Road through Lot 393. The property is fenced and the access track has a gate to prevent unauthorised access. Internal tracks will be established within the extraction area to facilitate extraction and subsequent rehabilitation. Outside the extraction area, internal tracks will also be established to facilitate rehabilitation.

7.11 FIRE MANAGEMENT

Fire breaks will be maintained along property boundaries as per Shire of Capel guidance. The internal tracks for extraction and rehabilitation purposes can also be used for firefighting access if necessary.

7.12 SIGNAGE

Signage will be placed at the entry gate into Lots 287 and 393 advising of the extractive operations. Signs warning of excavation will also be placed along the property boundary. Signs and/or physical barriers will be placed at the interface where rehabilitation areas immediately abut active works areas and access tracks to clearly delineate that personnel are entering a rehabilitation zone.

The area that was assessed as dieback free (Bark Environmental 2020) will be sign posted and delineated in the field. Access to this area will require clean down and instructions regarding this will also be posted. Any dieback



free topsoil will be stockpiled separately and signposted, and returned to the area it came from, and no topsoil from other parts of the property will be brought into the dieback free area.

Signage will be used to differentiate topsoil stockpiles from native vegetation areas versus other areas. The native vegetation areas to be retained will be delineated and sign posted when clearing blue gum plantation. Additional signage may be posted if considered necessary.

7.13 FENCING

Due to kangaroo and rabbit populations in the local area, fencing is considered necessary to minimise grazing impact, particularly on native revegetation. Fencing to minimise grazing would be at least 1,500 mm high, composed of ring lock and would include a rabbit proof mesh skirting. In order to allow native ground dwelling fauna to continue to move across the property, it is not desirable to apply kangaroo and rabbit fencing to the entire property boundary. Rather it is proposed that sections of the native revegetation would be fenced gradually, leaving 'unfenced' corridors for fauna movement. A one way kangaroo gate will be installed within each fenced area to facilitate safe exit for any kangaroos that may have jumped in.



8. Revegetation Implementation Methodology

8.1 DECOMMISSIONING

As part of decommissioning, any temporary site infrastructure (e.g. portable toilets) and waste/debris will be removed.

8.2 EARTHWORKS

Upon completion of an extraction stage, rehabilitation works will commence by finalising the landform. The pit batters will be formed no steeper than 1:6 slope, with the rest of the pit landform sloping gently at approximately 1:10.

8.3 TOPSOIL RESPREAD

8.3.1 Zone 1: Extraction Area to Pasture

Topsoil that was stockpiled prior to extraction will be respread across the pasture rehabilitation area to a depth of no greater than 100 mm.

8.3.2 Zone 2: Extraction Area to Native Vegetation

Topsoil and mulch that were stockpiled prior to extraction will be respread across the native revegetation area to a depth of no greater than 100 mm. Only topsoil from native clearing areas will be respread in Zone 2. Heavily weed infested topsoil will not be spread in native revegetation areas as this has potential to compromise revegetation success and additional mulch may be required instead.

8.3.3 Zone 3: Plantation to Native Vegetation

Not applicable - topsoil will remain in situ.

8.3.4 Zone 4: Native Vegetation Improvement

Not applicable - topsoil will remain in situ.

8.4 Erosion Management

The risk of erosion will be managed as follows:

- Gradual extraction followed by gradual rehabilitation to minimise the bare area open to the elements.
- Implementation of the Dust Management Plan (MBS 2024a).
- Implementation of the Stormwater Management Plan (MBS 2024b).
- Gradual conversion from blue gums to native vegetation (outside the extraction area) with trials to determine whether some blue gum stumps should be retained for stability.
- Any ripping, mounting or similar will occur along contour to maximise infiltration of rainfall.
- Monitoring will be undertaken for early detection of erosion and mitigation measures and additional management measures will be implemented as necessary if erosion is observed.



8.5 DEEP RIPPING AND SCARIFICATION

Ripping promotes root penetration and runoff infiltration, increasing revegetation success and reducing the risk of erosion. Ripping depth and rip line separation distances will vary, depending on the historic land use and rehabilitation objectives, as detailed below. In addition to deep ripping, scarification or other ways of creating micro depressions (e.g. tracking) will be implemented in areas where native seeding will be undertaken on slopes to assist with seed retention.

8.5.1 Zone 1: Extraction Area to Pasture

In the pasture rehabilitation areas, ripping will be undertaken along contour lines to 300 mm to 500 mm with 1 to 2 m centres between lines.

8.5.2 Zone 2: Extraction Area to Native Vegetation

In native revegetation areas, ripping will be undertaken along contour lines to a minimum of 600 mm deep with approximately 1 m centres between lines. Scarification or other ways of creating micro depressions (e.g. tracking) will be implemented in areas where native seeding will be undertaken.

8.5.3 Zone 3: Plantation to Native Vegetation

Ripping in Zone 3 will be dependent on whether, and to what degree, blue gum stumps will be retained as retaining stumps will limit access by machinery and ability to rip. Augering can be used an alternative method in areas where ripping is not feasible.

8.5.4 Zone 4: Native Vegetation Improvement

No ripping is proposed in these areas. Planting will be undertaken with a hand auger.

8.6 HABITAT LOGS

Select plant matter, such as larger branches and or tree trunks may be salvaged from the clearing areas and be transferred to the native revegetation areas to create microhabitats and assist with topsoil retention.

8.7 Mulching

Vegetation will be cleared in stages and mulched for respread. As far as practicable, mulching will be undertaken during or immediately after vegetation clearing and spread directly to a native revegetation area, to a depth of no greater than 25 mm. The mulch will act not only as carbon for soil microbial activity, but may also provide a source of native seed, and will assist in dust suppression and erosion control. If mulch is brought to site from elsewhere, it must meet Australian Standards AS4454-2012) (CS-037 2012), in an effort to manage weed seed, pathogens, and diseases.

8.8 WEED MANAGEMENT

The Weed and Dieback Management (MBS 2024c) prepared for the extractive operations will apply for rehabilitation and decommissioning as well, however rehabilitation will also involve additional weed control measures. Weed control will be required across the rehabilitation areas to manage weeds during the establishment of pasture and native species.



8.8.1 Zone 1: Extraction Area to Pasture

In the pasture rehabilitation areas, weed management will aim to control weeds that could outcompete the desired pasture species and will also aim to eradicate declared pest plants, weeds of national significance and priority weeds of concern for the region.

Where necessary, weeds will be controlled prior to the seeding of pasture with a broad-spectrum or a selective herbicide. Fluazifop may be used as a grass specific herbicide and Metsulfuron-methyl for geophytes.

Manual removal and spot spraying with glyphosate or a selective herbicide will also be undertaken as necessary after seed germination and plant establishment to support the achievement of the completion criteria.

8.8.2 Zone 2: Extraction Area to Native Vegetation

As the re-spread topsoil and mulch is expected to provide a source of native seed but will also include some weed seed, weed control in Zone 2 will need to be tailored to support the establishment of natives while minimising weeds. It is proposed that an adaptive management approach is undertaken in Zone 2 comprising inspections prior to control to determine the best weed control approach. Broad spectrum, selective herbicides and/or manual removal will continue to be applied as necessary until the completion criteria have been met.

8.8.3 Zone 3: Plantation to Native Vegetation

Weed control in Zone 3 will aim to minimise weeds prior to commencement of native revegetation. Weed control will be undertaken prior to and after the removal of blue gums, and after any ground disturbance (e.g. stump removal or ripping) and ahead of seeding/planting. Planting and/or seeding should be delayed until weeds are under control to avoid weeds from compromising native revegetation. Weed control will be tailored to the specific site requirements that will vary over time and will include broad spectrum, selective herbicides and/or manual removal. Weed control will continue as necessary until the completion criteria have been met.

8.8.4 Zone 4: Native Vegetation Improvement

Weed control in Zone 4 will aim to reduce weed load in the retained native vegetation areas and eradicate any declared pest plants, weeds of national significance and priority weeds of concern (if any present). Care will be taken to ensure that weed control does not adversely affect the native vegetation already present.

8.8.5 General

Herbicides will be selected based on the target species, the receiving environment and potential sensitivities or constraints that may be present. Selective herbicide application will be favoured to reduce the likelihood of off-target damage to remnant native vegetation. Herbicide will be applied from a boom spray unit where accessible and hand sprayed in harder to access areas and in areas adjacent to sensitive receivers such as native vegetation. Manual removal of weeds will also be considered where appropriate.

Herbicides proposed for used on site include but are not limited to:

- Glyphosate Biactive broadleaf and grasses.
- Fluazifop grass specific.
- Metsulfuron methyl geophytes such as arum lily.

Areas to be planted with seedlings will ideally be sprayed the winter before planting with a residual (e.g. Simazine) and knockdown (e.g. Glyphosate + Metsulfuron Methyl) herbicide mix. Simazine would typically be sprayed at 2.4 kg/ha, Roundup UltraMax (540) at a minimum 2+ litres/ha and Metsulfuron Methyl at 7 grams/ha, with the carrier 100 litres of water per hectare. If weeds are forming seed pods and the herbicide application will not kill the weeds



before this seed sets then slashing may be considered. The following year the same mix will be sprayed again during May/early June before planting (timing may vary with seasonal conditions).

Control of weeds will be undertaken in accordance with the *Agriculture and Related Resources Protection Act 1976*, BAM Act, guidance from the Department of Primary Industries and Regional Development and under industry best practise for control. Records will be kept of all herbicide applications undertaken on site.

8.9 DIRECT SEEDING

Direct seeding is proposed in Lot 287 for both pasture and native revegetation.

8.9.1 Zone 1: Extraction Area to Pasture

Revegetation to pasture will proceed in stages in areas that have been ripped and contoured:

- The site will be allowed to wet up with autumn rains before fertiliser is applied at 200 kg per hectare of NPK
 + Trace Elements.
- A pasture species mix will then be direct seeded into the topsoil by appropriate machinery. This will include a mix of annual grasses, clovers and other species suitable to sand over gravel/clay soils. Seeding will only take place once sufficient rains have fallen to allow for successful germination.
- Pasture seed will be sown at a rate of 25 kg of seed per hectare.

8.9.2 Zone 2: Extraction Area to Native Vegetation

Direct seeding of suitable native species will be undertaken in areas where micro depressions have been created through scarification, tracking or other means. The species mix with be selected based on position in the landscape, provenance seed availability and species with the highest probability of successfully establishing from seed.

Seed will be pretreated with a mycorrhizal bio-stimulant and will be hand broadcast at a rate of 4 kg per ha. Hand broadcasting is expected to be the most suitable method for the site considering the site topography and confidence in achieving adequate coverage.

Germination rates and survival of germinants can vary significantly depending on a wide range of environmental, site and climate factors. Anticipated death rates of germinants are estimated to range from 50-70% in the year following seeding, 20-30% in the second year and 10-20% in the third year.

Native everlastings may be broadcast at a rate of 5 kg per ha on batters or steep slopes, to control erosion and weeds whilst native germinants establish. Everlasting will reduce in abundance over time as other native species mature and increase in height.

Direct seeding should be programmed to April-June while soil temperatures are still warm, as close to as possible to the break of autumn rains.

8.9.3 Zone 3: Plantation to Native Vegetation

Methods described for direct seeding in Zone 2 above will also apply to Zone 3.

8.9.4 Zone 4: Native Vegetation Improvement

No direct seeding is expected to be undertaken in Zone 4, but rather seedlings will be planted to infill and improve existing vegetation.



8.10 SEEDLING PLANTING

Planting of seedlings will be undertaken in Zones 2, 3, and 4. Planting works may use different methodologies, depending on landscape conditions, stage of rehabilitation and site constraints or sensitivities. Where possible it is preferential that planting of seedlings is undertaken along rip lines. Alternatively, seedlings may need to be planted with a hand auger and this is expected to occur under the following circumstances:

- In Zone 4, where existing native vegetation is present.
- In areas where remnant native vegetation or blue gum stumps prevent access of machinery to complete rip lines.
- If topography of the site makes machinery access unsafe.
- During subsequent infill planting.

Each tubestock/ cell will be planted with a single 10 g native fertiliser tablet (excluding proteaceous species). The use of initiator insecticide tables will also be trialled for eucalyptus seedlings.

In Zones 2 and 3, the initial seedling planting density is expected to be one plant per 10 m², supporting the proposed seeding rate of 4 kg/ha. Infill planting will be undertaken in Zones 2 and 3 as required in alignment with completion criteria. Infill planting will be undertaken in Zone 4 to supplement existing native vegetation and the rate for this will be determined as part of the Clearing Permit application process.

8.11 SCHEDULE OF WORKS

The extraction staging plan is shown in Figure 3, with extraction in maximum 2 ha stages, however as noted earlier the rate of extraction is dependent on dependent on demand for the resource. Typically, one or two stages would be expected to be extracted in a year. Rehabilitation works in Zones 3 and 4 will also be gradual but is not dependent on the progress of extraction. Staging for Zones 3 and 4 will be developed as part of the Clearing Permit application process.


Indicative scheduling for rehabilitation works is presented in Table 5. The table presents a typical schedule for the rehabilitation actions required, subsequent to the surface preparation works. It should be noted that best efforts will be made to ensure that seedling orders are made for the next planting season if completion of extraction within a stage is projected to be completed with sufficient time to implement preparatory works for winter planting the following year.



REHABILITATION AND DECOMMISSIONING PROGRAMME

Table 5: Indicative Rehabilitation Schedule of Works

		Yea	ar O			Υe	ear 1			Ye	ear 2			Ye	ear 3	
Aspect	Spring	Summer	Autumn	Winter												
Initial weed control																
Seed collection																
Seedling order																
Site preparation																
Direct seeding																
Seedling planting																
Follow up weed control																
Monitoring and reporting																
Infill planting																



Note: Following implementation of this revegetation schedule, seasonal weed control, bi-annual monitoring and reporting and potentially other maintenance actions will be required until completion criteria have been met.



9. POST INSTALLATION MANAGEMENT

Regular monitoring, maintenance and review of methodologies is key to ensuring success of the rehabilitation program. Post installation management is specified below.

9.1 MONITORING

Each rehabilitation stage will be monitored on a biannual basis (Spring and Autumn) for a two-year period after installation. Following the two-year period, monitoring will drop down to an annual basis (in Spring) until the completion criteria have been met and maintained for two years. Monthly inspections of the fencing infrastructure will be undertaken, as this is critical for rehabilitation success and monitoring will be followed by maintenance as necessary.

9.1.1 Zone 1: Extraction Area to Pasture

One permanent monitoring points per hectare will be established in the pasture rehabilitation areas. Monitoring of pasture sites will capture the following information:

- Observations of pasture establishment vigour, resilience, % coverage.
- Soil issues evident from areas lacking growth vigour.
- Erosion damage.
- Weed presence.

Photographs will be taken of the monitoring points during each monitoring event. Additional opportunistic monitoring will be undertaken while traversing between the monitoring points. Opportunistic ad hoc monitoring will also be undertaken as part of the operations so that any emerging issues can be addressed as promptly as possible and completion criteria achieved.

9.1.2 Zone 2: Extraction Area to Native Vegetation

A mixture of permanent and random quadrats (minimum one per hectare of each) will be established in Zone 2. The permanent quadrats will also act as photo monitoring points. The quadrats will be 10 m by 10 m in size and will also include a smaller nested quadrat for germinants. Photographs will be taken of the quadrats during each monitoring event to provide a direct visual capture of rehabilitation progress. In addition to quadrat based data collection, opportunistic visual observations will also be recorded during each monitoring event. The data to be collected in each monitoring event is summarised in Table 6.



Table 6: Monitoring Data Requirements for Native Revegetation

Quantitative Data	Qualitative Data
 Density of native vegetation (stems per m²). Native species present (species richness). 	Observed health of native vegetation.Observed health of weeds.
 Native foliage cover (%). Maximum heigh of each native species present. Native vegetation structure. Weed species present. 	 Grazing and pest activity. Evidence of disease (e.g. dieback, Marri canker). Soil moisture observations. Native fauna observations.
 Total weed foliage cover (%). Vegetation condition (Keighery 1994). 	 Soil movement/ erosion signs. Notes on surrounds (e.g. whether the quadrat is representative of surrounds). Photographs of quadrats and photo points. Opportunistic observations.

Ad hoc visual observations and site inspections will also be undertaken opportunistically during day-to-day activities and site meetings, to ensure any emerging issues can be addressed promptly.

9.1.3 Zone 3: Plantation to Native Vegetation

Methods described for monitoring in Zone 2 above will also apply to Zone 3.

9.1.4 Zone 4: Native Vegetation Improvement

Monitoring in Zone 4 will target the effectiveness of the improvement actions and will continue until the completion criteria have been achieved and maintained for two years. Monitoring in Zone 4 will be further defined as part of the Clearing Permit application process with DWER but at this stage is expected to include:

- Monitoring of effectiveness of weed control.
- Monitoring the success of infill plantings.
- Monitoring of trends in native species diversity and cover following fencing.

9.2 MAINTENANCE

Ongoing maintenance will be undertaken in response to findings of the monitoring events and any opportunistic observations whilst on site. Maintenance activities will include, but are not limited to:

- Weed control.
- Infill planting or reseeding native vegetation in areas where completion criteria are projected to not be met. Reseeding will be limited to areas where appropriate soil preparation can be undertaken; elsewhere infill planting will be used.
- Reseeding of pasture.
- Fence repairs.
- Disease and pest control.
- Repairs to erosion damage and implementation of any additional erosion control measures.
- Application of fertilisers and soil improvers.



9.3 COMPLETION CRITERIA

9.3.1 Zone 1: Extraction Area to Pasture

Completion criteria for Zone 1 pasture rehabilitation are presented in Table 7. The completion criteria for pasture rehabilitation are expected to be achieved within two years of a particular stage undergoing pasture seeding, however if this is not the case, then rehabilitation works will continue until the completion criteria have been achieved. As the extraction and rehabilitation works are staged, the completion criteria will be achieved gradually across the site.

Table 7: Completion Criteria - Zone 1

Aspect	Completion Criteria
Landform	Final landform is in accordance with an approved post-extraction plan.
Pasture cover	Pasture cover is sufficient to stabilise soil.
Significant Weeds	No declared pest plants or Weeds of National Significance present.
Bare Ground	No bare patches of ground more than 30 m ² in size.

9.3.2 Zone 2: Extraction Area to Native Vegetation

Indicative completion criteria for Zone 2 native revegetation are presented in Table 8. These are expected to be further refined during the Clearing Permit application process with DWER.

Table 8: Completion Criteria - Zone 2

Aspect	Completion Criteria	Intermediate Targets	Assessment Methodology
Landform	Maximum batter slopes no steeper than 1:6.	Gradual establishment of final landform in accordance with Finished Development Plan in areas where extraction has been finished.	Site survey
Soil profile	All rehabilitated areas contain at least 50 mm of topsoil (either from clearing areas or constructed from subsoil and mulch):	Gradual spreading of topsoil across areas where landform has been finalised.	Earthwork logs, rehabilitation monitoring.
Site stability	Slopes are stable.	Slope stability issues are being captured in monitoring and mitigated.	Rehabilitation monitoring.
Rehabilitation extent	All of Zone 2 has been revegetated.	Gradual revegetation of areas where extraction has been finished.	Rehabilitation monitoring.
Vegetation - Species composition	Minimum 10 native species per quadrat.	 First year - 80% of species planted / seeded represented. Second year - 70% of species planted / seeded represented. 	Rehabilitation monitoring.



Aspect	Completion Criteria	Intermediate Targets	Assessment Methodology
Vegetation - Density	Minimum 5,000 stems per ha including: • ≥750 upper storey stems per hectare. • ≥4,250 other strata stems per hectare.	 First year Minimum 1,100 stems per ha of upper storey species. Minimum 5,500 stems per ha of other strata species. Second year Minimum 900 stems per hectare of upper storey species. Minimum 4,750 stems per ha of other strata species. 	Rehabilitation monitoring.
Vegetation - Condition	Vegetation is self-sustaining.	Threats to self-sustaining vegetation are identified and mitigated.	Rehabilitation monitoring.
Weed Management	≤20% weed cover with no declared weeds present.	Weed control has been undertaken and weeds are not outcompeting revegetation.	Rehabilitation monitoring.

9.3.3 Zone 3: Plantation to Native Vegetation

Indicative completion criteria for Zone 3 native revegetation are presented in Table 9.

Table 9: Completion Criteria - Zone 3

Aspect	Completion Criteria	Intermediate Targets	Assessment Methodology
Site stability	Slopes are stable.	Slope stability issues are being captured in monitoring and mitigated.	Rehabilitation monitoring.
Rehabilitation extent	All of Zone 3 has been revegetated.	Gradual revegetation of areas where extraction has been finished.	Rehabilitation monitoring.
Vegetation - Species composition	Minimum 10 native species per quadrat.	 First year - 80% of species planted / seeded represented. Second year - 70% of species planted / seeded represented. 	Rehabilitation monitoring.
Vegetation - Density	Minimum 5,000 stems per ha including: • ≥750 upper storey stems per hectare. • ≥4,250 other strata stems per hectare.	 First year Minimum 1,100 stems per ha of upper storey species. Minimum 5,500 stems per ha of other strata species. Second year Minimum 900 stems per hectare of upper storey species. Minimum 4,750 stems per ha of other strata species. 	Rehabilitation monitoring.
Vegetation - Condition	Vegetation is self-sustaining.	Threats to self-sustaining vegetation are identified and mitigated.	Rehabilitation monitoring.



Aspect	Completion Criteria	Intermediate Targets	Assessment Methodology
Weed Management	≤20% weed cover with no declared weeds present.	Weed control has been undertaken and weeds are not outcompeting revegetation.	Rehabilitation monitoring.

9.3.4 Zone 4: Native Vegetation Improvement

Completion criteria for the improvement of existing native vegetation in Zone 4 will be defined as part of the Clearing Permit application process with DWER. At this stage it is expected that the completion criteria for Zone 4 will specify measurable targets for:

- Reduction in weeds.
- Absence of declared weeds.
- Increase in native flora species diversity.
- Increase in native flora species regeneration.



10. RECORD KEEPING, AUDITING, AND REPORTING

10.1 RECORD KEEPING

The applicant is responsible for collecting and maintaining records on the implementation of rehabilitation. This will include, but is not limited to, the following data:

- Date and location of landform finalisation.
- Date and location of preparatory earthworks (e.g. spreading of topsoil and/or mulch, ripping).
- Date and location of revegetation actions (e.g. planting and seeding).
- Date and location of weed control actions.
- Date and location of monitoring, maintenance, and mitigation actions.
- Monitoring reports issued by consultants (e.g. environmental specialist).
- Invoices relating to the implementation of this programme.

10.2 REPORTING AND AUDITING

It is expected that the Shire of Capel will require an annual audit of compliance to be prepared by a suitably qualified independent expert. This audit will cover the conditions of the DA/EIL and also include a progress report on the rehabilitation, including the following:

- Details of completed, ongoing, and future rehabilitation areas.
- Photos of rehabilitation areas.
- Monitoring and reporting details, if available.
- Start and completion dates, and expected start dates, if applicable.
- A map depicting the rehabilitation areas and their completion progress.

An environmental specialist will prepare reports for each of the monitoring surveys detailing findings, progress towards completion criteria, and recommendations for management actions. These reports can be used as evidence for the annual compliance audit.



11. REFERENCES

Australian Government (Aus Gov). 1999. Environment Protection and Biodiversity Conservation Act 1999. Administered by the Department of Climate Change, Energy, the Environment and Water. Accessed February 2024.

https://www.legislation.gov.au/C2004A00485/2014-03-27/text

Bark Environmental. 2020. *Phytophthora Dieback Assessment Report Lot 287 Gwindinup*. Unpublished report for Mario Michele Giacci, February 2020.

Bureau of Meteorology (BOM). 2024. *Climate Statistics for Australian Locations*. Monthly climate statistics for Donnybrook, Station 9534. Accessed March 2024.

http://www.bom.gov.au/climate/averages/tables/cw 009534.shtml

Daniel March Botanical Consulting. 2019. *Desktop Study and Reconnaissance Flora and Vegetation Survey Lot 287 South West Hwy, Gwindinup, WA.* Unpublished report for Mario Michele Giacci, January 2019.

Department of Biodiversity, Conservation and Attractions 2018. Vegetation Complexes - South West forest region of Western Australia (DBCA-047). https://catalogue.data.wa.gov.au/dataset/vegetation-complexes-swf-50k (accessed December 2023).

Department of Conservation and Land Management (CALM). 2003. *A Biodiversity Audit of Western Australia's 53 Biogeographical Subregions in 2002.* Relevant section written by Hearn, R., Williams, K., Comer, S., and Beecham, B. titled *Jarrah Forest 2 (JAF02 – Southern Jarrah Forest Subregion).* https://library.dbca.wa.qov.au/static/FullTextFiles/021927.pdf. Accessed August 2023.

Department of the Environment (DoE). 2014. *Environmental Management Plan Guidelines*. Commonwealth of Australia, Department of Climate Change, Energy, the Environment and Water. Accessed March 2024. https://www.dcceew.gov.au/sites/default/files/documents/environmental-management-plan-quidelines.pdf

Department of Primary Industries and Regional Development (DPIRD). 2019. *Pre-European Vegetation (DPIRD-006)*. Accessed January 2024.

https://catalogue.data.wa.gov.au/dataset/pre-european-dpird-006

Department of Primary Industries and Regional Development (DPIRD). 2022. *Soil Landscape Mapping - Systems (DPIRD-064)*. Accessed March 2024.

https://catalogue.data.wa.gov.au/dataset/soil-landscape-mapping-systems

Government of Western Australia (WA Gov). 2015. *Agriculture and Related Resources Protection Act 1976*. Administered by the Department of Biodiversity, Conservation and Attractions. Accessed March 2024. https://www.legislation.wa.gov.au/legislation/statutes.nsf/main_mrtitle_13_homepage.html

Government of Western Australia (WA Gov). 2016. *Biodiversity Conservation Act 2016*. Administered by the Department of Biodiversity, Conservation and Attractions. Accessed February 2024. https://www.legislation.wa.gov.au/legislation/statutes.nsf/main_mrtitle_13811 homepage.html

Government of Western Australia (WA Gov). 2021. *Western Australian Climate Projections* Summary. Department of Water and Environmental Regulations, Prime House, 8 Davidson Terrace, Joondalup Western Australia. Published September 2021. Accessed March 2024.

https://www.wa.gov.au/system/files/2022-01/Western_Australian_Climate_Projections_Summary.pdf

Government of Western Australia (WA Gov). 2023. *Biosecurity and Agriculture Management Act 2007*. Administered by the Department of Primary Industries and Regional Development. https://www.legislation.wa.gov.au/legislation/statutes.nsf/main_mrtitle_2736 homepage.html



Harewood, G. 2019. Fauna Assessment - Lot 287 South Western Highway Gwindinup. Unpublished report for MGM Bulk.

Keighery, B.J. 1994. *Bushland Plant Survey: A Guide to Plant Community Survey for the Community*. Wildflower Society of WA (Inc). Nedlands, Western Australia. Published September 1994.

Landgate. 2024. *Map Viewer Plus*. Historical aerial photographs of region. Accessed March 2024. https://map-viewer-plus.app.landgate.wa.gov.au/

MBS Environmental (MBS). 2024a. *Dust Management Plan.* Unpublished report prepared for Mario Michele Giacci, March 2024.

MBS Environmental (MBS). 2024b. *Stormwater Management Plan.* Unpublished report prepared for Mario Michele Giacci, March 2024.

MBS Environmental (MBS). 2024c. Weed and Dieback Management Plan. Unpublished report prepared for Mario Michele Giacci, March 2024.

Molloy, S., Wood, J., Hall, S., Wallrodt, S., and Whisson, G. 2009. *South West Regional Ecological Linkages Technical Report.* Western Australian Local Government Association (WALGA) and Department of Environment and Conservation, Perth. Published by WALGA, September 2009. Accessed March 2024.

https://walga.asn.au/getattachment/Policy-Advice-and-

Advocacy/Environment/Biodiversity/SWREL_LowRes.pdf?lang=en-

<u>AU#:~:text=The%20South%20West%20Regional%20Ecological%20Linkages%20project%20is%20a%20partners</u> hip,(%C2%B3the%20SWREL%20project%E4%B8%A5)

Project Dieback. 2024. *Dieback Public Map*. Accessed January 2024. https://dieback.net.au/dieback-public-map/

Shire of Capel. 2023. *Shire of Capel Local Planning Scheme No. 8.* Gazetted on 17 July 2023 by the Department of Planning, Lands and Heritage. Accessed March 2024.

https://www.capel.wa.gov.au/Profiles/capel/Assets/ClientData/Document-

Centre/Planning/Capel Scheme 8 Final 17072023.pdf

Standards Australia Ltd Committee CS-037 (CS-037). 2012. *Australian Standard AS 4454-2012*. Prepared by Committee CS-037 and approved by the Council of Standards Australia, 16 February 2012. https://store.standards.org.au/product/as-4454-2012

Thackway, R., and Cresswell, I.D. 1995. *Regionalisation for Australia: a framework for setting priorities in the national reserves system cooperative program.* Reserve Systems Unit, Australian Nature Conservation Agency, Canberra. Version 4.0 published March 1994. Accessed March 2024.

https://www.dcceew.gov.au/sites/default/files/documents/ibra-framework-setting-priorities-nrs-cooperative-program.pdf



LOT 287 SOUTH WESTERN HIGHWAY, GWINDINUP REHABILITATION AND DECOMMISSIONING PROGRAMME

APPENDICES



LOT 287 SOUTH WESTERN HIGHWAY, GWINDINUP REHABILITATION AND DECOMMISSIONING PROGRAMME

APPENDIX 1: RISK ASSESSMENT AND MANAGEMENT



The risk of potential impacts to native rehabilitation success has been assessed using a qualitative risk assessment methodology to measure the likelihood of the risk occurring and the resulting level of consequence to designate a rating of Low, Medium, High, or Severe (DoE 2014). The designated risk rating assumes that the specified management measures are being implemented.

Table A2-1: Qualitative Measure of Likelihood

Rating	Description
Highly likely	Is expected to occur in most circumstances.
Likely	Will probably occur during the life of the project.
Possible	Might occur during the life of the project.
Unlikely	Could occur but considered unlikely or doubtful.
Rare	May occur in exceptional circumstance.

Table A2-2: Qualitative Measure of Consequences

Rating	Description
Minor	Minor incident of environmental damage that can be reversed.
Moderate	Isolated but substantial instances of environmental damage that could be reversed with intensive efforts.
High	Substantial instances of environmental damage that could be reversed with intensive efforts.
Major	Major loss of environmental amenity and real danger of continuing.
Critical	Severe widespread loss of environmental amenity and irrecoverable environmental damage.

Table A2-3: Risk Rating

	Consequence					
	Minor	Moderate	High	Major	Critical	
Highly Likely	Medium	High	High	Severe	Severe	
Likely	Low	Medium	High	High	Severe	
Possible	Low	Medium	Medium	High	Severe	
Unlikely	Low	Low	Medium	High	High	
Rare	Low	Low	Low	Medium	High	



Risk Factors to Rehabilitation	Risk Rating*	Reasoning	Management/Mitigation
Weeds	Low	Likelihood: likely. Consequence: minor. Weeds can be spread or introduced via wind, vehicle movement, rain runoff, fauna activity (e.g. kangaroos), movement of soil (including rabbit movement and diggings), dust, and introduction of soil/plant matter from external sources. The surrounding properties support a range of rural land uses, including paddocks for grazing and hay production, timber plantations, extraction site, residential dwellings and associated gardens, and bushland. Many of these activities either involve weed species or they pose a risk for introducing and spreading weed species in the local area. Past and current rural activities on Lot 287 also pose a risk of introducing and spreading weed. Considering the local setting, the site history, the post-extraction land use and establishment of pasture through rehabilitation, the occurrence, introduction and spread of weeds are expected to continue. Weeds have potential to outcompete rehabilitation.	 Access to site will be restricted to authorised personnel only. Clean on entry and exit requirements will be established. Weed control will be undertaken as specified in this document. Monitoring will be carried out as specified in this document. Any mulch externally sourced will be weed free. Fencing will be used to restrict access by fauna as described in this document. A Weed and Dieback Management Plan will be implemented.
Dieback	Low	Likelihood: possible. Consequences: low. Dieback is spread through infected soil by fauna movement, surface water runoff, soil movement on sloping surfaces, spores, and human activity. Infected soil can contaminate vehicles, footwear, and equipment. Additionally, the transport of infected soil as import or export material from a site can contribute to dieback spread. Dieback may occur on site already. Historical and current land uses on the property and the surrounding area have potential to introduce and spread dieback and it may also spread via natural means (e.g. kangaroos). Dieback poses a risk to rehabilitation, particularly native revegetation. The rehabilitation works themselves, have potential to spread dieback e.g. through movement of soil, mulch, and seedlings.	 Access to site will be restricted to authorised personnel only. Clean on entry and exit requirements will be established. Seedlings will be sourced from an accredited nursery only. Any externally sourced mulch will be certified dieback free. Fencing will be used to restrict access by fauna as described in this document. A Weed and Dieback Management Plan will be implemented. Active revegetation works will focus on dieback resistant species.



Risk Factors to Rehabilitation	Risk Rating*	Reasoning	Management/Mitigation
Erosion	Low	Likelihood: possible Consequence: minor Wind erosion has potential to occur in the bare ground areas and will be managed through staged clearing and dust management measures. Due to the sloping nature of the site and gravelly soils (clay at depth), there is potential for water erosion, mostly in association with major rainfall events.	 Revegetation will be undertaken in stages and closely following the completion of extraction to ensure soil is stabilised in a timely manner. Mulch and/or other soil stabilisers will be used as described in this document. During operations, water truck will be available to water dust suppression. Ripping will be undertaken along contour to capture any localised runoff and increase retention of moisture (and thus reduce potential for erosion). Contour bunds will be established in extraction area as part of rehabilitation to reduce runoff. Potential retention of blue gum stumps will be trialled along the steeper slopes where plantation will be converted to native vegetation. Monitoring and mitigation will be undertaken for erosion as described in this document. Separate Dust Management Plan will also be implemented for the extraction operations. Separate Stormwater Management Plan will be implemented for the extraction operations.
Fire	Medium	Likelihood: possible. Consequence: moderate. Fire presents a threat to all native vegetation in the local landscape, including revegetation. It is unlikely a fire will be started as a result of operations; however it is considered possible for a fire to occur in the local area over the course of the project and therefore fire could impact the site.	 Weed control will be undertaken as described in this document and in the separate Weed and Dieback Management Plan to reduce weed load and therefore fire risk. Firebreaks will be maintained as required by local government. Access tracks will be maintained across the property to facilitate fire-fighting access.



Risk Factors to Rehabilitation	Risk Rating*	Reasoning	Management/Mitigation
Grazing	Low	Likelihood: unlikely. Consequence: minor. Grazing poses a low risk because of the management measures that will be put in place. Without these management measures, the risk grazing poses would be much higher due to the presence of horses, kangaroos, and rabbits.	 The property is fenced to prevent access by livestock from surrounding properties. Additional fencing will be undertaken to exclude kangaroos and rabbits from native revegetation areas as described in this document.
Poor Soil Moisture (e.g. due to low rainfall, prolonged heatwave)	Low	Likelihood: possible. Consequence: minor. The South West region experiences reasonably predictable seasons, including seasonal rainfall that allows for planning to seeding/planting at opportune times of year. However, sometimes unexpected periods of low rainfall and high temperatures result in poor soil moisture that will reduce germination and seedling survival.	 Ripping of soil pre-seeding/planting. Mulch to help retain soil moisture. Selection of drought tolerant native species suited to the conditions. Using significantly larger than required volume of seed and/or initial seedling numbers to offset losses. Infill seeding/planting as required to meet rehabilitation targets.
Climate Change	Low	Likelihood: possible. Consequence: minor. Whilst climate change is expected to have long-term impacts on all native vegetation, it is not expected to have a significant impact on the proposed rehabilitation over the duration of the works, beyond what is already factored in due to variability in existing climate records.	 Seeding/planting will be undertaken during the winter when temperatures are low and expected rainfall maximised. Only local endemic species will be selected for rehabilitation. Selection of drought tolerant species suited to the conditions. Local provenance stock will be used for rehabilitation to maximise adaptation to local environment.
Insufficient Mulch	Low	Likelihood: possible. Consequence: minor. It is possible that mulch available from site clearing will be insufficient to meet rehabilitation demands on site. Lack of mulch has potential to result in poorer rehabilitation outcomes e.g. through poor soil moisture	 Where possible, mulch will be sourced from onsite vegetation proposed for clearing as described in this document. If necessary, mulch can be brought in as described in this document.



Risk Factors to Rehabilitation	Risk Rating*	Reasoning	Management/Mitigation
Availability of local provenance seed/cuttings/seedlings	Low	Likelihood: unlikely Consequence: minor The availability of local provenance seed, cuttings and seedlings is a concern in the South West as major revegetation projects are underway and stripping supply. However, the remnant native vegetation on the property outside of the proposed extraction area can be used to supply local provenance stock and the property owner also has access to other sites of local provenance.	 Seed/cuttings collected from the property as far as practicable and in accordance with RIAWA guidelines. Additional seed/cuttings sourced from accredited collectors or nursery using local provenance stock (within 50 km).
Seed/Seedling Quality	Low	Likelihood: unlikely Consequence: minor Poor quality seedlings have higher mortality rates and poor quality seed will have lower germination rates.	 Seed will be collected, stored, treated and broadcast by experienced operators. Seedlings will be propagated or provided by an accredited nursery. Seedlings will be propagated from local endemic sources.
Unauthorised Access	Low	Likelihood: unlikely Consequence: minor Unauthorised access has potential to damage the revegetation and introduce weeds and disease.	 The property is fenced and further fencing will be erected around native revegetation areas as described in this document Fence monitoring and mitigation will be undertaken as described in this document.

^{*}Designated risk rating assumes that the specified management measures are being implemented.



LOT 287 SOUTH WESTERN HIGHWAY, GWINDINUP REHABILITATION AND DECOMMISSIONING PROGRAMME

APPENDIX 2: INDICATIVE SPECIES LIST



Species	From	Seed/Seedling/ Cutting/ Transplant
Acacia extensa	Shrub	Seed
Acacia pulchella	Shrub	Seed
Acacia saligna	Shrub	Seed
Adenanthos meisneri	Shrub	Cutting
Agonis flexuosa	Tree	Seed, Seedling
Allocasuarina fraseriana	Tree	Seed, Seedling
Allocasuarina humilis	Shrub	Seed
Banksia attenuata	Tree	Seed, Seedling
Banksia grandis	Tree	Seed, Seedling
Bossiaea eriocarpa	Shrub	Seedling
Bossiaea ornata	Shrub	Seed
Calothamnus quadrifidus	Shrub	Seed
Corymbia calophylla	Tree	Seed, Seedling
Corymbia haematoxylon	Ttree	Seed, Seedling
Eremaea pauciflora	Shrub	Seed, Seedling
Eucalyptus marginata	Tree	Seed, Seedling
Hakea amplexicaulis	Shrub	Seed, Seedling
Hakea lissocarpha	Shrub	Seed, Seedling
Hardenbergia comptoniana	Herb	Seed
Hemiandra pungens	Herb	Cutting
Hibbertia hypericoides	Shrub	Cutting
Hibbertia racemosa	Shrub	Cutting
Hypocalymma angustifolia	Shrub	Seedling
Hypocalymma robustum	Shrub	Seedling
Jacksonia furcellata	Shrub	Seed, Seedling
Kennedia coccinea	Herb	Seed
Kennedia prostrata	Herb	Seed
Kunzea glabrescens	Shrub	Seed
Leschenaultia biloba	Herb	Cutting
Macrozamia riedlei	Shrub	Seed
Melaleuca thymoides	Shrub	Seed, Seedling
Patersonia occidentalis	Herb	Seedling
Patersonia umbrosa	Herb	Seedling
Rhodanthe chlorocephala	Herb	Seed
Stirlingia latifolia	Shrub	Seed
Xanthorrhoea brunonis	Shrub	Seed
Xanthorrhoea gracilis	Shrub	Seed, Transplant
Xanthorrhoea preissii	Shrub	Seed, Transplant
Xylomelum occidentale	Tree	Seedling




11100	N /1. 0	E GIACCI
IVIARI()	IVII(:HFI	F (¬IA(∷(∷

DA AND EIL APPLICATION

APPENDIX 12: EXISTING CONTOUR AND FEATURE PLAN (A1)





APPENDIX 13: FINISHED DEVELOPMENT PLAN (A1)



